



# APPLE RIDGE APARTMENTS

114 ROCHESTER HILL ROAD


PREPARED FOR

D.R. LEMIEUX BUILDERS, INC. ROCHESTER, N.H. 03867 JUNE 22, 2018





OVERALL SITE 1" = 200'



## CIVIL ENGINEERS

NORWAY PLAINS ASSOCIATES, INC. 2 CONTINENTAL BOULEVARD ROCHESTER, NEW HAMPSHIRE 03867 (603) 335-3948

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.

## LANDSCAPING ARCHITECTS

WOODBURN & COMPANY LANDSCAPE ARCHITECTURE, LLC 103 KENT PLACE NEWMARKET, NEW HAMPSHIRE 03857 (603) 659-5949

## ARCHITECTS

LASSEL ARCHITECTS PA 370 MAIN STREET SOUTH BERWICK, ME 03908-370 (207) 384-2049

## OWNER OF RECORD

TAX MAP 134, LOT 5 OWNER OF RECORD: ROCHESTER HILL HOLDINGS, LLC 76 EXETER ROAD NEWMARKET, NH 03857 SCRD BOOK 4452, PAGE 648

## **APPLICANT**

D.R. LEMIEUX BUILDERS, INC. 76 EXETER ROAD NEWMARKET, NH 03857 (603) 292-3555

### NHDES ALTERATION OF TERRAIN: NHDES WETLANDS PERMIT: NHDES SUBDIVISION PERMIT:

NHDES SUBSURFACE SYSTEMS PERMIT: NHDES WASTEWATER PERMIT: NHDOT DRIVEWAY/ENTRANCE PERMIT:

NPDES PERMITS ARE ONLY REQUIRED FOR PROJECTS MEETING THE DISTURBED AREA CRITERIA BELOW AND HAVING A POINT SOURCE STORMWATER DISCHARGE FROM THE SITE TO AN ADJACENT WETLAND OR WATER BODY (I.E. CULVERT, SWALE, ETC. OUTLETING TO A WETLAND, CREEK, STREAM OR RIVER)

NPDES PERMITS CONSIST OF A NOTICE OF INTENT (NOI) FILED WITH THE ENVIRONMENTAL PROTECTION AGENCY AT LEAST 14 DAYS PRIOR TO CONSTRUCTION COMMENCING AND A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) BEING PREPARED, KEPT ON SITE AND FOLLOWED BY THE CONTRACTOR.

FOR STATUS OF THIS PERMIT, CONTACT THE PROJECT GENERAL CONTRACTOR

FINAL APPROVAL BY ROCHESTER PLANNING BOARD


CERTIFIED BY: \_\_\_\_\_ DATE: \_\_\_\_


### PLAN OF LAND SHEET E-1 SHEET C-1 EXISTING FEATURES 1" = 40' 1" = 100'SHEET C-2 SHEET C-2-P1 SITE LAYOUT PLAN SITE LAYOUT PLAN - PHASE 1 ONL' 1" = 40'SHEET C-3 SHEET C-3-P1 GRADING AND DRAINAGE PLAN 1" = 40'GRADING AND DRAINAGE PLAN-PHASE 1 ONL 1" = 40'1" = 20' 1" = 20' DETAILED GRADING AND DRAINAGE PLAN SHEET C-3A-P1 DETAILED GRADING AND DRAINAGE PLAN — PHASE SHEET C-4 1" = 40'EROSION AND SEDIMENTATION CONTROL PLAN SHEET C-4-P1 1" = 40'EROSION AND SEDIMENTATION CONTROL PLAN SHEET C-5-P1 SHEET C-5A UTILITY PLAN - PHASE 1 ONLY 1" = 40' DETAILED UTILITY PLAN 1" = 20'SHEET C-6 PARKING AND SIDEWALK DETAILS AS SHOWN SHEET C-7 CONSTRUCTION DETAILS AS SHOWN SHEET C-8 SHEET C-9 DRAINAGE DETAILS AS SHOWN GRAVEL WETLANDS BASIN DETAILS AS SHOWN TEMPORARY EROSION AND SEDIMENTATION AS SHOWN AS SHOWN PERMANENT EROSION AND SEDIMENTATION CONTROL DETAILS SHEET C-12 UTILITY DETAILS AS SHOWN SHEET C-13 SHEET C-14 SEWER DETAILS AS SHOWN PUMP STATION AND FORCE MAIN DETAILS AS SHOWN SHEET C-15 GUARDRAIL DETAILS AS SHOWN GRAVITY SEWER & FORCE MAIN PROFILE AS SHOWN SHEET C-17 SHEET P-1 FORCE MAIN & OFFSITE GRAVITY SEWER PROFILE AS SHOWN SHEET L-1 SHEET L-2 SITE LANDSCAPING PLAN GRAVEL WETLANDS PLANTING & SEEDING 1" = 30'SHEET L-3 SHEET L-4 1" = 20'FOUNDATION LANDSCAPE PLAN LIGHTING PLAN AND DETAILS 1" = 40'LIGHTING PLAN AND DETAILS - PHASE 1 ONL SHEET DOT-0 1" = 200' AS SHOWN STANDARD LEGEND AND SYMBOLS AS SHOWN OVERALL IMPROVEMENTS PLAN SHEET DOT-4 SHEET DOT-5 EXISTING FEATURES PLAN 1" = 50'1" = 50'ROADWAY IMPROVEMENT PLAN 1" = 50'PAVEMENT MARKING AND SIGNAGE PLAN AS SHOWN DRIVEWAY IMPROVEMENT PLAN AND PROFILE ROADWAY PROFILE AND TYPICAL CROSS SECTIONS AS SHOWN CROSS SECTIONS CROSS SECTIONS CROSS SECTIONS CROSS SECTIONS


SHEET INDEX


PLAN NO. C-2780 DWG. NO. 15225/SP-2


LAND SURVEYORS SEPTIC SYSTEM DESIGNERS CIVIL ENGINEERS TRANSPORTATION PLANNERS <u>LEGEND</u> - PROPERTY LINE ----- LIMITS OF JURISDICTIONAL WETLANDS CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. EXISTING TREE LINE SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE EXISTING STONEWALLS GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS - EXISTING OVERHEAD WIRES ASSOCIATES, INC. (603)-335-3948. EXISTING WETLANDS 06/20/2018 - REVISE OWNER OF RECORD EXISTING UTILITY POLE EXISTING MONUMENT GENERAL SITE PLAN NOTES 1. THIS PARCELS ARE LOCATED IN THE RESIDENTIAL-2 (R2) ZONE. TOTAL PARCEL AREA: 1,078,277 SQUARE FEET OR 24.75 THE PURPOSE OF THIS PLAN IS TO DEPICT THE EXISTING FEATURES ON THE LOT. 4. ALL EXISTING UTILITIES LOCATIONS ARE APPROXIMATE AS SHOWN. THE CONTRACTOR SHALL VERIFY THEIR EXACT LOCATION PRIOR TO ANY WORK BEING PERFORMED. THESE PLANS SHOW ONLY THOSE FEATURES THAT WERE VISUALLY PER REFERANCE PLAN 1. DIMENSIONAL REGULATIONS PER ZONING ORDINANCE: MAP 239 LOT 34
ROCHESTER HILL TRUST % TRUSTEE
% ROBIE PROPERTIES
175 ANDOVER ST
DANVERS, MA 01923 RESIDENTIAL (R2) ZONE: MINIMUM LOT AREA/DWELLING UNIT = 75,000 SF MINIMUM LOT AREA = 30,000 SF MINIMUM LOT FRONTAGE = 100 FEET MINIMUM YARD SETBACKS: FRONT = 15SIDE = 10'REAR = 25'MAXIMUM LOT COVERAGE = 30% MAXIMUM BUILDING HEIGHT = 35' ORIENTATION: HORIZONTAL AND VERTICAL DATUMS - CITY OF N 35°07'03" ROCHESTER GIS. N 37°34'49" E N 37°34'49" E MAP 239 LOT 26 NH NORTHCOAST CORP PO BOX 429 OSSIPEE, NH 03864 475.36 PARCEL IS NOT LOCATED WITHIN ZONE A (100YR FLOOD) 329.79 AS SHOWN ON FEDERAL EMERGENCY MANAGEMENT AGENCY MAP 134 LOT 1 SEVEY, MICHAEL 2 DORA DRIVE ROCHESTER, NH 03867 MAP, COMMUNITY #33017C0212D DATED MAY 17, 2005. VILLANOVA LN. DORA DRIVE /-EDGE OF VERY POORLY DRAIN SOILS BOUNDARY DOSTIE FAMILY
REVOCABLE TRUST
07 ROCHESTER HILL RD
ROCHESTER, NH 03867 MAP 239 LOT 121 WARREN, STEVEN D 7 DORA DR ROCHESTER, NH 03867 MAP 239 LOT 122 LEMIEUX, DAVID R PO BOX 1163 ROCHESTER, NH 03866 MAP 134 LOT 3 JOHNSON, JOSEPH L PO BOX 1701 ROCHESTER, NH 03866 755.56 ┌ EDGE OF JURISDICTIONAL N 35°12'17" E HENRIETTA ST. WETLANDS AS MAP 134 LOT 4 VARNEY,HOLLIS & KAREN 110 ROCHESTER HILL RD ROCHESTER, NH 03867 DELINEATED BY GARY C. FLAHERTY C.W.S., C.S.S. MAP 134 − LOT 5 \* GIS COORDINATES TOTAL PARCEL AREA: 1,078,277 S.F. 24.75 Ac. S 34°59'25" W S 36°43'34" W S 39°03'08" W S 37°45'14" W CITY OF ROCHESTER GIS COORDINATES N:288696 E:1175967 LINE DATA N 52°06'40" W 150.00' L2 N 37°53'20" E *38.66'* L3 N 33°58'59" E 10.00' TAX MAP 134, LOT 5 OWNER OF RECORD: ROCHESTER HILL HOLDINGS, LLC CURVE DATA 76 EXETER ROAD C1 R=25.00' L=39.27'  $\triangle=90^{\circ}00$ '00" NEWMARKET, NH 03857 C2 R=1450.09' L=98.86'  $\Delta=3^{\circ}54$ '22" SCRD BOOK 4552, PAGE 648 PLAN OF LAND TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH PREPARED FOR: D.R. LEMIEUX BUILDERS, INC. OWNER OF RECORD: APPLE RIDGE ESTATES LLC MAY 2016 GRAPHIC SCALE 1)"APPLE RIDGE ROCHESTER HILL ROAD, ROCHESTER NEW HAMPSHIRE" DATED: JANUARY 3, 2005, REV. TO 1-3-2006; BY CIVILWORKS, INC. FILE NO. 104 PLAN NO. C-2780 2)"LOT LINE ADJUSTMENT PLAN LOTS 5 & 6, TAX ASSESSOR'S MAP 134, ROCHESTER HILL ROAD, ROCHESTER, NEW HAMPHIRE, COUNTY OF STRAFFORD". SCALE 1'=100'; DATED: JANUARY 11, 2002, REV. TO 2-11-2002; BY CIVILWORKS, INC. RECORDED S.C.R.D. PLAN 64-76.  $DWG\ NO.\ 15225 \SP-2$ 1 INCH= 100 FT. F.B. NO.INORWAY PLAINS ASSOCIATES, INC. 31 Mooney Street, Alton, N.H. 603-875-3948 2 Continental Blvd., Rochester, N.H. 603-335-3948







































FOOTING 4-FT DEEP (TYP.)





**DUMPSTER PAD DETAIL** NOT TO SCALE


## TYPICAL SOLID VINYL FENCE DUMPSTER ENCLOSURE SCALE: 1/2"=1'

**ELEVATION** 

FINISHED GRADE

——— FOOTING 4-FT DEEP (TYP.)

**SECTION** 



## TYPICAL CHAINLINK FENCE

NOT TO SCALE

## **Typical Gravity Wall** with 41" Blocks Load Condition A Shown (No Backslope - No Surcharge) (4.0° Batter Angle on Wall) Ground Level Installtion to Engage Shear Knobs (Typical) Exposed Height - Free Draining Backfill to Extend at Least 12" Behind Wall - Non-Woven Geotextile Fabric (If Specified) (As Specified by Engineer) Redi-Rock<sup>®</sup>International, LLC

## TYPICAL BLOCK RETAINING WALL DETAIL

### NOT TO SCALE


- DESIGN OF RETAINING WALLS TO BE PROVIDED BY MANUFACTURE AND
- INSTALLED PER THE MANUFACTURES REQUIREMENTS.
  SHOP DRAWINGS SHALL BE SUBMITTED PRIOR TO ORDERING AND APPROVED BY NORWAY PLAINS ASSOCIATES, INC.
- CHAINLINK FENCE SHALL BE INSTALLED ON TOP OF WALL WHERE THE VERTICAL DROP IS GREATER THAN 2 FEET OR AS REQUIRED BY CODES.


# PAVED WALKWAY GALVANIZED STEEL HANDRAIL, PAINTED. PAVED WALKWAY **PROFILE**

## RAIL & STAIR DETAIL

31 Mooney Street, Alton, N.H. 603-875-3948

FILE NO. 104 PLAN NO. C-2780 DWG. NO. 15225/SP-2 F.B. NO.






**BICYCLE RACK DETAIL** NOT TO SCALE

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.

CIVIL ENGINEERS



05/20/2016 - REVISED PLAN PER ROCHESTER TRG COMMENTS


CONSTRUCTION DETAILS TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH

PREPARED FOR: D.R. LEMIEUX BUILDERS, INC.

2 Continental Blvd., Rochester, N.H. 603-335-3948

MAY 2016

C-7



30 | 12' | 7.5'

ANTI-SEEP COLLAR DETAIL


NOT TO SCALE


PLAN NO. C-2780


*F.B. NO*.

DWG. NO. 15225/SP-2

31 Mooney Street, Alton, N.H. 603-875-3948







## PRE-CAST HEADWALL CROSS COUNTRYUNDER PAVEMENT 4" COMPACTED LOAM & SEEDED - ROAD BASE COURSE CLEAN GRANULAR FILL OR SUITABLE MAT. **BLANKET** DRAIN LINE SEE NOTE #1 CRUSHED STONE BEDDING FOR FULL WIDTH OF THE TRENCH UP TO SPRING LINE OF PIPE. 6" BELOW PIPE IN EARTH/12" BELOW PIPE IN UNDISTURBED SEE NOTE #1 (WHICHEVER IS GREATER)

1. PIPES MAY BE INSTALLED BY EXCAVATING AN OPEN TRENCH WITH SIDE SLOPES OF 1:1 MAXIMUM TO A DEPTH OF 4-FT. INTALLATIONS DEEPER THAN 4-FT REQUIRE THE USE OF A TRENCH BOX.

2. PIPE MATERIALS SHALL BE AS SPECIFIED ON THE DESIGN PLAN.

3. SAND BLANKET MAY BE OMITTED FOR REINFORCED CONCRETE PIPE. DRAINAGE PIPE TRENCH INSTALLATION DETAIL


NOT TO SCALE

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WIT IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS

ASSOCIATES, INC. (603)-335-3948.



05/20/2016 - REVISED PLAN PER ROCHESTER TRG COMMENTS 06/12/2018 - REVISED FOUNDATION AND DRIP EDGE DETAIL



## INFILTRATION BASIN CROSS SECTION

1" =20' (HORZ.) & 1" = 2' (VERT.)


## **INFILTRATION BASIN:**

DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO THE INFILTRATION BASIN. DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE

- THE LIMITS OF THE INFILTRATION BASIN. AFTER THE BASIN IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHALL BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING DRAG.
- VEGETATION SHALL BE ESTABLISHED IMMEDIATELY AFTER FINIAL GRADING IS COMPLETED. CONSTRUCT THE INFILTRATION BASIN TO THE GRADES DEPICTED ON THE PLAN AND CROSS-SECTION.
- LOAM AND SEED <u>ONLY</u> THE SLOPES OF THE INFILTRATION BASIN AS PRESCRIBED IN THE "<u>PERMANENT VEGETATION</u>" NOTES FOUND ON <u>SHEET C-11</u>. SEED MIXTURE = A
- DO NOT PLACE INFILTRATION SYSTEMS INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.

INSPECT PRETREATMENT MEASURES (I.E. SEDIMENT FOREBAY(S), HOODED CATCH BASINS, ETC.) AT LEAST TWICE A YEAR AND AFTER EVERY STORM GREATER THAN 2.5 INCHES OF RAIN OVER A 24-HOUR PERIOD.

- INSPECT INFILTRATION SURFACE BI-ANNUALLY. ONCE IN THE SPRING PRIOR TO MAY 15 AND ONCE IN THE FALL PRIOR TO OCTOBER 15. INSPECT INFILTRATION SURFACE AFTER ANY RAINFALL EVENT OF 2.5-INCHES OR GREATER IN A 24-HOUR PERIOD. REMOVE AND DISPOSE OF ACCUMULATED SEDIMENT BASED ON INSPECTION. REPAIR AREA OF REMOVAL AS NECESSARY TO RESTORE INFILTRATION
- PERFORM MAINTENANCE AND REHABILITATION BASED ON INSPECTIONS
- REMOVE DEBRIS (IF ANY) FROM INFILTRATION BASIN INLET BASED ON INSPECTION.
- CONDUCT PERIODIC MOWING OF THE INFILTRATION BASIN SLOPES AND EMBANKMENTS (MINIMUM TWICE A YEAR) TO ELIMINATE WOODY GROWTH FROM THE EMBANKMENTS AND BOTTOM. MOWING THE INFILTRATION BASIN EMBANKMENTS WHEN MOWING THE REST OF THE SITE IS RECOMMENDED. 8. IF THE INFILTRATION SYSTEM DOES NOT DRAIN WITHIN 72-HOURS FOLLOWING A RAINFALL EVENT, THEN A QUALIFIED PROFESSIONAL (I.E. PROFESSIONAL ENGINEER, CERTIFIED SOILS SCIENTIST, ETC.) SHALL ASSESS THE CONDITION OF THE FACILITY TO DETERMINE MEASURES REQUIRED TO RESTORE




## INFILTRATION BASIN #1 **OUTLET STANDPIPE DETAIL**


NOT TO SCALE

DRAINAGE DETAILS TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH PREPARED FOR:

D.R. LEMIEUX BUILDERS, INC. MAY 2016

2 Continental Blvd., Rochester, N.H. 603-335-3948





ALL BLANKET AND MATS SHALL BE INSPECTED WEEKLY DURING THE CONSTRUCTION PERIOD, AND AFTER ANY RAINFALL EVENT EXCEEDING 1/2 INCH IN A 24-HOUR PERIOD. ANY FAILURE SHALL BE REPAIRED IMMEDIATELY. IF WASHOUT OF THE SLOPE, DISPLACEMENT OF THE MAT, OR DAMAGE TO THE MAT OCCURS, THE AFFECTED SLOPE SHALL BE REPAIRED AND RESEEDED, AND THE AFFECTED AREA OF MAT SHALL BE RE-INSTALLED. NSTRUCTION SPECIFICATIONS:

SLOPE INSTALLATION

MANUFACTURE'S INSTALLATION INSTRUCTIONS: PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP's), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.

BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECP'S IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH WITH APPROXIMATELY 12" (30cm) OF RECP'S EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP'S WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF RECP'S BACK OVER SEED AND COMPACTED SOIL. SECURE RECP'S OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) APART ACROSS THE WIDTH OF THE RECP's.

C. ROLL THE RECP'S (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. RECP'S WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP'S MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM STAPLES/STAKES SHALL BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE

D. THE EDGES OF PARALLEL RECP'S MUST BE STAPLED WITH APPROXIMATELY 2" - 5" (5 CM - 12.5 CM) OVERLAP DEPENDING ON RECP's TYPE. CONSECUTIVE RECP'S SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5 CM) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30 CM) APART ACROSS ENTIRE RECP's WIDTH.

NECESSARY TO PROPERLY SECURE THE RECP's.

SITE PREPARATION: PROPER SITE PREPARATION IS ESSENTIAL TO ENSURE COMPLETE CONTACT OF THE PROTECTION MATTING WITH THE SOIL GRADE AND SHAPE AREA IF INSTALLATION. REMOVE ALL ROCKS, CLODS, TRASH, VEGETATIVE OR OTHER OBSTRUCTIONS SO THAT THE INSTALLED BLANKETS WILL HAVE DIRECT CONTACT WITH THE SOIL.


NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE


PREPARE SEEDBED BY LOOSENING 2-3 INCHES OF TOPSOIL ABOVE FINAL GRADE INCORPORATE AMENDMENTS, SUCH AS LIME AND FERTILIZER, INTO SOIL ACCORDING TO SOIL TEST AND THE SEEDING PLAN. A. SEED AREA BEFORE BLANKET INSTALLATION FOR EROSION CONTROL AND REVEGETATION. SEEDING AFTER MAT INSTALLATION IS OFTEN SPECIFIED FOR TURF REINFORCEMENT APPLICATIONS. WHEN SEEDING PRIOR TO BLANKET INSTALLATION, ALL CHECK SLOTS

AND OTHER AREAS DISTURBED DURING INSTALLATION MUST BE RESEEDED. WHEN SOIL FILLING IS SPECIFIED, SEED THE MATTING AND THE ENTIRE DISTURBED AREA AFTER INSTALLATION AND PRIOR TO FILLING THE MAT WITH SOIL.

## **TEMPORARY** EROSION CONTROL BLANKET DETAIL

NOT TO SCALE





### SPACING BETWEEN STONE CHECK DAMS

STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE

CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION, AIR AND WATER POLLUTION WILL BE MINIMIZED.

STRUCTURES SHALL BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS BEEN COMPLETED.

TEMPORARY GRADE STABILIZATION STRUCTURES SHALL BE INSPECTED AFTER EACH STORM AND DAILY DURING PROLONGED STORM EVENTS. ANY DAMAGE TO THE STRUCTURES SHALL BE REPAIRED PARTICULAR ATTENTION SHALL BE GIVEN TO END RUN AND EROSION AT THE DOWNSTREAM TOE OF THE

WHEN REMOVING THE STRUCTURES, THE DISTURBED AREAS SHALL BE BROUGHT UP TO EXISTING CHANNEL

GRADE AND THE AREAS PREPARED, SEEDED AND MULCHED.


. SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURES WHEN IT REACHES 1/2 THE ORIGINAL HEIGHT OF THE STRUCTURE.


STONE CHECK DAM

31 Mooney Street, Alton, N.H. 603-875-3948

FILE NO. 104 PLAN NO. C-2780 DWG. NO. 15225/SP-2 F.B. NO.

**INSTALLATION DETAIL** NOT TO SCALE





CROSS-SECTION MAINTENANCE REQUIREMENTS: FENCES SHALL BE INSPECTED AND MAINTAINED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED

. SEDIMENT DEPOSITION SHALL BE REMOVED, AT A MINIMUM, WHEN DEPOSITION ACCUMULATES TO ONE-HALF THE HEIGHT OF THE FENCE, AND MOVED TO AN APPROPRIATE LOCATION SO THE SEDIMENT IS NOT READILY TRANSPORTED BACK TOWARD THE SILT FENCE. SILT FENCES SHALL BE REPAIRED IMMEDIATELY IF THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THEM. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES OF THE BARRIER, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THEM, SEDIMENT BARRIERS SHALL BE REPLACED WITH A TEMPORARY CHECK DAM. SHALL THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY; THE FABRIC SHALL BE REPLACED PROMPTLY. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO

6. IF THERE IS EVIDENCE OF END FLOW ON PROPERLY INSTALLED BARRIERS, EXTEND BARRIERS UPHILL OR CONSIDER REPLACING THEM WITH OTHER MEASURES, SUCH AS TEMPORARY DIVERSIONS AND SEDIMENT TRAPS. 7. SILT FENCES HAVE A USEFUL LIFE OF ONE SEASON. ON LONGER CONSTRUCTION PROJECTS, SILT FENCE SHALL BE REPAIRED

PERIODICALLY AS REQUIRED TO MAINTAIN EFFECTIVENESS.

FENCES SHALL BE USED IN AREAS WHERE EROSION WILL OCCUR ONLY IN THE FORM OF SHEET EROSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY ABOVE THE FENCE. SEDIMENT BARRIERS SHALL BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE CONTRIBUTING DRAINAGE AREA ABOVE THEM. THE MAXIMUM CONTRIBUTING DRAINAGE AREA ABOVE THE FENCE SHALL BE LESS THAN 1 ACRE PER 100 LINEAR FEET OF FENCE; THE MAXIMUM LENGTH OF SLOPE ABOVE THE FENCE SHALL BE 100 FEET; THE MAXIMUM SLOPE ABOVE THE FENCE SHALL BE 2:1;

FENCES SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSELY AS POSSIBLE, AND

RAINFALLS:

THE EXISTING GRADE PREPARED AND SEEDED.

THE ENDS OF THE FENCE SHALL BE FLARED UPSLOPE; B. THE FABRIC SHALL BE EMBEDDED A MINIMUM OF 4 INCHES IN DEPTH AND INCHES IN WIDTH IN A TRENCH EXCAVATED INTO THE GROUND, OR IF SITE CONDITIONS INCLUDE FROZEN GROUND, LEDGE, OR THE PRESENCE OF HEAVY ROOTS, THE BASE OF THE FABRIC SHALL BE EMBEDDED WITH A MINIMUM THICKNESS OF 8 INCHES OF 3/4-INCH STONE; THE SOIL SHALL BE COMPACTED OVER THE EMBEDDED FABRIC;

D. SUPPORT POSTS SHALL BE SIZED AND ANCHORED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS WITH MAXIMUM POST SPACING OF 6 FEET: ADJOINING SECTIONS OF THE FENCE SHALL BE OVERLAPPED BY A MINIMUM OF 6 INCHES (24 INCHES IS PREFERRED), FOLDED

AND STAPLED TO A SUPPORT POST. IF METAL POSTS ARE USED, FABRIC SHALL BE WIRE-TIED DIRECTLY TO THE POSTS WITH THREE DIAGONAL TIES. SILT FENCING SHALL NOT BE STAPLED OR NAILED TO TREES. THE FILTER FABRIC SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON, POLYESTER OR ETHYLENE YARN AND SHALL BE CERTIFIED

BY THE MANUFACTURER OR SUPPLIER. THE FILTER FABRIC SHALL CONTAIN ULTRAVIOLET RAY INHIBITORS AND STABILIZERS TO PROVIDE A MINIMUM OF 6 MONTHS OF EXPECTED USABLE CONSTRUCTION LIFE AT A TEMPERATURE RANGE OF 0 DEGREES FAHRENHEIT TO 120 DEGREES FAHRENHEIT. 9. POSTS FOR SILT FENCES SHALL BE EITHER 4-INCH DIAMETER WOOD OR 1.33 POUNDS PER LINEAR FOOT STEEL WITH A MINIMUM

LENGTH OF 5 FEET. STEEL POSTS SHALL HAVE, PROJECTIONS FOR FASTENING WIRE TO THEM. POSTS SHALL BE PLACED ON THE DOWN SLOPE SIDE OF THE FABRIC. 10. THE HEIGHT OF A SILT FENCE SHALL NOT EXCEED 36 INCHES AS HIGHER FENCES MAY IMPOUND VOLUMES OF WATER SUFFICIENT TO CAUSE FAILURE OF THE STRUCTURE

THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE NECESSARY; FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY SEALED. 12. A MANUFACTURED SILT FENCE SYSTEM WITH INTEGRAL POSTS MAY BE USED.

13. POST SPACING SHALL NOT EXCEED 6 FEET. 14. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4 INCHES WIDE AND 4 INCHES DEEP ALONG THE LINE OF POSTS AND UP GRADIENT FROM THE BARRIER.

15. THE STANDARD STRENGTH OF FILTER FABRIC SHALL BE STAPLED OR WIRED TO THE POST, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC. 17. SILT FENCE MAY BE INSTALLED BY "SLICING" USING MECHANICAL EQUIPMENT SPECIFICALLY DESIGNED FOR THIS PROCEDURE. THE SLICING METHOD USES AN IMPLEMENT TOWED BEHIND A TRACTOR TO "PLOW" OR SLICE THE SILT FENCE MATERIAL INTO THE SOIL.

THE SLICING METHOD MINIMALLY DISRUPTS THE SOIL UPWARD AND SLIGHTLY DISPLACES THE SOIL, MAINTAINING THE SOIL'S PROFILE AND CREATING AN OPTIMAL CONDITION FOR SUBSEQUENT MECHANICAL COMPACTION. 18. SILT FENCES SHALL BE INSTALLED WITH "SMILES" OR "J—HOOKS" TO REDUCE THE DRAINAGE AREA THAT ANY SEGMENT WILL IMPOUND 19. THE ENDS OF THE FENCE SHALL BE TURNED UPHILL.

20. SILT FENCES PLACED AT THE TOE OF A SLOPE SHALL BE SET AT LEAST 6 FEET FROM THE TOE M ALLOW SPACE FOR SHALLOW PONDING AND TO ALLOW FOR MAINTENANCE ACCESS WITHOUT DISTURBING THE SLOPE.

21. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREAS HAVE

## SILTATION CONTROL FENCE DETAIL NOT TO SCALE


### TEMPORARY VEGETATION SEEDING RECOMMENDATIONS

SPECIES	PER ACRE BUSHELS (BU) OR POUNDS (LBS.)	PER 1,000-SF	REMARKS
WINTER RYE	2.5 BU OR 112 LBS.	2.5 LBS.	BEST FOR FALL SEEDING. SEED FROM AUGUST 15 TO SEPTEMBER 15 FOR BEST COVER. SEED TO A DEPTH OF 1 INCH.
OATS	2.5 BU OR 80 LBS.	2.0 LBS.	BEST FOR SPRING SEEDING. SEED NO LATER THAN MAY 15 FOR SUMMER PROTECTION. SEED TO A DEPTH OF 1 INCH.
ANNUAL RYE GRASS	40 LBS.	1.0 LB.	GROWS QUICKLY, BUT IS OF SHORT DURATION. USE WHERE APPEARANCES ARE IMPORTANT. SEED EARLY SPRING AND/OR BETWEEN AUGUST 15 AND SEPTEMBER 15. COVER THE SEED WITH NO MORE THAN 0.25 INCH OF SOIL.
PERENNIAL RYE GRASS	30 LBS.	0.7 LBS.	BEST FOR FALL SEEDING. SEED FROM AUGUST 15 TO SEPTEMBER 15 FOR BEST COVER. SEED TO A DEPTH OF 1 INCH.


2. MINNICK, E.L. AND H.T. MARSHALL, (AUGUST 1992)

**CIVIL ENGINEERS** TRANSPORTATION PLANNERS

SPECIFICATIONS:



CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WIT IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.



# - STONE FLOW \_\_\_ CATCH BASIN

## BLOCK AND GRAVEL DROP INLET SEDIMENT FILTER

**SECTION** 

NOT TO SCALE

CONSTRUCTION SPECIFICATIONS

PLACE CONCRETE BLOCKS LENGTHWISE ON THEIR SIDE IN A SINGLE ROW AROUND THE PERIMETER OF THE INLET, WITH THE ENDS OF ADJACENT BLOCKS ABUTTING. THE HEIGHT OF THE BARRIER CAN BE VARIED, DEPENDING ON DESIGN NEEDS, BY STACKING COMBINATIONS OF 4-INCH, 8-INCH AND 12-INCH WIDE BLOCKS. THE BARRIER OF BLOCKS SHALL BE AT LEAST 12 INCHES HIGH AND NO GREATER THAN 24 INCHES HIGH.

WIRE MESH SHALL BE PLACED OVER THE OUTSIDE VERTICAL FACE (WEBBING) OF THE CONCRETE BLOCKS TO PREVENT STONE FROM BEING WASHED THROUGH THE HOLES IN THE BLOCKS. HARDWARE CLOTH OR COMPARABLE WIRE MESH WITH 1/2-INCH OPENINGS SHALL BE USED.


STONE SHALL BE PILED AGAINST THE WIRE TO THE TOP OF THE BLOCK BARRIER, AS SHOWN IN FIGURE 16.7. STONE GRADATION SHALL BE WELL GRADED WITH THE MAXIMUM STONE SIZE OF 6 INCHES AND MINIMUM STONE SIZE OF 1 INCH.


IF THE STONE FILTER BECOMES CLOGGED WITH SEDIMENT SO THAT IT NO LONGER ADEQUATELY PERFORMS ITS FUNCTION, THE STONE MUST BE PULLED AWAY FROM THE BLOCKS, CLEANED AND REPLACED.

<u>MAINTENANCE</u> THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS

SEDIMENT SHALL BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.

STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.





CONSTRUCTION SPECIFICATIONS:

1. THE DE-WATERING AREA WILL BE CONSTRUCTED BEFORE ANY PUMPING OCCURS AT

2. TEMPORARY DE-WATERING AREA TYPE, <u>ABOVE GRADE</u>, WILL BE CONSTRUCTED AS SHOWN ABOVE, WITH A RECOMMENDED MINIMUM LENGTH AND MINIMUM WIDTH OF

20-FT. The De-Watering area will be located as shown or as directed by teh **ENVIRONMENTAL CONSULTANT** 4. GEOTEXTILE LINING WILL BE FREE OFTEARS, OR OTHER DEFECTS THAT COMPROMISE

MAINTENANCE NOTES:

THE DURABILITY OF THE MATERIAL.

THE DE-WATERING AREAS(S) WILL BE INSPECTED DAILY TO ENSURE THAT ALL SEDIMENT IS BEING DISCHARGED INTO THE HAYBALE DAM AREA, NO TEARS ARE PRESENT AND TO IDENTIFY WHEN SEDIMENT NEED OT BE REMOVED. THE DE-WATERING AREA(S) WILL BE CLEANED OUT ONCE THE AREA IS FILLED TO 75

PERCENT OF ITS HOLDING CAPACITY. ONCE THE HOLDING CAPACITY HAS BEEN REACHED THE SEDIMENT SHALL BE REMOVED AND DISPOSED OF OFF-SITE IN ACCORDANCE WITH LOCAL, STATE AND

4. THE GEOTEXTILE LINING WILL BE REPLACED IF TEARS OCCUR DURING REMOVAL OF SEDIMENT FROM THE DE-WATERING AREA.

## DE-WATERING AREA DETAIL NOT TO SCALE

## TEMPORARY VEGETATION:

INSTALL NEEDED EROSION AND SEDIMENT CONTROL MEASURES SUCH AS SILTATION BARRIERS, DIVERSIONS, AND

SEDIMENT TRAPS 2. GRADE AS NEEDED FOR THE ACCESS OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH

APPLICATION, AND MULCH ANCHORING 3. RUNOFF SHALL BE DIVERTED FROM THE SEEDBED AREA.

4. ON SLOPES 4:1 OR STEEPER, THE FINAL PREPARATION SHALL INCLUDE CREATING HORIZONTAL GROOVES PERPENDICULAR O THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNOFF.

STONES AND TRASH SHALL BE REMOVED SO AS NOT TO INTERFERE WITH THE SEEDING AREA.

WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2

INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED. 3. IF APPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHALL BE APPLIED DURING THE GROWING SEASON. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. FERTILIZER SHALL BE RESTRICTED TO LIME, WOOD ASH OR LOW PHOSPHATE AND SLOW RELEASE NITROGEN VARIETIES. UNLESS A SOIL TEST WARRANTS OTHERWISE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL FERTILIZER AND LIMESTONE MAY BE APPLIED AT THE FOLLOWING RATES:

LIMESTONE APPLICATION RATE = 3 TONS/ACRE (138 LB./1,000-SF)\* \*EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM OXIDE

FERTILIZER APPLICATION RATE = 870 LB./ACRE (20 LB./1,000-SF)\* \*LOW PHOSPHATE FERTILIZER (6-0-4) OR EQUIVALENT

APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL CULTIPACKER TYPE SEEDER OR HYDRO SEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED BY 10% WHEN HYDROSEEDING.

TEMPORARY SEED SHALL TYPICALLY OCCUR PRIOR TO SEPTEMBER 15.


AREAS SEEDED BETWEEN MAY 15 AND AUGUST 15 SHALL BE COVERED WITH HAY OR STRAW MULCH, ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN THE NHSSM, VOL 3. VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA SHALL BE ACHIEVED PRIOR TO OCTOBER 15. IF THIS CONDITION IS NOT ACHIEVED, IMPLEMENT OTHER TEMPORARY STABILIZATION MEASURES FOR OVER WINTER PROTECTION.

**MAINTENANCE REQUIREMENTS:** 

1. TEMPORARY SEEDING SHALL BE INSPECTED WEEKLY AFTER ANY RAINFALL EXCEEDING 1/2 INCH IN 24 HOURS ON ACTIVE CONSTRUCTION SITES. TEMPORARY SEEDING SHALL BE INSPECTED JUST PRIOR TO SEPTEMBER 15, TO ASCERTAIN WHETHER ADDITIONAL SEEDING IS REQUIRED TO PROVIDE STABILIZATION OVER THE WINTER

2. BASED ON INSPECTION, AREAS SHALL BE RESEEDED TO ACHIEVE FULL STABILIZATION OF EXPOSED SOILS. IF IT IS TOO LATE IN THE PLANTING SEASON TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY STABILIZATION MEASURES SHALL BE IMPLEMENTED.

3. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND AREAS SHALL BE RESEEDED, WITH OTHER TEMPORARY MEASURES (I.E. MULCH, ETC.) USED TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.



## TEMPORARY CONSTRUCTION EXIT

NOT TO SCALE

MAINTENANCE REQUIREMENTS:
1. WHEN THE CONTROL PAD BECOMES INEFFECTIVE, THE STONE SHALL BE REMOVED ALONG WITH THE COLLECTED SOIL MATERIAL, REGRADED ON SITE, AND STABILIZED. THE ENTRANCE SHALL TEN BE

THE CONTRACTOR SHALL SWEEP THE PAVEMENT AT EXITS WHENEVER SOIL MATERIALS ARE TRACKED ONTO THE ADJACENT PAVEMENT OR TRAVELED WAY.

WHEN WHEEL WASHING IS REQUIRED, IT SHALL BE CONDUCTED ON AN AREA STABILIZED WITH AGGREGATE, WHICH DRAINS INTO AN APPROVED SEDIMENT-TRAPPING DEVICE. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING STORM DRAINS, DITCHES, OR WATERWAYS.

CONSTRUCTION SPECIFICATIONS:

1. THE MINIMUM STONE USED SHALL BE 3-INCH CRUSHED STONE

THE MINIMUM LENGTH OF THE PAD SHALL BE 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH BERM IS INSTALLED AT THE ENTRANCE OF THE

THE PAD SHALL BE THE FULL WIDTH OF CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS

GREATER. THE PAD SHALL SLOPE AWAY FROM THE EXISTING ROADWAY. THE PAD SHALL BE AT LEAST 6 INCHES THICK.

THE GEOTEXTILE FILTER FABRIC SHALL BE PLACED BETWEEN THE STONE PAD AND THE EARTH SURFACE

THE PAD SHALL BE MAINTAINED OR REPLACED WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES ARE TRACKED OFF-SITE.

NATURAL DRAINAGE THAT CROSSES THE LOCATION OF THE STONE PAD SHALL BE INTERCEPTED AND PIPED BENEATH THE PAD, AS NECESSARY, WITH SUITABLE OUTLET PROTECTION.

TEMPORARY EROSION AND SEDIMENTATION CONTROL TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH PREPARED FOR:


D.R. LEMIEUX BUILDERS, INC.

MAY 2016

C-10

NORWAY PLAINS ASSOCIATES, INC. 2 Continental Blvd., Rochester, N.H. 603-335-3948 RIP-RAP GRADATION

(INCHES)



## END SECTION / RIP-RAP CULVERT EXISTING

SECTION A-A


(PIPE OUTLET TO WELL DEFINED CHANNEL)

GEOTEXTILE FABRIC

SUB-GRADE

## % OF WEIGHT SMALLER SIZE OF STONE THAN THE GIVEN SIZE

## d50 = 4" % OF WEIGHT SMALLER SIZE OF STONE THAN THE GIVEN SIZE (INCHES)



### APRON DIMENSION TABLE 9' | 21.8' | 32.2' | 18" | 6" 7.5' | 27.5' | 20.0' | 9" | INFILTRATION BASIN 24" CPP OUTLET 6' | 21.85' | 15.85' | 9" |

### END SECTION / RIP-RAP CULVERT **EXISTING** SUB-GRADE GEOTEXTILE FABRIC SECTION A-A (PIPE OUTLET TO FLAT AREA NO WELL DEFINED CHANNEL)

### NOTES: 1. ALL PIPE CULVERTS SHALL HAVE END SECTIONS OR HEADWALLS. END SECTION MATERIAL AND MANUFACTURER SHALL MATCH THAT F THE PIPE CULVERT. 2. THE LARGEST RIP-RAP SIZE DETERMINED DURING HYDROLOGIC ANALYSIS HAS BEEN USED FOR ALL OUTLETS FOR ECONOMY AND

- 3. APRON LENGTHS, WIDTHS AND THICKNESSES HAVE BEEN ROUNDED UP TO WHOLE NUMBERS FOR EASE OF CONSTRUCTION.
- PREPARE THE SUB-GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP-RAP TO THE GRADES SHOWN ON THE PLANS. MINIMUM 6" SAND/GRAVEL BEDDING OR GEOTEXTILE FABRIC REQUIRED UNDER ALL ROCK RIP-RAP. THE ROCK OR GRAVEL USED FOR FILTER OR RIP-RAP SHALL CONFORM TO THE SPECIFIED GRADATION.
- GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF ROCK RIP-RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO (2) PIECES OF FABRIC SHALL BE A
- STONE FOR THE RIP-RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.
- RIP-RAP SIZE CHOSEN FOR THE WORST CASE OF ALL OUTLETS. ALL RIP-RAP USED FOR PIPE OUTLET PROTECTION WILL HAVE THE SAME GRADATION AND THICKNESS.

### OUTLETS SHALL BE INSPECTED AND CLEANED ANNUALLY AND AFTER ANY MAJOR STORM EVENT. ANY EROSION OR DAMAGE TO THE RIP-RAP SHALL BE REPAIRED IMMEDIATELY.

THE CHANNEL IMMEDIATELY DOWNSTREAM FROM THE OUTLET SHOULD BE CHECKED TO SEE THAT NO EROSION IS OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.

## PIPE OUTLET PROTECTION DETAIL

### **DUST CONTROL PRACTICES:**

- APPLY DUST CONTROL MEASURES AS NECESSARY TO MAINTAIN CONTROL OF DUST ON SITE.
- A) MOISTEN EXPOSED SOIL SURFACES PERIODICALLY WITH ADEQUATE WATER TO CONTROL DUST. B) AVOID EXCESSIVE APPLICATION OF WATER THAT WOULD RESULT IN MOBILIZING SEDIMENT AND SUBSEQUENT DEPOSITION IN NATURAL WATERBODIES.
- **STONE APPLICATION:** A) COVER SURFACE WITH CRUSHED OR COARSE GRAVEL.
- B) IN AREAS NEAR WATERWAYS USE ONLY CHEMICALLY STABILIZED OR WASHED AGGREGATE. REFER TO "NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3 CONSTRUCTION PHASE EROSION AND SEDIMENT CONTROLS, DECEMBER 2008" FOR OTHER ALLOWABLE DUST CONTROL PRACTICES (I.E. COMMERCIAL TACKIFIERS OR CHEMICAL TREATMENTS SUCH AS CALCIUM CHLORIDE, ETC.)

## STOCKPILE PRACTICES:

- LOCATE STOCKPILES A MINIMUM OF 50-FT. AWAY FROM CONCENTRATED FLOWS OF STORMWATER, DRAINAGE
- PROTECT ALL STOCKPILES FROM STORMWATER RUN-ON USING TEMPORARY PERIMETER MEASURES SUCH AS DIVERSIONS, BERMS, SANDBAGS OR OTHER APPROVED PRACTICES.
- STOCKPILES SHALL BE SURROUNDED BY SEDIMENT BARRIERS AS DESCRIBED ON THE PLANS AND IN NHSMM VOL. 3. TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILE.
- IMPLEMENT WIND EROSION CONTROL PRACTICES AS APPROPRIATE ON ALL STOCKPILED MATERIAL. . PLACE BAGGED MATERIALS ON PALLETS OR UNDERCOVER.

**MAINTENANCE NOTES:** 

- PROTECTION OF INACTIVE STOCKPILES:
  6. INACTIVE SOIL STOCKPILES SHALL BE COVERED WITH ANCHORED TARPS OR PROTECTED WITH SOIL STABILIZATION MEASURES (TEMPORARY SEED AND MULCH OR OTHER TEMPORARY STABILIZATION PRACTICE) AND TEMPORARY PERIMETER SEDIMENT BARRIERS (I.E. SILT FENCE, ETC.) AT ALL TIMES.
- INACTIVE STOCKPILES OF CONCRÈTE RUBBLE, ASPHALT CONCRETE RUBBLE, AGGREGATE MATERIALS, AND SIMILAR MATERIALS SHALL BE PROTECTED WITH TEMPORARY SEDIMENT PERIMETER BARRIERS (I.E. SILT FENCE, ETC.) AT ALL TIMES. IF THE MATERIALS ARE A SOURCE OF DUST, THEY SHALL ALSO BE COVERED.

### PROTECTION OF ACTIVE STOCKPILES:

FILE NO. 104

F.B. NO.

PLAN NO. C-2780

DWG. NO. 15225/SP-2

- 8. ALL STOCKPILES SHALL BE SURROUNDED WITH TEMPORARY LINEAR SEDIMENT BARRIERS (I.E. SILT FENCE, ETC.) PRIOR TO THE ONSET OF PRECIPITATION. PERIMETER BARRIERS SHALL BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMMODATE THE DELIVERY AND REMOVAL OF MATERIAL FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIER SHALL BE INSPECTED AT THE END OF EACH WORKING DAY.
- WHEN A STORM IS PREDICTED, STOCKPILES SHALL BE PROTECTED WITH AN ANCHORED PROTECTIVE COVERING.

## PERMANENT VEGETATION:

- SITE PREPARATION:

  1. INSTALL NEEDED EROSION AND SEDIMENT CONTROL MEASURES SUCH AS SILTATION BARRIERS, DIVERSIONS. AND SEDIMENT TRAPS GRADE AS NEEDED FOR THE ACCESS OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING,
- MULCH APPLICATION, AND MULCH ANCHORING. RUNOFF SHALL BE DIVERTED FROM THE SEEDBED AREA.
- 4. ON SLOPES 4:1 OR STEEPER, THE FINAL PREPARATION SHALL INCLUDE CREATING HORIZONTAL GROOVES PERPENDICULAR TO THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE
- WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OPERATION SHALL BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FINE SEEDBED IS PREPARED. ALL BUT CLAY AND SILT SOILS SHALL
- BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE. REMOVE FROM THE SURFACE ALL STONES 2INCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, CONCRETE CLODS, LUMPS, TRASH
- OR OTHER UNSUITABLE MATERIAL. INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED; THE AREA MUST BE TILLED AND FIRMED AS ABOVE.
- WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED. IF APPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHALL BE APPLIED DURING THE
- APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. FERTILIZER SHALL BE RESTRICTED TO LIME, WOOD ASH OR LOW PHOSPHATE AND SLOW RELEASE NITROGEN VARIETIES, UNLESS A SOIL TEST WARRANTS OTHERWISE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL FERTILIZER AND LIMESTONE MAY BE APPLIED AT THE FOLLOWING RATES:

LIMESTONE APPLICATION RATE = 3 TONS/ACRE (138 LB./1,000-SF)\* \*EQUIVALENT TO 50% CALCIUM PLUS MAGNÉSIUM OXIDE

FERTILIZER APPLICATION RATE = 870 LB./ACRE (20 LB./1,000-SF)\* \*LOW PHOSPHATE FERTILIZER (6-0-4) OR EQUIVALENT

- INOCULATE ALL LEGUME SEED WITH THE CORRECT TYPE OF INOCULANT. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE.
- 3. WHERE FEASIBLE EXCEPT WHERE EITHER CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED, THE SEEDBED SHALL BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR 4. SPRING SEEDING USUALLY GIVES THE BEST RESULTS FOR ALL SEED MIXES OR WITH LEGUMES. PERMANENT SEEDING SHALL BE COMPLETED 45 DAYS PRIOR TO FIRST KILLING FROST. WHEN CROWN VETCH IS SEEDED IN LATE SUMMER AT LEAST 35% OF THE SEED SHALL BE HARD
- SEED (UNSCARIFIED). IF SEEDING CANNOT BE DONE WITHIN THE SPECIFIED SEEDING DATES. MULCH ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN THE NHSSM, VOL 3. AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD. AREAS SEEDED BETWEEN MAY 15 AND AUGUST 15 SHALL BE COVERED WITH HAY OR STRAW
- MULCH, ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN THE NHSSM, VOL 3. VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA SHALL BE ACHIEVED PRIOR TO OCTOBER 15. IF THIS CONDITION IS NOT ACHIEVED, IMPLEMENT OTHER TEMPORARY

- WHEN HYDROSEEDING (HYDRAULIC APPLICATION), PREPARE THE SEEDBED AS SPECIFIED ABOVE OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND REMOVE SURFACE STONES LARGER THAN 2 INCHES IN DIAMETER.
- SLOPES BUST BE NO STEEPER THAN 2:1 (2 FEET HORIZONTALLY BY 1 FOOT VERTICALLY. LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. THE USE OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). BETTER PROTECTION IS GAINED BY USING STRAW MULCH AND HOLDING IT WITH ADHESIVE MATERIALS OR 500 POUNDS PER ACRE OF WOOD FIBER MULCH.
- SEEDING RATES MUST BE INCREASED BY 10% WHEN HYDROSEEDING.

STABILIZATION MEASURES FOR OVER WINTER PROTECTION.

### PERMANENT SEEDED AREAS SHALL BE INSPECTED AT LEAST MONTHLY DURING THE COURSE OF

- CONSTRUCTION. INSPECTION, MAINTENANCE AND CORRECTIVE ACTIONS SHALL CONTINUE UNTIL THE OWNER ASSUMES PERMANENT OPERATION OF THE SITE. SEEDED AREAS SHALL BE MOWED AS REQUIRED TO MAINTAIN A HEALTHY STAND OF
- VEGETATION. MOWING HEIGHT AND FREQUENCY DEPEND OF TYPE OF GRASS COVER. BASED ON INSPECTION, AREAS SHALL BE RESEEDED TO ACHIEVE FULL STABILIZATION OF
- EXPOSED SOILS. 4. AT A MINIMUM 85% OF THE SOIL SURFACE SHALL BE COVERED BY VEGETATION. 5. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND AREAS SHALL BE RESEEDED. WITH OTHER TEMPORARY MEASURES (I.E. MULCH, ETC.) USED TO

PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.

## PERMANENT VEGETATION SEEDING RECOMMENDATIONS

USE	MIXTURE	SPECIES	LBS./ACRE	LBS./ 1,000-SF
STEEP CUTS AND FILLS, BORROW AND DISPOSAL AREAS	А	TALL FESCUE CREEPING RED FESCUE REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95
WATERWAYS, EMERGENCY SPILLWAYS, AND OTHER CHANNELS WITH FLOWING WATER	A	TALL FESCUE CREEPING RED FESCUE REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95
LIGHTLY USED PARKING LOTS, ODD AREAS, UNUSED LANDS, AND LOW INTENSITY RECREATION SITES	A	TALL FESCUE CREEPING RED FESCUE REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95
PLAY AREAS AND ATHLETIC FIELDS (TOPSOIL ESSENTIAL FOR GOOD TURF)	F	CREEPING RED FESCUE KENTUCKY BLUEGRASS TOTAL	50 50 100	1.15 1.15 2.30

### NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3, TABLES 4-2 AND 4-3 . MINNICK, E.L. AND H.T. MARSHALL, (AUGUST 1992)

- A SITE IS DEEMED STABILIZED WHEN IT IS IN A CONDITION IN WHICH THE SOIL ON SITE WILL NOT EXPERIENCE ACCELERATED OR UNNATURAL EROSION UNDER THE CONDITIONS OF A 10-YEAR STORM EVENT, SUCH AS BUT NOT LIMITED TO: A) IN AREAS THAT WILL NOT BE PAVED:
  - a) A MINIMUM OF 85% VEGETATIVE COVER HAS BEEN ESTABLISHED; b) A MINIMUM OF 3-INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR A CERTIFIED COMPOST BLANKET HAS BEEN INSTALLED, OR; c) EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.
- A) IN AREAS TO BE PAVED: a) BASE COURSE GRAVELS HAVE BEEN INSTALLED.


**CONSTRUCTION PHASING:** 

- TEMPORARY STABILIZATION:
  ALL AREAS OF EXPOSED OR DISTURBED SOIL SHALL BE TEMPORARILY STABILIZED AS SOON AS PRACTICABLE BUT NO LATER THAN 45 DAYS FROM THE TIME OF INITIAL DISTURBANCE, UNLESS A SHORTER TIME IS SPECIFIED BY LOCAL AUTHORITIES, THE ONSTRUCTION SEQUENCE APPROVED AS PART OF THE ISSUED PERMIT OR AN
- PERMANENT STABILIZATION ALL AREAS OF EXPOSED OR DISTURBED SOIL SHALL BE PERMANENTLY STABILIZED AS 5. SOON AS PRACTICABLE BUT NO LATER THAN 3 DAYS FOLLOWING FINAL GRADING. 4. MAXIMUM AREA OF DISTURBANCE: THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN
- NO CASE EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREA ARE 5. ONLY DISTURB, CLEAR, OR GRADE AREAS NECESSARY FOR CONSTRUCTION. A) FLAG OR OTHERWISE DELINEATE AREAS NOT TO BE DISTURBED. ) EXCLUDE VEHICLES AND CONSTRUCTION EQUIPMENT FROM THESE AREAS TO
- PRESERVE NATURAL VEGETATION. 1. ALL GRADED OR DISTURBED AREAS INCLUDING SLOPES SHALL BE PROTECTED DURING CLEARING AND CONSTRUCTION IN ACCORDANCE WITH THE APPROVED GRADING AND
- DRAINAGE PLAN DEPICTED ON <u>SHEET C-3</u>.

  2. ALL EROSION AND SEDIMENT CONTROL PRACTICES AND MEASURES SHALL BE CONSTRUCTED, APPLIED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL PLAN DEPICTED ON <u>SHEET C-4</u>.
  TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED
- IN THE AMOUNT NECESSARY TO COMPLETE FINISHED GRADING AND BE PROTECTED FROM EROSION.
- 4. STOCKPILES, BORROW AREAS AND SPOILS SHALL BE STABILIZED AS DESCRIBED UNDER "SOIL STOCKPILE PRACTICES" SLOPES SHALL NOT BE CREATED SO CLOSE TO PROPERTY LINES AS TO ENDANGER
- ADJOINING PROPERTIES WITHOUT ADEQUATE PROTECTION AGAINST SEDIMENTATION, EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED DAMAGE. AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND/OR OTHER OBJECTIONABLE MATERIALS.
- AREAS SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3-INCHES PRIOR TO PLACEMENT OF TOPSOIL. TOPSOIL SHALL BE PLACED WITHOUT SIGNIFICANT COMPACTION TO PROVIDE A LOOSE BEDDING FOR PLACEMENT OF SEED. B. ALL FILLS SHALL BE COMPACTED IN ACCORDANCE WITH PROJECT SPECIFICATIONS TO
- REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES, SITE UTILITIES, CONDUITS AND OTHER FACILITIES, SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES. 9. IN GENERAL, FILLS SHALL BE COMPACTED IN LAYERS RANGING FROM 6 TO 24
- INCHES IN THICKNESS. THE CONTRACTOR SHALL REVIEW THE PROJECT GEOTECHNICAL REPORT AND/OR THE "PROJECT SPECIFIC PHASING NOTES" FOR SPECIFIC GUIDANCE. 10. ANY AND ALL FILL MATERIAL SHALL BE FREE OF BRUSH, RUBBISH, ROCKS (LARGER
- THAN 3/4 THE DEPTH OF THE LIFT BEING INSTALLED), LOGS, STUMPS, BUILDING DEBRIS, FROZEN MATERIAL AND OTHER OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY LIFTS. 11. FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE (I.E. CLAY, SILT)
- MATERIALS ARE SUSCEPTIBLE TO ACCELERATED SETTLEMENT AND POTENTIAL ACCELERATED EROSION. WORK IN AREAS OF THESE MATERIALS SHALL BE PERFORMED UNDER THE DIRECTION OF A PROFESSIONAL ENGINEER. 12. THE OUTER FACE OF THE FILL SLOPE SHALL BE ALLOWED TO STAY LOOSE, NOT ROLLED OR COMPACTED, OR BLADE SMOOTHED. A BULLDOZER MAY RUN UP AND DOWN THE FILL SLOPE SO THE DOZER TREADS (CLEAT TRACKS) CREATE GROOVES
- PERPENDICULAR TO THE SLOPE. IF THE SOIL IS NOT TOO MOIST. EXCESSIVE COMPACTION WILL NOT OCCUR. SEE "SURFACE ROUGHENING" IN THE NHSMM, VOL.3.

  13. ROUGHEN THE SURFACE OF ALL SLOPES DURING THE CONSTRUCTION OPERATION TO RETAIN WATER, INCREASE INFILTRATION AND FACILITATE VEGETATION ESTABLISHMENT. 14. USE SLOPE BREAKS, SUCH AS DIVERSIONS, BENCHES, OR CONTOUR FURROWS AS APPROPRIATE TO REDUCE THE LENGTH OF CUT-FILL SLOPES TO LIMIT SHEET AND
- RILL EROSION AND PREVENT GULLY EROSION. ALL BENCHES SHALL BE KEPT FREE OF SEDIMENT DURING ALL PHASES OF CONSTRUCTION. 15. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE EVALUATED BY A <u>PROFESSIONAL ENGINEER</u> (PREFERABLY THE DESIGN ENGINEER) TO DETERMINE IF THE PROPOSED DESIGN SHALL BE REVISED TO PROPERLY MANAGE THE CONDITION.
- 16. STABILIZE ALL GRADED AREAS (AS ABOVE) WITH VEGETATION, CRUSHED STONE. COMPOST BLANKET, OR OTHER GROUND COVER AS SOON AS GRADING IS COMPLETE OR IF WORK IS INTERRUPTED FOR 21 WORKING DAYS OR MORE. USE MULCH OR OTHER APPROVED METHODS TO STABILIZE AREAS TEMPORARILY WHERE FINAL GRADING
- MUST BE DELAYED. 17. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY FOLLOWING FINISHED GRADING. 18. THE PROJECT SHALL BE CONSTRUCTED TO MEET ALL REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER ARG 3800 RELATIVE TO INVASIVE SPECIES.

ABOVE NOTES EXCERPTED, ADAPTED AND REFERENCED FROM "NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3 CONSTRUCTION PHASE EROSION AND SEDIMENT CONTROLS, DECEMBER 2008" (NHSMM, VOL. 3)





05/20/2016 - REVISED PLAN PER ROCHESTER TRG COMMENTS

## PROJECT SPECIFIC CONSTRUCTION PHASING:

CIVIL ENGINEERS

LOCAL REGULATIONS.

- COMMENCING CONSTRUCTION IN ACCORDANCE WITH THE FOLLOWING PHASING. THE "GENERAL CONSTRUCTION PHASING" NOTES APPLY TO THE OVERALL CONSTRUCTION AND SHALL BE ADHERED TO
- INSTALL ALL TEMPORARY SEDIMENT CONTROL BARRIERS (I.E. SILT FENCE, EROSION CONTROL MIX BERM, STONE CHECK DAMS, ETC.) AROUND THE OUTER PERIMETER OF THE CONSTRUCTION SITE AS DEPICTED ON SHEET
- C-4 PRIOR TO EARTH MOVING OPERATIONS. INSTALL ORANGE SNOW FENCE AROUND THE PEREMITER OF THE INFILTATION BASINS AND THE FENCE SHALL REMAIN IN PLACE UNTIL CONSTRUCTION OF
- THE BASINS HAS STARTED. CLEAR, GRUB AND STRIP THE SITE. STUMPS, BRUSH AND OTHER ORGANIC WASTE SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH STATE AND
- INSTALL A TEMPORARY CONSTRUCTION EXIT AT THE LOCATION OF THE PROPOSED DRIVEWAY CONNECTION TO AIRPORT DRIVE. MAINTAIN AS DIRECTED BY THE TEMPORARY CONSTRUCTION EXIT DETAIL STOCKPILE STRIPPED TOPSOIL AND CUT MATERIAL TO BE REUSED ON SITE IN AN APPROPRIATE LOCATION IN ACCORDANCE WITH THE "SOIL STOCKPILES
- PRACTICES". MAINTAIN THE STOCKPILES AS DIRECTED IN THE "SOIL STOCKPILE PRACTICES". PERFORM THE NECESSARY CUTS AND FILLS TO CONSTRUCT THE GRAVEL WETLANDS BASIN AS DEPICTED ON SHEET C-3 AND IN ACCORDANCE WITH
- THE GRAVEL WETLAND BASIN DETAILS SHOWN ON SHEET C-9. PERFORM THE NECESSARY CUTS AND FILLS TO CONSTRUCT THE INFILTRATION BASIN AS DEPICTED ON SHEET C-3 AND IN ACCORDANCE
- WITH THE INFILTRATION BASIN DETAILS SHOWN ON SHEET C-10. CONSTRUCT THE GRAVEL WETLANDS BASIN, SEDIMENT FOREBAY AND OUTLET PROTECTION. LOAM SEED AND MULCH THE SIDE SLOPES OF THE BASIN AS DIRECTED IN THE INFILTRATION BASIN DETAILS.
- 10. ALL DITCHES/SWALES/AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM. 11. PERFORM THE NECESSARY CUTS AND FILLS TO SUBGRADE IN THE BUILDING AND PARKING LOT AREAS. A) INSTALL REQUIRED FILLS IN MAXIMUM 8-INCH LIFTS AND COMPACT
- EACH LIFT TO 95% MAXIMUM PROCTOR DENSITY. AS SUBGRADE IS ACHIEVED INSTALL REMAINING SEDIMENT CONTROL BARRIERS WITHIN THE SITE (I.E. ADDITIONAL SILT FENCE, CHECK DAMS AND SEDIMENT CONTROLS AND CATCH BASINS, ETC.)
- INSTALL ALL UTILITIES AND CLOSED DRAINAGE SYSTEM COMPONENTS (I.E. PIPE CULVERTS, CATCH BASINS AND REMAINING WATER MAIN) PER THE CORRESPONDING DETAILS AND AS SHOWN ON <u>SHEET C-3 AND C-5</u>. AS EACH STRUCTURE IS COMPLETED INSTALL THE CORRESPONDING CONSTRUCT THE INFILTRATION BASINS AND OUTLET PROTECTION. LOAM
- INFILTRATION BASIN DETAILS AND TEMPORARY SEDIMENT CONTROL BARRIER DEPICTED ON <u>SHEET C-7.</u>

  4. ALL CUT AND FILL SLOPES AND LAWN AREAS NOT TO BE PAVED SHALL BE LOAMED AND SEEDED FOR PERMANENT VEGETATION AND STABILIZATION AS DESCRIBED UNDER THE "PERMANENT VEGETATION PRACTICES" WITHIN 3

SEED AND MULCH THE SIDE SLOPES OF THE BASIN AS DIRECTED IN THE

- DAYS OF ACHIEVING FINAL GRADE INSTALL ALL GRAVEL BASE AND CRUSHED GRAVEL MATERIALS FOR THE PARKING AREA AS SPECIFIED IN THE CORRESPONDING DETAILS.
- 6. THE PARKING AREAS SHALL BE STABILIZED (CONSTRUCTED TO GRAVEL BASE COURSE) WITHIN 3 DAYS OF ACHIEVING FINISHED SUBGRADE INSTALL PAVEMENT SURFACES AS SOON AS POSSIBLE AFTER THE
- INSTALLATION OF THE GRAVEL BASE AND CRUSHED GRAVEL, IN ORDER TO LIMIT THE SOIL EROSION AND POLLUTION OF THE GRAVEL MATERIALS WITH ORGANIC MATERIALS. IN NO CASE SHALL AREAS TO BE PAVED BE LEFT UNPROTECTED THROUGH OUT THE WINTER MONTHS.
- ALL DISTURBED AREAS SHALL BE STABILIZED AS SOON AS POSSIBLE. IN NO CASE SHALL ANY DISTURBED AREA BE LEFT UN-STABILIZED FOR LONGER THAN 21 DAYS. IF NECESSARY TEMPORARY STABILIZATION MEASURES AS DISCUSSED IN THE "GENERAL CONSTRUCTION PHASING NOTES" AND NHSMM, VOL. 3 SHOULD BE EMPLOYED. MAINTENANCE AND INSPECTION:
  20. DURING CONSTRUCTION ALL TEMPORARY AND PERMANENT SEDIMENT.
- EROSION CONTROL AND STORMWATER MANAGEMENT PRACTICES SHOULD BE INSPECTED WEEKLY, AFTER EVERY 1/2 INCH OF RAINFALL, AND ANNUALLY. 21. EXCESS SEDIMENT SHOULD BE REMOVED FROM TEMPORARY SEDIMENT. EROSION CONTROL AND STORMWATER MANAGEMENT PRACTICES WHEN IT
- 22. ALL DAMAGED TEMPORARY AND PERMANENT SEDIMENT, EROSION CONTROL AND STORMWATER MANAGEMENT PRACTICES SHOULD BE REPAIRED OR REPLACED IMMEDIATELY UPON NOTICE

REACHES PRESCRIBED THRESHOLDS DISCUSSED IN THE DETAILS FOR EACH

- 23. SEDIMENT SHALL BE DISPOSED OF PROPERLY EITHER ON SITE OR OFF SITE. PROJECT COMPLETION AND STABILIZATION:
  24. UPON PROJECT COMPLETION, ONCE THE SITE IS DEEMED STABILIZED (VEGETATION IS GERMINATED), THE TEMPORARY SEDIMENT CONTROL BARRIERS AND EROSION CONTROL PRACTICES SHALL BE REMOVED. ANY DISTURBANCE CREATED DURING REMOVAL SHALL BE REPAIRED IN AN
- APPROPRIATE MANNER. 25. ACCUMULATED SEDIMENT SHALL BE REMOVED FROM ALL ON SITE CATCH BASINS AND THE SEDIMENT FOREBAYS TO THE GRAVEL WETLANDS BASIN.

## WINTER STABILIZATION & **CONSTRUCTION PRACTICES:**

- MAINTENANCE REQUIREMENTS: MAINTENANCE MEASURES SHALL BE PERFORMED THROUGHOUT CONSTRUCTION, INCLUDING OVER THE WINTER PERIOD. AFTER EACH RAINFALL, SNOWSTORM, OR PERIOD OF THAWING AND RUNOFF, THE SITE CONTRACTOR SHALL CONDUCT INSPECTION OF ALL INSTALLED EROSION CONTROL PRACTICES AND PERFORM REPAIRS AS NEEDED TO INSURE THEIR
- CONTINUED FUNCTION. 2. FOR ANY AREA STABILIZED BY TEMPORARY OR PERMANENT SEEDING PRIOR TO THE ONSET OF THE WINTER SEASON, THE CONTRACTOR SHALL CONDUCT AN INSPECTION IN THE SPRING TO ASCERTAIN THE CONDITION OF THE VEGETATION AND REPAIR ANY DAMAGED AREAS OR BARE SPOTS AND RESEED AS REQUIRED TO ACHIEVE AN ESTABLISHED VEGETATIVE COVER (AT LEAST 85% OF AREA VEGETATED WITH HEALTHY, VIGOROUS GROWTH.)

### THE FOLLOWING STABILIZATION TECHNIQUES SHALL BE EMPLOYED DURING THE PERIOD FROM OCTOBER 15 THROUGH MAY 15. 1. THE AREA OF EXPOSED, UNSTABILIZED SOIL SHALL BE LIMITED TO 1-ACRE AND SHALL BE PROTECTED AGAINST EROSION BY THE METHODS DISCUSSE IN NHSMM, VOL. 3 AND ELSEWHERE IN THIS PLAN SET, PRIOR TO ANY

- THAW OR SPRING MELT EVENT. 2. STABILIZATION AS FOLLOWS SHALL BE COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST
- FOR MORE THAN 5 DAYS. A. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EXHIBIT A MINIMUM 85% VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH 3 TO 4 TONS OF HAY OR STRAW MULCH PER ACRE SECURED WITH ANCHORED NETTING, OR 2 INCHES OF EROSION CONTROL MIX (REFER TO NHSMM, VOL. 3 FOR SPECIFICATION).
- B. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF GREATER THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15 SHALL BE SEEDED AND COVERED WITH A PROPERLY INSTALLED EROSION CONTROL BLANKET OR WITH A MINIMUM OF 4 INCHES OF EROSION CONTROL MIX, UNLESS OTHERWISE SPECIFIED BY THE MANUFACTURER. NOTE THAT COMPOST BLANKETS SHALL NOT EXCEED 2 INCHES IN THICKNESS OR THEY MAY
- **OVERHEAT** 3. ALL STONE COVERED SLOPES MUST BE CONSTRUCTED AND STABILIZED BY
- 4. INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX SHALL NOT OCCUR OVER SNOW OF GREATER THAN 1 INCH IN DEPTH.
- 5. ALL MULCH APPLIED DURING WINTER SHALL BE ANCHORED (I.E. BY NETTING, TRACKING, WOOD CELLULOSE FIBER). 6. WITHIN 24 HOURS OF STOCKPILING SOIL MATERIALS SHALL BE MULCHED FOR OVER WINTER PROTECTION WITH HAY OR STRAW AT TWICE THE NORMAL
- RATE OR WITH A 4 INCH LAYER OF EROSION CONTROL MIX. MULCH SHALL BE REESTABLISHED PRIOR TO ANY RAIN OR SNOWFALL. NO SOIL STOCKPILE SHALL BE PLACED (EVEN COVERED WITH MULCH) WITHIN 100-FT OF ANY WETLAND OR OTHER WATER RESOURCE AREA.
- 7. FROZEN MATERIAL (I.E. FROST LAYER REMOVED DURING WINTER CONSTRUCTION) SHALL BE STOCKPILED SEPARATELY AND IN A LOCATION AWAY FROM ANY AREA NEEDING PROTECTION. FROZEN MATERIAL STOCKPILES CAN MELT IN SPRING AND BECOME UNWORKABLE AND
- DIFFICULT TO TRANSPORT DUE TO HIGH SOIL MOISTURE CONTEN 8. INSTALLATION OF EROSION CONTROL BLANKETS SHALL NOT OCCUR OVER SNOW OF GREATER THAN 1 INCH IN DEPTH OR ON FROZEN GROUND. 9. ALL GRASS-LINED DITCHES AND CHANNELS SHALL BE CONSTRUCTED BY SEPTEMBER 1. ALL DITCHES AND SWALES WHICH DO NOT EXHIBIT 85% VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS

APPROPRIATE FOR THE DESIGN FLOW CONDITIONS AS DETERMINED BY A

PROVIDE ADEQUATE CROSS-SECTION AFTER ALLOWING FOR PLACEMENT OF 10. ALL STONE LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND


PROFESSIONAL ENGINEER. IF STONE LINING IS NECESSARY, THE

CONTRACTOR MAY NEED TO RE-GRADE THE DITCH AS REQUIRED TO

- STABILIZED BY OCTOBER 15. 11. AFTER NOVEMBER 15, INCOMPLETE ROAD OR PARKING AREAS WHERE ACTIVE CONSTRUCTION HAS STOPPED FOR THE WINTER SHALL BE PROTECTED WITH A MINIMUM 3 INCH LAYER OF SAND AND GRAVEL WITH A GRADATION THAT IS LESS THAN 12% OF THE SAND PORTION, OR MATERIAL PASSING THE
- NUMBER 4 SIEVE, BY WEIGHT, PASSES THE NUMBER 200 SIEVE. 12. SEDIMENT BARRIERS THAT ARE INSTALLED DURING FROZEN CONDITIONS SHALL CONSIST OF EROSION CONTROL MIX BERMS, OR CONTINUOUS CONTAINED BERMS. SILT FENCES AND HAY BALES SHALL NOT BE INSTALLED WHEN FROZEN CONDITIONS PREVENT PROPER EMBEDMENT OF THESE BARRIERS.

PERMANENT EROSION AND SEDIMENTATION CONTROL TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH PREPARED FOR:

D.R. LEMIEUX BUILDERS, INC. MAY 2016



## TYPICAL HYDRANT SECTION

TIE RODS OPT. (IF USED

THRUST BLOCK AT HYD.

MAY BE OMITTED)

11/2"PENTAGON NAT.

/ SIDEWALK

**ADJUSTABLE** 

VALVE BOX

WOOD OR

CONC. BLOCKS

6" CEMENT-

LINED DUCTILE

STANDARD OPERATING

ROAD PVMT.

"WATER" EMBOSSED

ON COVER (CAST)

A.W.W.A. C509

6" IRON BODY RESILIENT

WEDGE TYPE GATE VALVE

VALVES SHALL OPEN BY TURNING

CLOCKWISE (RIGHT)

ANCHOR

SETTING BLOCK AGINST

AT BOTTOM (TYP. ALL

MATERIAL MIN. 2'-0"

BRIDLED VALVES)


-UNDISTURBED

MEETING OR EXCEEDING

NOT TO SCALE

## Alton 603-875-3548 Roch. 603-335-3948 PO Box 249 Rochester, NH 03866-0249

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WIT IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.



05/20/2016 - REVISED PLAN PER ROCHESTER TRG COMMENTS

### GENERAL UTILITY NOTES

- 1.) CONTRACTOR SHALL NOTIFY DIG-SAFE (1-888 344-7233) 72 HOURS PRIOR TO THE START OF CONSTRUCTION.
- 2.) ALL EXISTING UTILITY LOCATIONS ARE APPROXIMATE AS SHOWN. THE CONTRACTOR SHALL VERIFY THEIR LOCATIONS AND ELEVATIONS.
- 3.) THESE PLAN SHOWS ONLY THOSE FEATURES THAT WERE VISUALLY APPARENT ON THE DATE OF THE SURVEY. THE ABSENCE OF SUBSURFACE STRUCTURES, UTILITIES, ETC. FROM THIS PLAN, BUT IN EXISTENCE IS NOT INTENDED OR IMPLIED.
- 4.) ANY UTILITY POLES THAT NEED TO BE RELOCATED SHALL BE COORDINATED WITH EVERSOURCE OR VERIZON, WHOM EVER HAS CONTROL OVER THEM.
- 5.) PROPOSED UTILITIES ARE TO BE UNDERGROUND. COORDINATE LOCATION OF UNDERGROUND UTILITIES AND TRANSFORMER PADS WITH PSNH AND OTHER PERTINENT UTILITY COMPANIES.
- 6.) WATER AND SEWER LINES SHALL BE INSTALLED A MINIMUM OF 10-FT APART
- HORIZONTALLY. 7.) WHERE SEWER AND WATER LINES MUST CROSS, SEWER PIPE JOINTS SHALL BE LOCATED A MINIMUM 9-FT HORIZONTALLY FROM THE WATER LINE AND A VERTICAL SEPARATION OF 18-INCHES SHALL BE MAINTAINED.
- 8.) SEWER PIPE JOINTS SHALL BE TESTED WITH ZERO LEAKAGE AT 25 POUNDS PER SQUARE INCH FOR GRAVITY SEWER AND AT 1-1/2 TIMES WORKING PRESSURE FOR ALL FORCE MAINS.
- 9.) WATERLINE CONSTRUCTION:
- A.) ALL PROPOSED WATER LINE MATERIAL USED SHALL MEET ROCHESTER WATER DEPARTMENT AND ROCHESTER ENGINEERING DEPARTMENT SPECIFICATIONS. WATER LINES SHALL BE A.W.W.A C 151, CLASS 52, CEMENT LINED, DUCTILE IRON PIPE. B.) PROPOSED WATER GATE VALVES SHALL BE MANUFACTURED BY KENNEDY OF AMERICAN FLOW CONTROL, RESILIENT SEAT TYPE.
- C.) ALL WATER LINES SHALL BE BURIED A MINIMUM OF 5'.
- D.) IF 5' OF COVER IS NOT AVAILABLE WATER LINE SHALL BE INSULATED AS SHOWN IN THE "SHALLOW COVER TRENCH DETAIL FOR INSULATED WATER PIPE".
- E.) ALL WATER FITTINGS SHALL BE CLASS 52.
- F.) PROPOSED WATER GATE VALVE SHALL OPEN CLOCKWISE (RIGHT).

CROSS COUNTRY UNDER PAVEMENT

10.) WORK TO CONNECT INTO THE WATER OR SEWER MAINS REQUIRES A PERMIT FROM THE ROCHESTER PUBLIC WORKS DEPARTMENT. CONTRACTORS ARE TO BE PRE—QUALIFIED.

## POLE MOUNTED LIGHT DETAIL

NOT TO SCALE

—LIGHTING FIXTURE

PER LIGHTING PLAN


DIAMETER

- #4 12" O.C. CIRCULAR PATTERN

—3000 psi CONCRETE

-4-#4 EQUALLY SPACED

LIGTH POLE BASE SHALL BE 18" ABOVE FINISH GRADE FOR NON VEHICLE IMPACT AREAS AND 30" FOR VEHICLE IMPACT AREAS. THE LIGTH POLE BASES CAN BE PRECAST, WITH COORDINATION WITH THE LIGHTING FIXTURE MANUFACTURE FOR BOLT PATTERN.



MAX. FIXTURE

CLEAN GRANULAR FILL

NHDOT CRUSHED GRAVEL

BOLT PATTERN DETAIL

TO BE PROVIDED BY

FINISH GRADE 1


LIGHT POLE SUPPLIER.

18" OR 30"

(SEE NOTE)


## WATER MAIN CONNECTION

NOT TO SCALE



## TYPICAL FIRE SERVICE CONNECTION

NOT TO SCALE



NOTES:

1. ALL NON-METALLIC CONDUIT AND FITTINGS SHALL BE ELECTRICAL GRADE, SCHEDULE 40 PVC, AND SHALL CONFORM TO THE APPLICABLE SECTIONS OF NEMA TC2—1990 AND BE UL LISTED. ONLY GRAY—COLORED CONDUIT WILL BE ACCEPTED. ANY PVC CONDUIT NOT HAVING THE PROPER NEMA AND UL MARKINGS WILL NOT BE ACCEPTED. ALL STEEL CONDUITS SHALL CONFORM TO ASTM A120 AND BE RIGID GALVANIZED STEEL. ALL PVC JOINTS MUST BE CEMENTED. STEEL FITTINGS SHALL BE SEALED WITH COMPOUND.

2. ALL 90 DEGREE SWEEPS WILL BE MADE USING RIGID GALVANIZED STEEL WITH A MINIMUM RADIUS OF 36 INCHES FOR PRIMARY CABLES AND 24 INCHES

- FOR SECONDARY CABLES. ALL STEEL SWEEPS WITHIN 18" OF THE SURFACE SHALL BE PROPERLY GROUNDED.
- 3. A 10-FOOT HORIZONTAL SECTION OF RIGID GALVANIZED STEEL CONDUIT WILL BE REQUIRED AT EACH SWEEP, UNLESS IN THE OPINION OF THE PSN DESIGNER, THE SWEEP-PVC JOINT IS NOT SUBJECT TO FAILURE DURING CABLE PULLING. THE CONDUIT SHALL CROSS PAVED AREAS AT APPROXIMATELY 90 DEGREES. 5. BACKFILL MAY BE MADE WITH EXCAVATED MATERIAL OR COMPARABLE, UNLESS MATERIAL IS DEEMED UNSUITABLE BY PSNH. BACKFILL SHALL BE FREE
- OF FROZEN LUMPS, ROCKS, DEBRIS, AND RUBBISH. ORGANIC MATERIAL SHALL NOT BE USED AS BACKFILL. BACKFILL SHALL BE THOROUGHLY COMPACTED IN 6-INCH LAYERS. 6. A SUITABLE PULL STRING, CAPABLE OF 200 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE PSNH IS NOTIFIED TO INSTALL CABLE THE STRING SHOULD BE BLOWN INTO THE CONDUIT AFTER THE RUN IS ASSEMBLED TO AVOID BONDING THE STRING TO THE CONDUIT.
- ROUTING OF THE CONDUIT AND INSPECTION PRIOR TO BACKFILL WILL BE PROVIDED BY PSNH. INSTALLATION OF THE CONDUIT WILL BE DONE BY THI CONTRACTOR. THE PSNH SUPERVISOR MUST BE NOTIFIED 2 BUSINESS DAYS PRIOR TO BACKFILLING THE TRENCH. IN THE EVENT THAT A CABLE CANNOT BE SUCCESSFULLY PULLED THROUGH THE COMPLETED CONDUIT SYSTEM DUE TO A CONSTRUCTION ERROR, IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE AND REPAIR THE INVOLVED CONDUIT. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL RESULTING EXPENSES.
- 8. NORMAL CONDUIT SIZES FOR PSNH ARE 3-INCH FOR SINGLE PHASE PRIMARY AND SECONDARY VOLTAGE CABLES, 4-INCH FOR THREE PHASE SECONDARY, AND 5-INCH FOR THREE PHASE PRIMARY ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND
- ORDINANCES, AND WHERE APPLICABLE THE NATIONAL ELECTRIC CODE. 10. CONDUIT MAY BE INSTALLED BY EXCAVATING AN OPEN TRENCH WITH SIDE SLOPES OF 1:1 MAXIMUM TO A DEPTH OF 4-FT. INSTALLATIONS DEEPER THAN

## ELECTRICAL & UNDERGROUND UTILITY

NOT TO SCALE

TRENCH INSTALLATION DETAIL

UTILITY DETAILS TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH PREPARED FOR:

D.R. LEMIEUX BUILDERS, INC.

AS SHOWN MAY 2016

### DWG. NO. 15225/SP-2 F.B. NO.

EBAA IRON, INC., RELEASE 3.1.

." | 24 | 18 | 8 | 12 | 8

SIZE OF THRUST BLOCKS MAY BE INCREASED BY THE ENGINEER TO MEET SOIL CONDITIONS FOUND DURING CONSTRUCTION.

WATER MAIN

THRUST BLOCK DETAILS

NOT TO SCALE

22 1/2°

50 | 100 | 150 | 200

50 | 100 | 150 | 200

psi | psi | psi | psi

\* BASED ON A MINIMUM ATTACHED PIPE ALONG RUN (Lr) = 5 FEET

PIPE

DIAMETER

(INCHES)

10"

12"

10"

FILE NO. 104

PLAN NO. C-2780

11 1/4°

50 | 100 | 150 | 200 |

13 | 24 |

DUCTILE IRON MECHANICAL RETRAINED LENGTH (FEET)

100 | 150 | 200 | 50 | 100 | 150 | 200

REDUCER

ONE SIZE SMALLER

50 | 100 | 150 | 200 |

10

16 22

13

psi | psi | psi | psi

MECHANICAL RESTRAINED

LENGTH SCHEDULE

NOT TO SCALE

THE EXISTING SOIL IS POORLY GRADED GRAVEL AND GRAVEL SAND MIXTURE WITH LITTLE TO

NOTES:
1. PIPE IS BURIED TO A DEPTH OF 6 FEET WITH A MINIMUM OF 4 INCHES OF COMPACTED

4. ALL CALCULATIONS ARE BASED ON THE "RESTRAINED LENGTH CALCULATION PROGRAM" BY

GRANULAR MATERIAL UNDER THE PIPE TO THE SPRING LINE OF THE PIPE.

3. ALL CALCULATIONS ARE BASED ON A FACTOR OF SAFETY OF 1.5 TO 1.

31 Mooney Street, Alton, N.H. 603-875-3948

5 | 9 | 14 | 19

TWO SIZE SMALLER

DEAD END

100 | 150 | 200

2" TEE

WATER MAIN

PAYMENT

2" CORP.

COPPER GOOSENECK

2" COPPER

WATER SERVICE

NOTE: SERVICE LINE SHALL BE TYPE K COPPER CONFORMING TO ASTM-D88

TYPICAL DOMESTIC SERVICE CONNECTION

NOT TO SCALE

PAYMENT LIMIT

COPPER TUBING TYPE K

CURB STOP & BOX

LOCATION AS DIRECTED


COMPRESSION (NO DRAIN)

BRONZE FLARED TYPE

COMPRESSION FITTINGS

- BUILDING

SERVICE



BUILDING SEWER

C - 13

STAINLESS STEEL

LIFTING CHAIN (TYP.)

ALUMINUM HATCH WITH

3" SDR 21

PRESSURE PIPE

3" BRONZE

**DISCHARGE** 

SHUT-OFF GATE VALVES (TYP.)

36" X 54" OPENING

SEWER FROM SMH #1

- 8" SDR 35 PVC PIPE

10' I.D. CONCRETE WET WELL

BY SUPERIOR CONCRETE, INC.

OF THE WET WELL MUST BE

CONSTRUCTED WITH 5,000 LB MINIMUM, FLOTATION RESTRAINTS

SEWER FROM BUILDING 2 - 8" SDR 35 PVC PIPE

INV. IN = 328.65

OR EQUAL. THE BASE SECTION


INV. IN = 328.65

SEWER FROM SMH #3

- 8" SDR 35 PVC PIPE

INV. IN = 325.10'

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.



11/10/2016 - REVISED SEWER PUMP STATION DETAILS AND CALCULATIONS PER COMMENTS FROM ROCHESTER PUBLIC WORKS DEPARTMENT

12/12/16 - REVISED DETIALS PER NHDES WASTEWATER BUREAU COMMENTS 12/28/16 - REVISED DETIALS PER NHDES WASTEWATER BUREAU COMMENTS 08/11/18 - REVISE PUMPS STATION ELEVATIONS.

- HORIZONTAL JOINTS BETWEEN SECTIONS OF PRECAST CONCRETE BARRELS
  HALL BE OF AN OVERLAPPING TYPE, SEALED FOR WATER—TIGHTNESS USING A DOUBLE ROW OF AN ELASTOMERIC OR MASTIC-LIKE SEALANT.
- 2. PIPE TO MANHOLE JOINTS SHALL BE AS FOLLOWS: (1) ELASTOMERIC, RUBBER SLEEVE WITH WATERTIGHT JOINTS AT THE MANHOLE OPENING AND
- (2) CAST INTO THE WALL OR SECURED WITH STAINLESS STEEL CLAMPS; (3) ELASTOMERIC SEALING RING CAST IN THE MANHOLE OPENING WITH SEAL FORMED ON THE SURFACE OF THE PIPE BY COMPRESSION (4) NON-SHRINK GROUTED JOINTS WHERE WATERTIGHT BONDING TO THE
- MÁNHOLE AND PIPE CAN BE OBTAINED.
- 3. ALL PRECAST SECTIONS AND BASES SHALL BE COATED ON THE EXTERIOR WITH A BITUMINOUS DAMP-PROOFING COATING.
- 4. PRECAST BASES SHALL BE PLACED ON A 6-INCH LAYER OF COMPACTED BEDDING MATERIAL THAT CONFORMS TO THE ASTM C33/C33M NO. 67 STONE STANDARD IN EFFECT WHEN THE STONE IS PROCESSED BY THE MANUFACTURER, AVAILABLE AS NOTED IN APPENDIX D. THE EXCAVATION SHALL BE DEWATERED WHILE PLACING BEDDING MATERIAL AND SETTING THE BASE OR POURING CONCRETE.
- 5. CONCRETE FOR MANHOLES AND CONCRETE GRADE RINGS SHALL CONFORM TO THE REQUIREMENTS FOR CLASS AA CONCRETE IN THE NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION'S 'STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- 6. REINFORCING FOR CONCRETE MANHOLES AND CONCRETE GRADE RINGS SHALL BE STEEL OR STRUCTURAL FIBERS THAT CONFORM TO THE NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- PRECAST CONCRETE BARREL SECTIONS, CONES, AND BASES SHALL BE CERTIFIED BY THEIR MANUFACTURER(S) AS CONFORMING TO THE ASTM C478 STANDARD IN EFFECT AT THE TIME THE BARREL SECTIONS, CONES, AND BASES ARE MANUFACTURED.
- 8. WET WELLS SHALL BE TESTED PRIOR TO OPERATION USING EXFILTRATION TESTING METHOD ACI 350.1 METHOD HST-NML IN EFFECT AT THE TIME THE WET WELL IS INSTALLED, AVAILABLE AS NOTED IN APPENDIX D. ANY VISIBLE SIGNS OF LEAKAGE SHALL BE REPAIRED AND RETESTED PRIOR TO PLACING THE WET WELL IN SERVICE.
- 9. THE WET WELL FLOOR SHALL HAVE A MINIMUM SLOPE OF 1 TO 1 TO THE HOPPER BOTTOM.
- 10. ALARM SIGNAL SHALL BE ACTIVED IN ANY ONE OF THE FOLLOWING;
  - HIGH WATER IN WET WELL 2. LOW WATER IN WET WELL
  - 3. LOSS OF ONE OR MORE PHASES OF POWER SUPPLE OR SEVERE VOLTAGE DROP
  - 4. LOSS OF THE ALARM TRANSMISSION CAPABILITY 5. STANDBY GENERATOR APPLICATION
  - 7. LEVEL SENSING MALFUNCTION OR FAILURE 8. TEMPERATURE OUTSIDE NORMAL OPERATING RANGES.
- 11. HIGH WATER AND LOW WATER ALARM TRIGGERS SHALL BE SEPARATE DEVICES, INDEPENDENT OF PUMP WET WELL LEVEL CONTROL SYSTEM.
- 12. FOR THE POWER SOURCE FOR THE ALARM SYSTEM SHALL BE THE MAIN LINE POWER WITH A BACK UP BATTERY SYSTEM, WHICH SHALL BE CONNECTED AUTOMATICALLY SHOULD MAIN POWER FAILURE.
- 13. BACK-UP POWER SUPPLY FROM ON-SITE GENERATOR.
- 14. INSTALL A FLOW METER THAT RECORDS CONTINUOUS FLOW AND HAS THE CAPABILITY TO TOTALIZE.
- 15. INSTALL A WARNING SIGN ON THE ACCESS DOOR STATING THE BELOW;

THIS IS A CONFINED SPACE, ENTER ONLY WITH PROPER EQUIPMENT. FOLLOWING OSHA CONFINED SPACE ACCESS REGULATIONS.

- BACK UP GENERATOR NOTES:

  A. AN INDEPENDENT ENGINE-GENERATOR TYPE SOURCE OF ELECTRIC POWER SHALL BE PROVIDED FOR ELECTRICALLY— DRIVEN PUMPS. THIS SOURCE SHALL BE AUTOMATICALLY ACTIVATED BY FAILURE OF ANY PHASE OF POWER SUPPLY OR UPON ANY FLUCTUATION IN VOLTAGE, THE AMOUNT OR DURATION OF WHICH WOULD CAUSE DAMAGE TO THE MOTORS. INSTALLATIONS SHALL COMPLY WITH ALL APPLICABLE REQUIREMENTS OF THE NEC AND THE STATE FIRE
- B. THE EMERGENCY POWER GENERATOR SHALL BE PERMANENTLY SECURED IN PLACE, WITH PROVISIONS FOR REMOVAL TO FACILITATE GENERATOR REPAIR OR REPLACEMENT.
- PROVISIONS SHALL BE MADE FOR AUTOMATIC AND MANUAL START-UP AND CUT-IN. THE CONTROLS SHALL BE SUCH THAT UPON AUTOMATIC START-UP UNDER EMERGENCY CONDITIONS, SHUT-DOWN SHALL BE ACCOMPLISHED AUTOMATICALLY ON RESTORATION OF UTILITY POWER WITH CONTROLLED SHUT-DOWN OF UNIT. MANUAL SHUT DOWN SHALL ALSO BE PROVIDED. PROVISION SHALL BE MADE TO ALLOW PUMPS TO RUN DOWN BEFORE RE-ENERGIZING ON TRANSFER OF POWER.
- D. THE EMERGENCY POWER GENERATOR SHALL BE SIZED TO SEQUENTIALLY START AND OPERATE ALL PUMPS NEEDED TO HANDLE DESIGN MAXIMUM WASTE FLOWS, PLUS LIGHTING, VENTILATION, CONTROLS, SCREENING, AND, IF
- THE EMERGENCY POWER GENERATOR SHALL BE LOCATED ABOVE GRADE WITH VENTILATION OF EXHAUST GASES. ALL EMERGENCY POWER GENERATION EQUIPMENT SHALL BE PROVIDED WITH INSTRUCTIONS FOR ROUTINE EXERCISING,
- LOAD TESTING, AND MAINTENANCE. THE GENERATOR ENGINE CONTROLS SHALL BE EQUIPPED WITH AN AUTOMATIC EXERCISER WHICH CAN BE SET ON ANY SELECTED SCHEDULE TO START THE GENERATOR, RUN THE GENERATOR UNDER NO-LOAD OR LOAD CONDITIONS
- BY SELECTION, AND SHUT THE GENERATOR OFF WITHOUT ACTUATING THE ALARM SYSTEM. H. SUBJECT TO (I), BELOW, THE OWNER SHALL PROVIDE EACH EMERGENCY GENERATOR WITH ENOUGH FUEL FOR THE GENERATOR TO RUN UNDER FULL LOAD OR PEAK STATION FLOW FOR AT LEAST 48 HOURS OR UNDER NORMAL OPERATING CONDITIONS FOR AT LEAST 96 HOURS, WHICHEVER REQUIRES THE GREATER AMOUNT OF FUEL.
- I. FOR SEWAGE PUMPING STATIONS WITH DUPLEX PUMPS. A STANDBY ENGINE DRIVE SYSTEM WHICH AUTOMATICALLY STARTS ON POWER LOSS TO DRIVE ONE PUMP MAY BE FURNISHED AS AN ALTERNATIVE TO A PERMANENT GENERATOR.


PUMP STATION AND FORCE MAIN DETAILS TAX MAP 134, LOT 5 114 ROCHESTER HILL RD. ROCHESTER, NH

MAY 2016

PREPARED FOR: D.R. LEMIEUX BUILDERS, INC.


2 Continental Blvd., Rochester, N.H. 603-335-3948

CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF PUMP CHAMBER, PUMP, AND CONTROL PANEL TO NORWAY PLAINS, ASSOCIATES, INC. PRIOR TO ORDERING AND DELIVERY.



ENGINEER APPROVAL REQUIRED PRIOR TO ORDERING

PLAN VIEW



PUMP STATION INSTALLATION NOTES:

1. THE PUMP STATION IS BEING INSTALLED IN AN AREA WITH POTENTIAL SEASONAL HIGH WATER TABLE EFFECTS. THE CONCRETE CHAMBER SHALL HAVE AN INTEGRAL FOOTING RING

- DURING INITIAL CONSTRUCTION, DEWATERING WILL BE NECESSARY IN THE HOLE FOR THE PUMP STATION. ONCE BACKFILLED, THERE SHOULD BE NO THREAT OF FLOATATION. THE PUMP STATION WET WELL SHALL BE CONSIDERED CLASS I, GROUP D, DIVISION 2 AND THE DRY WELL SHALL BE CONSIDERED CLASS I, GROUP D, UNCLASSIFIED PURSUANT TO THE 2012 NFPA TABLE 4.2 UNLESS OTHERWISE CLASSIFIED BY AUTHORITY HAVING JURISDICTION (AHJ). ALL ELECTRICAL COMPONENTS SHALL MEET ALL REQUIREMENTS OF THE NATIONAL ELECTRICAL CODES.
- (a) SUBMERSIBLE PUMPS FOR SEWAGE PUMPING STATIONS SHALL CONFORM TO THE NEC REQUIREMENTS ADOPTED BY REFERENCE IN THE STATE BUILDING CODE PÙRSUANT TO RSA 155—A:1, IV, FOR INSTALLATION IN AREAS CLASSIFIED BY THE NEC AS CLASS I, DIVISION 1. (b) ELECTRICAL SYSTEMS AND COMPONENTS, INCLUDING MOTORS, LIGHTS, CABLE, CONDUITS, SWITCH BOXES, AND CONTROL CIRCUITS SHALL BE PROTECTED FROM FLOODING IN ACCORDANCE WITH ENV-WQ 705.01. (c) ELECTRICAL SYSTEMS AND COMPONENTS INCLUDING MOTORS, LIGHTS, CABLE, CONDUITS, SWITCH BOXES AND CONTROL CIRCUITS IN ENCLOSED OR PARTIALLY
- ENCLOSED SPACES WHERE FLAMMABLE MIXTURES OCCASIONALLY MAY BE PRESENT, INCLUDING RAW SEWAGE WET WELLS, SHALL BE CERTIFIED BY THEIR MANUFACTURER (1) COMPLYING WITH THE NEC REQUIREMENTS ADOPTED BY REFERENCE IN THE STATE BUILDING CODE PURSUANT TO RSA 155-A:1, IV, FOR CLASS I, DIVISION
- LOCATIONS: OR (2) BEING RATED FOR CLASS I DIVISION 2 REQUIREMENTS WHERE MECHANICAL VENTILATION IS PROVIDED IN ACCORDANCE WITH THE NFPA AS ADOPTED BY RÉFERENCE IN THE STATE FIRE CODE IN SAF-C 6000.
- (d) ALL ELECTRICAL EQUIPMENT AND WORK SHALL COMPLY WITH THE REQUIREMENTS OF NEC AS ADOPTED BY REFERENCE IN THE STATE BUILDING CODE PURSUANT TO RSA 155—A:1, IV, AND NFPA AS ADOPTED BY REFERENCE IN THE STATE FIRE CODE IN SAF—C 6000 IN EFFECT AT THE TIME OF INSTALLATION.

## PUMP STATION DETAIL

31 Mooney Street, Alton, N.H. 603-875-3948

LOAM AREA | PAVED AREA

1. PIPES MAY BE INSTALLED BY EXCAVATING AN OPEN TRENCH WITH SIDE SLOPES OF 1:1

3. TRENCHES FOR SEWER PIPES WITH SLOPES OVER 0.08 FEET PER FOOT SHALL HAVE

SHEETING SHALL BE CUT OFF AND LEFT IN PLACE TO AN ELEVATION NOT LESS THAN ONE

MATERIALS, GRADED SUCH THAT 100 PERCENT PASSES A 1/2-INCH SIEVE AND A MAXIMUM OF

TRENCH DETAIL FOR

SEWER FORCE MAIN

NOT TO SCALE

IMPERVIOUS TRENCH DAMS CONSTRUCTED EVERY 300 FEET TO PREVENT POTENTIAL

FOOT ABOVE THE TOP OF THE PIPE AND AT LEAST 3 FEET BELOW FINISHED GRADE.

5. THE PIPE SAND BLANKET MATERIAL SHALL BE GRADED SAND FREE FROM ORGANIC

2. PIPE MATERIALS SHALL BE AS SPECIFIED ON THE DESIGN PLAN.

DISTURBANCE TO PIPE BEDDING AND BLANKET MATERIALS

DAILY FLOW BASED ON 77 GALLONS PER DAY PER CAPITA FOR ONE BEDROOM

APRARTMENT UNITS: (Env-Wq. 706.03 Table 3-2) AND ASSUMES MAXIMUM OF 2

DAILY FLOW BASED ON 150 GALLONS PER DAY PER BEDROOM FOR 2 BEDROOM

51 ONE BEDROOM UNITS X 77 GPD/CAPITA X 2 PERSON = 7,854 GPD

51 TWO BEDROOMS X 150 GPD/BEDROOM X 2 BEDROOMS = 15,300 GPD

MAXIMUM TO A DEPTH OF 4-FT. INTALLATIONS DEEPER THAN 4-FT REQUIRE THE USE OF A

4. WHERE SHEETING IS PLACED ALONGSIDE THE PIPE AND EXTENDS BELOW MID-DIAMETER, THE

-GRAVEL

5' MIN.

PUMP HEAD CALCULATIONS:

PUMP OFF ELEV. =

TOTAL DYNAMIC HEAD = 45.80 FT

PUMP INFORMATION:
PUMP = BARNES 2.5" SOLIDS HANDLING SEWAGE PUMPS

MODEL = 3SE2024L 2.0 HP WITH 7" IMPELLERS

STATIC HEAD =

STATIC HEAD =

TOTAL DYNAMIC HEAD:

PUMP OPERATIONAL = 60 GPM

RUN TIME = 19.6 MIN.

CAPACITY

CLEAN GRANULAR

FILL OR SUITABLE

MATERIAL FROM

MAXIMUM LIFTS

TRENCH EXCAVATION

3" SDR 11

HDPE FORCE MAIN

COMPACETED IN 8"

CLEAN GRANULAR-

FILL OR SUITABLE

TRENCH EXCAVATION

COMPACETED IN 12'

NON-METALIC-

WARNING TAPE

DIA.

UNDISTURBED -

15 PERCENT PASSES A #200 SIEVE.

PUMP STATION DESIGN CALCULATIONS:

UNITS: (Env-Wa. 1008.03 Table 1008-1)

INFILTRATION: 300 GAL./INCH DIA/MILE/DAY

INFILTRATION OF GRAVITY LINES = 155 GPD

TOTAL DAILY DESIGN FLOW = 23,309 GPD

WET WELL AND PUMP OPERATION NOTES:

HIGH WATER ALARM = 323.60

LAG PUMP ON = 323.10

LEAD PUMP ON = 322.60'

DEPTH OF PUMP = 3.00 FT

CHAMBER BOTTOM = 317.60'

SUBMERSION

DOSE DEPTH = 2.00 FT.

PUMP OFF = 320.60

INV. IN = 325.10

WET WELL INVERTS:

FILE NO. 104

F.B. NO.

PLAN NO. C-2780

DWG. NO. 15225/SP-2

340 FEET OF 8" DIA. PVC SEWER COLLECTION

DAILY FLOW:

PERSONS PER UNIT

SOIL

SAND BEDDING FOR


FULL WIDTH OF THE


TRENCH

TRENCH BOX.

MATERIAL FROM

MAXIMUM LIFTS






SEPTIC SYSTEM DESIGNERS LAND SURVEYORS




CIVIL ENGINEERS TRANSPORTATION PLANNERS

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE
GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH
IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.





12/28/16 - REVISED DETIALS PER NHDES





ONSITE FORCEMAIN AND OFFSITE GRAVITY PROFILE SCALE: 1" = 20' (HORZ.) 1" = 4' (VERT.)

FORCE MAIN PROFILE STA. 4+40 TO STA. 8+36 OFF SITE GRAVITY STA. 8+36 TO STA. 10+40 TAX MAP 134, LOT 5 114 ROCHESTER HILL RD. ROCHESTER, NH PREPARED FOR:

D.R. LEMIEUX BUILDERS, INC.

FILE NO. 104 PLAN NO. C-2780 DWG. NO. 15225/SP-2





Seed Mix A 50% New England Wetland Plants – Roadside Matrix Wet Meadow Seed Mix

Seed Mix A 50% @ 35lbs/acre Roadside Matrix Wet Meadow Seed Mix

Seed Mix B 35lbs/acre Erosion Control/Restoration Mix for Dry Sites

As recommended by seed provider

Seed Mix B 100% New England Wetland Plants – Erosion Control/Restoration Mix for Dry Sites

50% @ 35lbs/acre Erosion Control/Restoration Mix for Dry Sites

50% New England Wetland Plants – Erosion Control/Restoration Mix for Dry Sites

Tall fescue bluegrass mix, such as Pennington Smartseed Tall Fescue Bluegrass Mix – or

Seed Mixes

**Application Rates:** 

CIVIL ENGINEERS - TRANSPORTATION PLANNERS

## Gravel Wetlands Specifications

Products: Soil Mixes – see engineering specifications.
Seed Mixes – See above.
Mulch – Clean wed-free straw

**Preparation:** Gravel wetland seeding shall be installed in the Spring and well established prior to release of stormwater runoff into the wetland.

Examine finish surfaces, grades, soil quality, and depth. Do not start seeding work until unsatisfactory conditions are corrected in a manner acceptable to Owner.

Prior to seeding soils in the gravel wetland area shall be loosened to a depth of 4" MIN.

### Installation:

Do not hydroseed, apply with a mechanical spreader or by hand.

to mitigate compaction from construction processes.

Seed immediately after preparation.

Apply seed to clean bare soil.

Perform seeding operations when the soil is dry and when winds do not exceed 5 miles

Install seed evenly by sowing equal quantities in 2 directions, at right angle to each

Lightly rake or lightly roll to insure proper seed contact with the soil.

Mulch – A very light application of clean weed-free straw shall be applied to the finished

Contractor shall provide temporary irrigation for the seeding until a well -established stand of vegetation exists and approval is given by the Landscape Architect or Owner's representative.

Water daily to maintain adequate surface soil moisture for proper seed germination. Thereafter apply 1/2" of water twice weekly until acceptance. Continue daily watering for not less than 60 days.

Repair, rework, and re-seed all areas that have washed out, are eroded, or do not catch. Any part of seeded areas which fails to show a uniform stand shall be reseeded every twenty one days until areas are covered with established plants.

nspection: Landscape architect or owner's representative shall inspect seeding for establishment and coverage prior to release of stormwater runoff into the wetland. The gravel wetland requires a healthy stand of vegetation which must be established before the

stormwater is directed into the system.

Contractor shall overseed as needed to provide a well-established stand of wetland plants. Any and all weed species shall be removed as directed by the Landscape Architect or Owner's Representative.

**Warrantee**: Provide a uniform stand of vegetation by maintaining seeded areas as specified for 1 year after final acceptance. Reseed areas which fail to provide a uniform stand, with specified materials, until all affected areas are accepted by the Owner.

### Maintenance

The forebay must be cleaned when it accumulates to either six (6) inches or 10% of the

Wetlands vegetation must be harvested at least once every three years and no more frequently than once a year.

Biweekly inspections of vegetation health should be performed during the first growing season or until the vegetation is established. Once established, inspections of vegetation health, density, and diversity should be performed at least twice annually during both the growing and non-growing seasons. The vegetative cover must be maintained at 85 percent. If vegetation has greater than 50 percent damage, the area must be reestablished in accordance with the original specifications and the inspection requirements presented above.

The seeded areas around the perimeter of the gravel should be mowed at least once

### Landscape Notes

- Design is based on drawings by Norway Plains dated 5/10/2016 and may require adjustment due to actual field conditions.
   The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and
- 3. Erosion Control shall be in place prior to construction.
- 4. Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water
- bodies, Wetlands and/or drainage ways prior to any construction.

  5. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any
- discrepancies or changes in layout and/or grade relationships prior to construction.

  6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- 7. Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction
- materials or portalets within the tree protection area.

  8. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the
- Contractor.

  9. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call
- DIGSAFE at 1-888-344-7233.

  10. The Contractor shall procure any required permits prior to construction.
- 11. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings
- to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.

  12. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a contractor is aware of a potential issue, and does not bring it to the attention of the landscape architect or owner's
- representative immediately, they may be responsible for the labor and materials associated with correcting the problem.

  13. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building,
- 14. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- 15. All plants shall be legibly tagged with proper botanical name.
- The Contractor shall guarantee all plants for not less than one year from time of acceptance.
   Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard
- 18. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.19. All landscaping shall be provided with either of the following
- a. An underground sprinkling system
   b. An outside hose attachment within 150 feet

for all plants of the same species used in this work.

- 20. If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.21. All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant
- beds shall be prepared to a depth of 12" with 75% loam and 25% compost.

  22. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and ½" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be
- 23. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied
- mulch) over the root ball of any plant.

  24. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a
- height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy.

  25. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.

26. Landscape Architect is not responsible for the means and methods of the contractor.

## Plant List

Pachysandra terminalis

### TREE

Symbol	Botanical Name	Common Name	Quantity	Size	min	min	Comments
					height	width	
APPLE	Malua II ib artist	Liborty Apple	2	2-2.5" CAL.			ВВ
HAM	<i>M</i> alus 'Liberty' Hamamelis x intermedia "Arnold promise'	Liberty Apple Arnold Promise Witchhazel	2	2-2.5 CAL. 7-8' Ht			DD
BN	•	Heritage River Birch	4 4	7-6 ⊓t 7-8' Ht			
	Betula nigra 'Heritage'	•		7-6 Fit 7-8' Ht			
AM	Amelanchier x grandiflora 'Robin Hill'	Robin Hill Serviceberry	4				DD MATOUED
AR	Acer rubrum 'October Glory'	October Glory Red Maple	12	3-3.5" cal			BB MATCHED
JV	Juniperus virginiana	Eastern Red Cedar	8	7-8 Ht.			BB
MAG	Magnolia stellata	Star Magnolia	2	8-10'			BB
MAL	Malus 'Donald Wyman'	Donald Wyman Crabapple	4	2-2.5" CAL.			ВВ
PRY	Pyrus c. 'Cleveland Select'	Cleveland Select Flowering Pear	14	3-3.5" cal			ВВ
TH	Thuja plicata	Western Red Cedar	29	8-9' ht.			ВВ
UA	Ulmus americana 'Princeton'	Princeton American Elm	16	3-3.5" cal			ВВ
SHRUBS							
Symbol	Botanical Name	Common Name	Quantity	Size			Comments
ENK	Enkianthus campanulatus	Redvein Enkianthus	3	4-5' ht	4'	3'	ВВ
HYA	Hydrangea arborescens "Annabelle'	Annabelle Hydrangea	11	5 gal.	2'	2'	
HYE	Hydrangea macrophylla 'Endless Summer'	Endless Summer Hydrangea	13	3 gal.	18'	18"	
HYI	Hydrangea arborescens 'Incrediball'	Incrediball Hydrangea	13	3 gal.	18'	18"	
HYLL	Hydrangea 'Little Lime'	Little Lime Hydrangea	8	3 gal.	18'	18"	
IBM	Ilex meserve 'Blue Maid'	Blue Maid Holly (female conical)	2	4-5' ht.	4'	2.5'	BB
IG	Ilex glabra 'Shamrock'	Shamrock Inkberry	21	3 gal.	18'	18"	
JUN2	Juniperus chinensis 'Seagreen'	Seagreen Juniper	15	3 gal.	18"	24"	
JUN3	Juniperus chinensis 'Mountbatten	Mountbatten Juniper	4	5-6' ht.	5'	2'	
ROS	Rosa 'Knockout'	Knockout Rose Double Red	20	3 gal.	18'	18"	
SP	Spiraea x 'Goldmound'	Goldmound Spirea	40	3 gal.	18'	18"	
SPA	Spiraea x bumalda 'Anthony Waterer'	Anthony Waterer Spirea	19	3 gal.	18'	18"	
SYR1	Syringa meyeri 'Palibin'	Dwarf Korean Lilac	15	22.5'	24"	24"	ВВ
SYR2	Syringa 'Bloomerang'	Bloomerang Lilac	6	5 gal.	2 <del>4</del> "	2 <del>4</del> 24"	DD
TMT	Taxus media 'Tauntonii'	Taunton Yew	13	2-2.5'	2 <del>4</del> 24"	2 <del>4</del> 24"	ВВ
VPT		Marie's Doublefile Viburnum	10	2-2.5 3-4'ht.	24 3'	2 <del>4</del> 3'	ВВ
VPI	Viburnum plicatum tomentosum 'Mariesii'	Marie's Doubleille Viburnum	10	3 <del>-4</del> M.	3	3	ВВ
PERENNIA	ALS, GROUNDCOVERS, VINES and ANNUAL	LS					
Symbol	Botanical Name	Common Name	Quantity	Size			Comments

12 flats/100

-WETLANDS EDGE OF JURISDICTIONAL WETLANDS BY DELINEATED BY GARY FLAHERTY, CWS INFILTRATION Seed Mix "A" WETLANDS


GRAVEL WETLAND PLANTING & SEEDING

TAX MAP 134, LOT 5
114 ROCHESTER HILL RD
ROCHESTER, NH
PREPARED FOR:

D.R. LEMIEUX BUILDERS, INC.

JUNE 2016

GRAPHIC SCALE



FILE NO. 104 PLAN NO. C-2780 DWG. NO. 15225/SP-1 flats/100



### **Plant List**


Symbol	Botanical Name	Common Name	Quantity	Size	min	min	Comments
	Botaliloa Namo	- Common Name	- Quantity		height	width	-
APPLE	Malus 'Liberty'	Liberty Apple	2	2-2.5" CAL.			ВВ
HAM	Hamamelis x intermedia "Arnold promise"	Arnold Promise Witchhazel	4	7-8' Ht			
BN	Betula nigra 'Heritage'	Heritage River Birch	4	7-8' Ht			
ΑM	Amelanchier x grandiflora 'Robin Hill'	Robin Hill Serviceberry	4	7-8' Ht			
AR	Acer rubrum 'October Glory'	October Glory Red Maple	12	3-3.5" cal			BB MATCHE
JV	Juniperus virginiana	Eastern Red Cedar	8	7-8 Ht.			ВВ
MAG	Magnolia stellata	Star Magnolia	2	8-10'			ВВ
MAL	Malus 'Donald Wyman'	Donald Wyman Crabapple	4	2-2.5" CAL.			ВВ
PRY	Pyrus c. 'Cleveland Select'	Cleveland Select Flowering Pear	14	3-3.5" cal			ВВ
TH	Thuja plicata	Western Red Cedar	29	8-9' ht.			BB
UA	Ulmus americana 'Princeton'	Princeton American Elm	16	3-3.5" cal			ВВ
HRUBS							
Symbol	Botanical Name	Common Name	Quantity	Size			Comments
ENK	Enkianthus campanulatus	Redvein Enkianthus	3	4-5' ht	4'	3'	ВВ
HYA	Hydrangea arborescens "Annabelle'	Annabelle Hydrangea	11	5 gal.	2'	2'	
HYE	Hydrangea macrophylla 'Endless Summer'	Endless Summer Hydrangea	13	3 gal.	18'	18"	
HYI	Hydrangea arborescens 'Incrediball'	Incrediball Hydrangea	13	3 gal.	18'	18"	
HYLL	Hydrangea 'Little Lime'	Little Lime Hydrangea	8	3 gal.	18'	18"	
IBM	Ilex meserve 'Blue Maid'	Blue Maid Holly (female conical)	2	4-5' ht.	4'	2.5'	ВВ
IG	llex glabra 'Shamrock'	Shamrock Inkberry	21	3 gal.	18'	18"	
JUN2	Juniperus chinensis 'Seagreen'	Seagreen Juniper	15	3 gal.	18"	24"	
JUN3	Juniperus chinensis 'Mountbatten	Mountbatten Juniper	4	5-6' ht.	5'	2'	
ROS	Rosa 'Knockout'	Knockout Rose Double Red	20	3 gal.	18'	18"	
SP	Spiraea x 'Goldmound'	Goldmound Spirea	40	3 gal.	18'	18"	
SPA	, Spiraea x bumalda 'Anthony Waterer'	Anthony Waterer Spirea	19	3 gal.	18'	18"	
SYR1	Syringa meyeri 'Palibin'	Dwarf Korean Lilac	15	22.5'	24"	24"	ВВ
SYR2	Syringa 'Bloomerang'	Bloomerang Lilac	6	5 gal.	24"	24"	
	• •	<del>-</del>		2-2.5'	24"		ВВ
TMT	Taxus media 'Tauntonii'	Taunton Yew	13	2-2.5	24	24"	BB

### PERENNIALS, GROUNDCOVERS, VINES and ANNUALS


P Pachysandra terminalis

Symbol	Botanical Name	Common Name	Quantity	Size	Comments

Japanese Spurge



## Tree Planting Detail, Typ.



such that the trunk flare is visible at the top of the root ball. Shrubs where the trunk flare is not visible may be rejected. 100 mm (4 in.) high earth saucer beyond edge of root

–100 mm (4 in.) max mulch outside the saucer between shrubs in a bed. Maintain the mulch weed—free for a minimum of three years after

-Backfill with existing soil, in sandy and heavy clay soils add 20% max. by volume composted organic material to the existing soil. –Remove all twine, rope, wire, and burlap from top half of root ball

Shrub Planting Detail, Typ.

F.B. NO. 31 Mooney Street, Alton, N.H. 603-875-3948

| PLAN NO. C-2780

DWG. NO. 15225/SP-1

NORWAY PLAINS ASSOCIATES, INC. 2 Continental Blvd., Rochester, N.H. 603-335-3948


(IN FEET) 1 INCH = 20 FEET


L-3


Vpt(2) -TmT(5)TmT(8)Vpt(2) -Syr2(2)HyE(3) - $(\mathbf{x})$ ×

> FOUNDATION LANDSCAPE PLAN TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH PREPARED FOR:

D.R. LEMIEUX BUILDERS, INC. JUNE 2016 GRAPHIC SCALE











# ROADWAY IMPROVEMENT PLANS

FOR

# APPLE RIDGE ESTATES, LLC 114 ROCHESTER HILL ROAD ROCHESTER, N.H. 03867 SEPTEMBER 2016





OVERALL SITE 1" = 200'

NORWAY PLAINS ASSOCIATES, INC. 2 CONTINENTAL BOULEVARD ROCHESTER, NEW HAMPSHIRE 03867 (603) 335-3948

CIVIL ENGINEERS

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.

> OWNER OF RECORD TAX MAP 134, LOT 5 OWNER OF RECORD: ROCHESTER HILL HOLDINGS, LLC 76 EXETER ROAD NEWMARKET, NH 03857 SCRD BOOK 4552, PAGE 648

## APPLICANT


DR LEMIEUX BUILDERS, INC. 76 EXETER ROAD NEWMARKET, NH 03857

SHEET INDEX SHEET DOT-0 COVER 1" = 200'SHEET DOT-1 STANDARD LEGEND AND SYMBOLS AS SHOWN SHEET DOT-2 STANDARD LEGEND AND SYMBOLS AS SHOWN 1" = 100'SHEET DOT-4 EXISTING FEATURES PLAN 1" = 50'SHEET DOT-5 ROADWAY IMPROVEMENT PLAN 1" = 50'1" = 50'SHEET DOT-6 PAVEMENT MARKING AND SIGNAGE PLAN SHEET DOT-7 DRIVEWAY IMPROVEMENT PLAN AND PROFILE AS SHOWN SHEET DOT-8 ROADWAY PROFILE AND TYPICAL CROSS SECTIONS AS SHOWN SHEET DOT-9 CROSS SECTIONS 1" = 10' SHEET DOT-10 CROSS SECTIONS 1" = 10' SHEET DOT-11 CROSS SECTIONS 1" = 10' SHEET DOT-12 CROSS SECTIONS

FILE NO. 104 PLAN NO. C-2780 DWG. NO. 15225/SP-2

F.B. NO.







31 Mooney Street, Alton, N.H. 603-875-3948



**UTILITIES DRAINAGE TRAFFIC SIGNALS PROPOSED** existing PROPOSED existing TELEPHONE POLE MANHOLE POWER POLE ⊡cb CATCH BASIN (PROPOSED) (existing) MAST ARM (existing) (plot point at face JOINT OCCUPANCY ⊡ di DROP INLET (NOTE ANGLE FROM B) not center of symbol) OPTICOM RECEIVER MISCELLANEOUS/UNKNOWN POLE (label size & type) -DRAINAGE PIPE (existing) OPTICOM STROBE GUY POLE OR PUSH BRACE DRAINAGE PIPE (PROPOSED) 0 LIGHT POLE TRAFFIC SIGNAL (label size show & type) direction UNDERDRAIN (PROPOSED) of flow - W/ FLUSHING BASIN LIGHT ON POWER POLE PEDESTAL WITH PEDESTRIAN SIGNAL Q<u>.</u> ⊞ **HEADS AND PUSH BUTTON UNIT** with stone outlet protection) LIGHT ON JOINT POLE HEADER (existing & PROPOSED) SIGNAL CONDUIT METAL OF PLASTIC POLE STATUS: END SECTION (existing & PROPOSED) REMOVE, LEAVE, PROPOSED, OR TEMPORARY ⊠cc  $\boxtimes CC$ CONTROLLER CABINET AS APPLICABLE e.g.: **⊠** MP OPEN DITCH (PROPOSED) ⊠ mp METER PEDESTAL RAILROAD (label ownership)  $\square$  PB □ pb EROSION CONTROL/ STONE PULL BOX RAILROAD SIGN SLOPE PROTECTION  $\infty$ r-----**DO** RAILROAD SIGNAL LOOP DETECTOR (QUADRUPOLE) F-----'----i **BOUNDARIES / RIGHT-OF-WAY** (label size) ⊠jb ⊠JB UTILITY JUNCTION BOX -----1 LOOP DETECTOR (RECTANGULAR) (label type) RIGHT-OF-WAY LINE (label size) OVERHEAD ELECTRIC RR RIGHT-OF-WAY LINE PROPERTY LINE **UNDERGROUND UTILITIES CONSTRUCTION NOTES** (on existing lines label size, type and note if abandoned) PROPERTY LINE (COMMON OWNER) CURB MARK NUMBER - BITUMINOUS B-1 TOWN LINE SEWER COUNTY LINE CURB MARK NUMBER - GRANITE G-1 TELEPHONE STATE LINE NEW HAMPSHIRE CLEARING AND GRUBBING AREA ELECTRIC NATIONAL FOREST DRAINAGE NOTE LCHIP CONSERVATION EASEMENT BENCH MARK / SURVEY DISK EROSION CONTROL NOTE LIGHTING BOUND (PROPOSED) INTELLIGENT TRANSPORTATION SYSTEM FENCING NOTE STATE LINE/ TOWN LINE MONUMENT · S/L • T/L FIBER OPTIC GUARDRAIL NOTE NHDOT PROJECT MARKER **WATER SHUT OFF** LIGHTING NOTE IRON PIPE OR PIN GAS SHUT OFF DRILL HOLE IN ROCK TRAFFIC SIGNAL NOTE **HYDRANT** ₩0 **MANHOLES** SHEET 2 OF 2 (156 14 SEWER TAX MAP AND LOT NUMBER STATE OF NEW HAMPSHIRE 1642/341 TELEPHONE MHT DEPARTMENT OF TRANSPORTATION . BUREAU OF HIGHWAY DESIGN 6.80 Ac.± ELECTRICAL STANDARD SYMBOLS PROPERTY PARCEL NUMBER HISTORIC PROPERTY UNKNOWN REVISION DATE STATE PROJECT NO. SHEET NO. TOTAL SHEETS 10-25-11 stdsymb1\_2

31 Mooney Street, Alton, N.H. 603-875-3948





LAND SURVEYORS SEPTIC SYSTEM DESIGNERS **CIVIL ENGINEERS** TRANSPORTATION PLANNERS **LEGEND** PROPERTY LINE CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. ..... EXISTING TREE LINE SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE EXISTING STONEWALLS No. 10026 GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN ---258 ----- EXISTING CONTOUR LINE THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS EXISTING DRAIN LINE ASSOCIATES, INC. (603)-335-3948. - EXISTING OVERHEAD WIRES EXISTING WATER LINE 09/21/16 ADD EXISTING LANE MARKINGS AND DISTANCES FROM PROPOSED PAVEMENT TO UTILITY POLES EXISTING SEWER LINE 11/30/16 REVISE PROPOSED WIDEN SHOULDER WIDTH AND TAPER EXISTING UTILITY POLE LENGTH AS REQUESTED BY NHDOT DISTRICT 6 ENGINEER EXISTING SEWER MANHOLE EXISTING MONUMENT PROPOSED EDGE OF PAVEMENT W/ CURB PROPOSED EDGE OF PAVEMENT PROPOSED SIGN MAP 134 LOT 36 DOSTIE FAMILY MAP 134 LOT 46 PEASE FAMILY TRUST REVOCABLE TRUST 107 ROCHESTER HILL RI 103 ROCHESTER HILL RD MAP 134 LOT 21 I HEART MEADIA TOWER CO I LLC ROCHESTER, NH 03867 ROCHESTER, NH 03867 O ROCHESTER HILL RD ROCHESTER, NH 03867 / RIM = 361.1'MAP 134 LOT 23 CORNOCK, ROBERT DRIVE CENTER / INV. IN = 353.3'/ INV. OUT = 353.1'111 ROCHESTER HILL RD
ROCHESTER, NH 03867

FRAME & COVER
REPLACE WITH TYPE B-ALT
FRAME AND COVER -350' TAPER FOR 35mph ZONE-FRAME AND COVER EXIST. TYPE C-EXIST. & SEWER  $RIM = 361.1'_{7}$ FRAME & COVER
REPLACE WITH TYPE B-ALT MAP 134 LOT 47 YORK, SALLY L. 1252 FRANKLIN PIERCE HGWY TOP=364.6' -APPROX. DI = 363.5'CATCH BASIN LOCATION APPROX. LOCATION INV IN.=359.0' BARRINGTON, NH 03825 ₹0P=362.0° TOP=359.9' DI=358.7' INV. OUT=358.8' T EXIST. POLE DRAIN LINE RIM = 359.9'EV#1/69 INV. IN=356.3' EV#1/68 INV. OUT=357.8' INV. IN =352.2'  $\setminus$ EV#921\_ NET#223 POLE EV#1/64 JNV. OUT=356.1'🛱 NET#224 INV. IN =352.2' OF 12" RCP DRAIN LINE INV. OUT =351.1SLOPE LIMITS EXIST. EDGE OHWOF PAVEMENT EXIST. EDGE OF PAVEMENT L21.3' +70.9 L21.4' PROP. PAVED -362-SSL (W) PROP. 10' PAVED PROP. SAW-NH ROUTE 108 ROCHESTER HILL ROAD BYPASS SHOULDER EXIST. EXIST. ---366---DOUBLE E SEWER EXIST. SMH MAIN RIM = 360.5' EXIST. EDGE -OF PAVEMENT EXIST. POLE EXIST. OF PAVEMENT EV#1/63A1 INV=335.5' RIM = 362.4'INV. IN =349.8' (E) MAP 134 LOT 4 FP#229S INV. IN (S) = 353.4' MAP INV. IN =350.1VARNEY, HOLLIS & KAREN INV. IN (E) = 351.6INV. OUT =349.7' 110 ROCHESTER HILL RD ROCHESTER, NH 03867 HOUSE DRIVEWAY MAP 134 LOT 9
DECOWSKE, JOHN & PATRICIA MAP 134 LOT 6
MASSE DAVID P & MICHELLE L/
118 ROCHESTER HILL RD
ROCHESTER, NH 03867 18 MOUNTAIN VIEW LANE ROCHESTER, NH 03867 MAP 239 LOT 107 GREYSTONE OF MAINE LTD 334 ROUTE 108 MADBURY, NH 03823 MAP 134 LOT 3 JOHNSON, JOSEPH L PO BOX 1701 ROCHESTER, NH 03866 MAP 134 LOT 1 SEVEY, MICHAEL 2 DORA DRIVE MAP 134 LOT 7
PHILLIPS, PAUL R JR & LEE A
122 ROCHESTER HILL RD
ROCHESTER, NH 03867 ROCHESTER, NH 03867 PAVED / P MAP 134 LOT 8 FERLAND, JOHN & KIMBERLY 124 ROCHESTER HILL RD ROCHESTER, NH 03867 MAP 134 LOT 10
NELSON, MICHAEL & MICHELLE
PO BOX 2054
ROCHESTER, NH 03867 MAP 134, LOT 2 BRETON, DONALD 3 DORA DR ROCHESTER, NH 03867 MAP 239 LOT 122 LEMIEUX, DAVID R PO BOX 1163 ROCHESTER, NH 03866 TAX MAP 134, LOT 5 OWNER OF RECORD: ROCHESTER HILL HOLDINGS, LLC 76 EXETER ROAD NEWMARKET, NH 03857 SCRD BOOK 4552, PAGE 648 ROADWAY IMPROVEMENT PLAN TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH PREPARED FOR: D.R. LEMIEUX BUILDERS, INC. MAY 2016 GRAPHIC SCALE "APPLE RIDGE ROCHESTER HILL ROAD, ROCHESTER NEW HAMPSHIRE" DATED: JANUARY 3, 2005, REV.

1 INCH = 50 FEET

2)"LOT LINE ADJUSTMENT PLAN LOTS 5 & 6, TAX ASSESSOR'S MAP 134, ROCHESTER HILL ROAD,


ROCHESTER, NEW HAMPHIRE, COUNTY OF STRAFFORD". SCALE 1'=100'; DATED: JANUARY 11, 2002, REV. TO 2-11-2002; BY CIVILWORKS, INC. RECORDED S.C.R.D. PLAN 64-76.


FILE NO. 104

F.B. NO.

PLAN NO. C-2780

DWG NO. 15225\SP−1





LAND SURVEYORS SEPTIC SYSTEM DESIGNERS




CIVIL ENGINEERS TRANSPORTATION PLANNERS

> CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.




THE TYPICAL CROSS SECTION. ADD CATCH BASIN FRAME AND GRATE DETAILS. 01/24/16 REVISE TYPICAL CROSS SECTION PAVEMENT DEPTHS



## ROADWAY PROFILE

SCALE: 1" = 50' (HORZ.) 1" = 5' (VERT.)

CONSTRUCTION




## TYPICAL CROSS SECTION

STA. 3+33.1 TO 7+43.0 (LT.)

SCALE: 1" = 5

- 1. SAW CUT PAVEMENT AT ONE FOOT INSIDE OF THE EXISTING EDGE OF PAVEMENT. 2. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE NHDOT "STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION", LATEST EDITION, AND THE
- "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES." 3. ALL DISTURBED SLOPES SHALL BE LOAMED AND SEEDED AS SHOWN.



SLAB TO BE PLACED IN LIEU OF TAPERED SECTION WHERE PIPE WOULD OTHERWISE ENTER INTO TAPERED SECTION OF THE STRUCTURE AND WHERE PERMITTED.

## REINFORCED CONCRETE SLAB COVER

NOT TO SCALE



FLOW LINE THIS FLANGE
EXCLUDED FOR
3 FLANGE FRAME

ROADWAY PROFILE AND TYPICAL CROSS SECTION TAX MAP 134, LOT 5 114 ROCHESTER HILL RD ROCHESTER, NH

PREPARED FOR: D.R. LEMIEUX BUILDERS, INC.

MAY 2016

FILE NO. 104 PLAN NO. C-2780 DWG. NO. 15225/SP-2 F.B. NO.


31 Mooney Street, Alton, N.H. 603-875-3948

INORWAY PLAINS ASSOCIATES, INC.


2 Continental Blvd., Rochester, N.H. 603-335-3948

DOT-8

LAND SURVEYORS SEPTIC SYSTEM DESIGNERS CIVIL ENGINEERS TRANSPORTATION PLANNERS CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION.
SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT
BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE
GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH
IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN
THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948. 11/23/16 - REVISE PROPOSED PAVEMENT WIDTH AND FILL SLOPES APPROX. LOCATION OF 15 4+00 LOCATION OF EXIST. 12" RCP 10 | 15 | 20 12.2 16.9 APPROX. LOCATION OF EXIST. 12" RCP EXIST. POLE STA. 2+76.4 LEFT 39.8' ROADWAY CROSS SECTIONS TAX MAP 134, LOT 5 12.3 17.2 114 ROCHESTER HILL RD ROCHESTER, NH FILE NO. 104 PREPARED FOR: D.R. LEMIEUX BUILDERS, INC. PLAN NO. C-2780 MAY 2016 DWG. NO. 15225/SP-2 1 INCH = 10 FEETF.B. NO. NORWAY PLAINS ASSOCIATES, INC. 2 Continental Blvd., Rochester, N.H. 603-335-3948 31 Mooney Street, Alton, N.H. 603-875-3948



31 Mooney Street, Alton, N.H. 603-875-3948



LAND SURVEYORS SEPTIC SYSTEM DESIGNERS CIVIL ENGINEERS TRANSPORTATION PLANNERS CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION.
SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT
BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948. 11/23/16 - REVISE PROPOSED PAVEMENT WIDTH AND FILL SLOPES 09/21/16 - ADD UTILITY POLE LOCATIONS TO CROSS SECTIONS 10 15 20 25 11.8 16.5 9+00 LOCATION OF | 15 17.0 15 EXIST. POLE STA. 8+11.8 LEFT 34.9' APPROX. LOCATION OF EXIST. 12" RCP HENRIETTA STREET APPROX. LOCATION OF ROADWAY CROSS SECTIONS 10 15 20 25 30 35 12.1 16.8 33.2 TAX MAP 134, LOT 5 114 ROCHESTER HILL RD EXIST. POLE STA. 7+42.2 LEFT 36.0' ROCHESTER, NH FILE NO. 104 PREPARED FOR: D.R. LEMIEUX BUILDERS, INC. PLAN NO. C-2780 MAY 2016 DWG. NO. 15225/SP-2 1 INCH = 10 FEETNORWAY PLAINS ASSOCIATES, INC. 2 Continental Blvd., Rochester, N.H. 603-335-3948 31 Mooney Street, Alton, N.H. 603-875-3948