


MAJOR SUBDIVISION APPLICATION

(a total of four or more lots)

City of Rochester, New Hampshire



Date: July 8, 2019	Is a conditional needed? Ves: No. Y Undown
Date. day o, 2010	Is a conditional needed? Yes: No: X Unclear: (If so, we encourage you to submit an application as soon as possible.)
Property information	contract you so busined an application as possible.)
	#('s): 54-1 ; Zoning district: Agricultural
	410 Old Davies Barri B. 1 . 1 . 1111
Name of project (if applicable	
	e): Addison Estates Phase II Overlay zoning district(s)?
Property owner	Overlay 2011ing district(s)?
Name (include name of indiv	vidual): Donald & Bonnie Toy
	Drive, Rochester NH 03867
Telephone #: 603-335-2276	Email: Harleysdadtoy@aol.com
Applicant/developer (if	different from property owner)
Name (include name of indiv	vidual): Same
Mailing address:	
Telephone #:	Email:
Telephone #: Engineer/surveyor	Email:
Telephone #: Engineer/surveyor	Email:
Engineer/surveyor Name (include name of indiv	ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering Crown Point Road
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #:
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863 Email address: k.berry@berrysun	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering Crown Point Road
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #:
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863 Email address: k.berry@berrysun Proposed project	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #:
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863 Email address: k.berry@berrysurv Proposed project Number of proposed lots: 14	Email: vidual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #: veing.com, crberry@metrocast.net Professional license #: 14243
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863 Email address: k.berry@berrysurv Proposed project Number of proposed lots: 14 Number of cubic yard of eart	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #: reing.com, crberry@metrocast.net Professional license #: 14243 ; estimated length of new roads: 1,300 Ft. th being removed from the site? Fill Only
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863 Email address: k.berry@berrysurv Proposed project Number of proposed lots: 14 Number of cubic yard of eart City water? yes X no	Email: vidual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #: veing.com, crberry@metrocast.net Professional license #: 14243 ; estimated length of new roads: 1,300 Ft.
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863 Email address: k.berry@berrysun Proposed project Number of proposed lots: 14 Number of cubic yard of eart City water? yes X no C City sewer? yes no X	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #: reing.com, crberry@metrocast.net Professional license #: 14243 ; estimated length of new roads: 1,300 Ft. th being removed from the site? Fill Only ; How far is city water from the site? On site, Lot 53 ; How far is city sewer from the site? Proposed septic systems (sewer is over a mile away)
Engineer/surveyor Name (include name of indiv Mailing address: 335 Second C Telephone #: 603-332-2863 Email address: k.berry@berrysun Proposed project Number of proposed lots: 14 Number of cubic yard of eart City water? yes X no C City sewer? yes no X If city water, what are the est	Email: ridual): Christopher R. Berry, Kenneth Berry (PE, LLS), Berry Surveying & Engineering crown Point Road Fax #: reing.com, crberry@metrocast.net Professional license #: 14243 ; estimated length of new roads: 1,300 Ft. th being removed from the site? Fill Only ; How far is city water from the site? On site, Lot 53

Page 1 (of 2 pages)

Updated 3/27/2019

Wetlands: Is any fill proposed? N/A; area to be filled: N/A; buffer impact? N/A
Comments
Please feel free to add any comments, additional information, or requests for waivers here:
Applicant is proposing to construct Phase II of Addison Estates. This will include the construction if a 1,300 foot
roadway (1,000 LF to the neck), as well as merging Lots 53 & 54-1 so that all of Addison Estates is on one lot.
100 the fleck), as well as filerging Lots 33 & 34-1 so that all of Addison Estates is on one lot.
Submission of application This application must be signed by the property owner, applicant/developer (if different from property owner), <i>and/or</i> the agent.
I(we) hereby submit this Subdivision application to the City of Rochester Planning Board pursuant to the <u>City of Rochester Subdivision Regulations</u> and attest that to the best of my knowledge all of the information on this application form and in the accompanying application materials and documentation is true and accurate. As applicant/developer (if different from property owner)/as agent, I attest that I am duly authorized to act in this capacity. Signature of property owner.
Date: 7/8/2019
Signature of applicant/developer:
Date: 7/8/2019
Signature of agent:
Date: 7/8/2019
Authorization to enter subject property
I hereby authorize members of the Rochester Planning Board, Zoning Board of Adjustment, Conservation Commission, Planning Department, and other pertinent City departments, boards and agencies to enter my property for the purpose of evaluating this application including performing any appropriate inspections during the application phase, review phase, post-approval phase, construction phase, and occupancy phase. This authorization applies specifically to those particular individuals legitimately involved in evaluating, reviewing, or inspecting this specific application/project. It is understood that these individuals must use all reasonable care, courtesy, and diligence when entering the property. Signature of property owner:
Date: 7/8/2019
Page 2 (of 2 pages)

\roch-fileshare\plan\$\Forms\Applications\Major Subdivision	.doc
---	------

Updated 3/27/2019



BERRY SURVEYING & ENGINEERING

335 Second Crown Point Road Barrington, NH 03825 Phone: (603) 332-2863 Fax: (603) 335-4623 www.BerrySurveying.Com

July 8, 2019

City of Rochester Planning Department Attention Chief Planner Seth Creighton 33 Wakefield Street Rochester, NH 03867

RE: Mobile Home Subdivision "Project Narrative"

Donald & Bonnie Toy Addison Estates Phase II

418 Old Dover Road, Rochester, NH 03867

Seth,

On behalf of Donald & Bonnie Toy, Berry Surveying & Engineering (BS&E) is filing a subdivision application for Tax Map 256, Lot 54-1.

Background

Donald & Bonnie Toy own the parcel known as Tax Map 256, Lot 54-1. Berry Surveying and Engineering has been on site and has conducted a full topographic analysis. A wetlands analysis has also been conducted by Stoney Ridge Environmental. All onsite wetlands have been flagged. The front of the site is open and gradually slopes downhill towards the rear of the site, where it is fully wooded. In 2016 a variance was granted to allow this project to move forward using chapter 43 of the Rochester Zoning Ordnance.

Proposal

The proposal is to subdivide Lot 54-1 into 14 mobile home lots. This mobile home subdivision will become part of Addison Estates. As part of the subdivision, a road will be constructed off Alexandra Lane, known as Loren Way. This proposed roadway will provide access to the new subdivision. The proposed roadway will 22' wide, with 25' wide cul-de-sac lane, in order to provide emergency vehicles with ample room to access the site.

The proposed subdivision will be serviced by City Water and onsite septic systems. There is an existing water main in Alexandra Lane which will service the

1			

Project Narrative Donald & Bonnie Toy, Old Dover Road, Rochester

July 8, 2019 Page 2 of 2

proposed subdivision, which is provided by Somersworth. The lots will be serviced by individual septic systems. The houses are proposed to be 2 bedroom and age restricted to 55 years or older. The lots will be leased.

A full drainage analysis was done as part of this design and is included in the submission. The site will utilize mostly open drainage, featuring roadside swales and driveway culverts. These swales and culverts will divert the generated runoff to 4 proposed rain gardens. These rain gardens will serve to capture, treat and in some cases re-infiltrate the generated runoff using layers of stone and a bio-media mix.

All proper erosion and sediment control measures will be taken throughout the construction process to ensure that no sediment runs off into the onsite wetlands or abutting properties. A construction entrance will be installed prior to any earth disturbing activities, to prevent sediment tracking onto Alexandra Lane. Perimeter control will be used at the edge of disturbance and along the rain gardens to contain sediment and prevent it from going beyond the limits of construction.

As part of the subdivision application, the applicant is also proposing a lot merger to merge Lots 53 & 54-1. Doing this will allow for all of Addison Estates to be on one lot. In addition, the applicant is also filing for a NHDOT permit and an NHDES Subdivision application, among others. All approved permits will be provided to the City when acquired.

Respectfully Submitted,

BERRY SURVEYING & ENGINEERING

James/F. Hayden

Engineering Technician

Christopher Berry


Principal President




BERRY SURVEYING & ENGINEERING 335 Second Crown Pt. Rd., Barrington, NH 03825


(603) 332-2863 / (603) 335-4623 FAX www.BerrySurveying.Com


www.BerrySurveying.Com








SHEET 1 OF 35


























CHAPTER 43 MOBILE PARK HOME ORDINANCE

LOT COVERGE SHALL NOT EXCEED 35%

LOT COVERGE HOUSE SIZE/LOT 5122

LOT 54-1-1 = (2098 Sq.Ft./11,222 Sq.Ft.) = 18.7%

LOT 54-1-2 = (2098 Sq.Ft./11,3207 Sq.Ft.) = 18.8%

LOT 54-1-3 = (2098 Sq.Ft./13,307 Sq.Ft.) = 15.8%

LOT 54-1-4 = (2098 Sq.Ft./13,307 Sq.Ft.) = 18.5%

LOT 54-1-4 = (2098 Sq.Ft./13,307 Sq.Ft.) = 18.5%

LOT 54-1-6 = (2098 Sq.Ft./10,425 Sq.Ft.) = 20.1%

LOT 54-1-6 = (2098 Sq.Ft./10,819 Sq.Ft.) = 19.4%

LOT 54-1-7 = (2098 Sq.Ft./10,919 Sq.Ft.) = 18.9%

LOT 54-1-8 = (2098 Sq.Ft./12,905 Sq.Ft.) = 16.3%

LOT 54-1-10 = (2098 Sq.Ft./12,905 Sq.Ft.) = 10.7%

LOT 54-1-10 = (2098 Sq.Ft./15,060 Sq.Ft.) = 10.7%

LOT 54-1-10 = (2098 Sq.Ft./15,060 Sq.Ft.) = 10.7%

LOT 54-1-10 = (2098 Sq.Ft./17,19,97 Sq.Ft.) = 10.7%

LOT 54-1-11 = (2098 Sq.Ft./17,19,97 Sq.Ft.) = 16.5%

LOT 54-1-13 = (2098 Sq.Ft./15,960 Sq.Ft.) = 16.5%

LOT 54-1-14 = (2098 Sq.Ft./15,146 Sq.Ft.) = 13.8%

33.) IF REQUIRED, SNOW SHALL BE REMOVED TO AN APPROVED LOCATION. SNOW STORAGE SHALL NOT IMPEDE DRAINAGE. PAYMENT COVERAGE: 83,385 Sq. Ft. SNOW STORAGE: 13,594 Sq. Ft. 8:1 RATIO PROVIDED

34.) WRITTEN DIMENSION ON THIS PLAN TAKE PRECEDENCE OVER SCALED DIMENSIONS. THE CONTRACTOR SHALL USE CAUTION WHEN SCALING REPRODUCED PLANS, IN THE EVENT OF A CONFLICT BETWEEN THIS PLAN SET AND ANY OTHER DRAWINGS AND/OR SPECIFICATIONS, THE ENGINEER SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION, CONTRACTOR IS TO CONFIRM ALL ELEVATIONS, CONFLICTS WILL BE REPORTED TO THE DESIGN ENGINEER PRIOR TO CONSTRUCTION.

36.) PROPOSED ROADWAY, ROADSIDE SWALES AND RAIN GARDENS ARE TO BE FULLY CONSTRUCTED AND STABILIZED PRIOR TO RESIDENTIAL LOT CONSTRUCTION.

35.) SEE CONSTRUCTION DETAILS FOR LIGHTING CUT SHEETS.

16.) THE LIMITS OF CONSTRUCTION DISTURBANCE SHALL BE STAKED, FLAGGED AND CLEARLY IDENTIFIED PRIOR TO THE COMMENCEMENT OF SITE WORK. 17.) ALL TREATMENT SWALES TO BE CONSTRUCTED SHALL HAVE SOD BOTTOMS.

18.) A LETTER OF CREDIT FOR THE COST OF RE-VEGETATING ALL TO BE DISTURBED AREAS ON THE SITE SHALL BE SUBMITTED PRIOR TO ANY EARTH DISTURBING ACTIVITY OCCURS. COORDINATE WITH THE CITY OF ROCHESTER DEPARTMENT OF PLANNING & DEPARTMENT OF PUBLIC WORKS. 19.) A PRE-CONSTRUCTION CONFERENCE WITH THE DEVELOPER, THE DESIGN ENGINEER, THE EARTHWORK CONTRACTOR, AND THE TECHNICAL STAFF SHALL OCCUR PRIOR TO ANY EARTH DISTURBING ACTIVITY.

BUILDING ADDRESSES SHALL BE ASSIGNED BY THE ASSESSING DEPARTMENT AT THE TIME OF ISSUANCE OF A BUILDING PERMIT.

21.) THE FOLLOWING FEDERAL AND STATE PERMITS HAVE BEEN ISSUED FOR THE SUBJECT PROPERTY:

23.) ALL CONSTRUCTION SHALL CONFORM TO THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION DATE 2016. CONSTRUCTION SHALL ALSO CONFORM TO THE CITY OF ROCHESTER POLICIES AND PRACTICES. EXTERIOR LIGHTING SHALL BE CUT-OFF TYPE FIXTURES AND SHALL PROVIDE LIGHTING DIRECTED ON-SITE ONLY.

 THE PROPOSAL IS TO CONSTRUCT 14, 2 BEDROOM MOBILE HOMES WITH GARAGES/ 2 ADDITIONAL SPACES PROVIDED IN THE DRIVEWAY. FINAL UTILITY LOCATIONS TO BE COORDINATED BETWEEN THE CONTRACTOR, ALL APPROPRIATE UTILITY COMPANIES AND THE ROCHESTER DPW. CONTRACTOR TO CONTACT ROCHESTER DPW A MINIMUM OF TWO WEEKS PRIOR TO ANY
CONSTRUCTION TO COORDINATE ALL WORK CONCERNING INSTALLATION OF ANY PROPOSED
WATER LINE IMPROVEMENTS AS MAY BE REQUIRED.


22). THIS PLAN PROPOSES APPROXIMATELY 88,000 SQ. FT. OF DISTURBANCE.


PROPERTY:
EPA NOTICE OF INTENT (NOI): (PENDING)
NHDES SUBDIMISON APPROVAL: (PENDING)
NHDOT DRIVEWAY PERMIT: (PENDING)
DIVISION OF HISTORICAL RESOURCES: (PENDING)
NATURAL HERITAGE BUREAU: (PENDING)


S & S BE



SHEET 11 OF 35







- 5.) THE INTENT OF THIS PLAN IS TO PROVIDE AN OVERVIEW GRADING AND ENGINEERING DETAIL OF LOREN WAY.
- 6.) EXISTING CONDITIONS INFORMATION IS BASED ON A SURVEY PERFORMED BY BERRY SURVEYING & ENGINEERING AND IS ENCLOSED IN THIS PACKAGE.
- 7.) ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL CONFORM TO CITY OF ROCHESTER SUBDIVISION REGULATIONS AND THE LATEST EDITION OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATION'S FOR ROAD & BRIDGE CONSTRUCTION.
- 8.) AS-BUILT PLANS OF THE SITE SHALL BE SUBMITTED ON A REPRODUCIBLE MYLAR MEDIUM AND IN A DIGITAL DXF FORMAT ON DISK TO THE GITY OF ROCHESTER UPON COMPLETION OF PROJECT, AS-BUILT PLANS SHALL BE PREPARED AND CERTIFIED CORRECT BY A LLS. OR P.E.
- 9.) TOPOGRAPHIC SURVEY PERFORMED BY BERRY SURVEYING & ENGINEERING IN JANUARY OF 2016.
- 10.) VERTICAL DATUM BASED ON NAVDBB ELEVATIONS. HORIZONTAL COORDINATES BASED ON NADB3. COORDINATES GATHERED USING TOPCON HIPER SR SURVEY GRADE GPS RECEIVERS.
- 11.) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVE AND BELOW GROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. ANY UTILITY CONFLICTS SHOULD BE REPORTED IMMEDIATELY TO THE DESIGN ENGINEER.
- THE CONTRACTOR SHALL CALL AND COORDINATE WITH DIGSAFE 1-888-344-7233 AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.
- 13.) SEE DETAILS CONCERNING SITE LAYOUT, DRAINAGE, UTILITY AND SEDIMENT AND EROSION CONTROLS
- 14.) SEE SEDIMENT & EROSION CONTROL PLAN FOR INLET PROTECTION AND CONTROLS FOR THE ENTIRE SITE.
- 15.) REQUIRED EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY DISTURBANCE OF THE SITE'S SURFACE AREA AND SHALL BE MAINTAINED THROUGH THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES. IF, DURING CONSTRUCTION, IT BECCHAS APPARENT THAT ADDITIONAL EROSION CONTROL MEASURES ARE REQUIRED TO STOP AND EROSION ON THE CONSTRUCTION SITE DUE TO ACTUAL SITE COMMITTON, THE OWNER SHALL BE REQUIRED TO INSTALL THE NECESSARY EROSION PROTECTION AT NO EXPENSE TO THE CITY.
- 16.) THE CONTRACTOR SHALL MAKE ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENT OF GAS, ELECTRIC, TELEPHONE AND ANY OTHER PRIVATE UTILITIES BY THE UTILITY COMPANIES.
- 17.) AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
- 18.) CONTRACTOR SHALL TAKE SPECIAL CARE IN NOT DISTURBING EXISTING MONUMENTS BOUNDS, AND OR BENCHMARKS WITHOUT FIRST MAKING PROVISIONS FOR RELOCATION.
- 19.) WHERE AN EXISTING UNDERGROUND UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FUNNISHED TO THE CONFLICT. THE CONFLICT.
- 20.) FINAL UTILITY LOCATIONS TO BE COORDINATED BETWEEN THE CONTRACTOR, ALL APPROPRIATE UTILITY COMPANIES AND THE CITY OF ROCHESTER.
- CONTRACTOR SHALL COORDINATE ALL ELECTRICAL INSTALLATIONS WITH EVERSOURCE AT (603)-436-770B. ALL ELECTRIC COMDUIT INSTALLATION SHALL BE INSPECTED BY EVERSOURCE PRIOR TO BACKFILL A 48-HOUR MINIMUM MOTICE IS REQUIRED.
- 22.) CONTRACTOR SHALL COORDINATE ALL CABLE AND TELECOMMUNICATIONS INSTALLATIONS WITH CONSOLIDATED COMMUNICATIONS.
- 23.) ALL NEW ON-SITE UTILITIES SHALL BE INSTALLED UNDERGROUND
- 24.) THE PROJECT WILL BE SERVED BY SOMERSWORTH WATER AND ON SITE SEPTIC SYSTEMS.

- 28.) PROTECTION OF SUBGRADE: THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN STABLE, DE-WAITERD SUBGRADE TRENCHES, AND OTHER AREAS DURING CONSTRUCTION. SUBGRADE DISTURBANCE MAY BE INFLUENCED BY EXCAPANT SETTIONS, MISSINGLE PROCEPTATION, OR CONTROLLAND CONSTRUCTION ACTIVITIES. THE CONTRACTOR SETTION OF THE CONTRACTOR SETTION OF THE CONTRACTOR STABLE PROCEPTATION OF THE CONTRACTOR STABLE PROCEPTATION OF THE CONTRACTOR STABLE PROCEPTATION OF THE CONTRACTOR AND STABLE PROCEPTATION OF THE CONTRACTOR AND STABLE PROCEPTATION OF THE CONTRACTOR STABLE PROCEPTATION OF THE CONTRACTOR OF THE CONT
- 29.) IF THE EARTHWORK IS PERFORMED DURING FREZING WEATHER (NOT ALLOWED IN CITY R.O.W.). EXPOSED SUBGRADES ARE SUSCEPTIBLE TO FROST HIO FILL OF INTLINES SHALL BE PLACED ON FROZED REGOON. THIS WILL LIVE PEQUIPE REMOVAL OF A FROZEN SOIL CRUST AT THE COMMENCEMENT OF EACH DAY'S OPERATION. THE FINAL SUBGRADE ELEVATION WOULD ALSO REQUIRE AN APPROPRIATE DEGREE OF INSULATION AGAINST FREEZING.
- 31.) BERMS ARE TO BE CONSTRUCTED WITH HIGH QUALITY CLAY OR LOAMY MATERIAL AND COMPACTED APPROPRIATEL NO FROZEM MATERIALS ARE TO BE USED IN THE CONSTRUCTION OF ANY BERM ON SITE. TO BE REVIEWED AND APPROVED BY THE CITY OF ROCHESTER OR THEIR AGENTS.
- 32.) ALL ELEVATIONS TO BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE DESIGN ENGINEER IS TO BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCY. TEMPORARY BENCHMARKS (T.B.M.) ARE TO BE PROVIDED BY THE DESIGN ENGINEER.
- 33.) ALL DRAINAGE PIPE IS TO BE HDPE N-12 ASTM F2648. (GREEN PIPE) INDIVIDUAL PIPE SIZES ARE SPECIFIED.
- 34.) UPON FINAL COMPLETION AND 85% STABILIZATION THE DRAINAGE SYSTEM IS TO BE CLEANED OF ALL DEBRIS TO INCLUDE THE PUMPING OF THE BASIN SUMPS.
- 35.) ALL BASINS AND DRAINS ARE TO HAVE BOOTS INSTALLED ON ALL INLETS AND DUTLETS. HOODS TO BE INSTALLED ON THE CATCH BASINS UPON INSTALLATION.
- 36.) ALL PROPOSED CLEAN OUTS ARE TO BE VERTICAL 12" N-12 PIPE WITH CAST IRON COVERS SCREWED WITH STAINLESS SCREWS. THE COVER IS TO BE DEMARCATED WITH A "D".
- 37.) ALL TREATMENT SWALE TO BE CONSTRUCTED SHALL HAVE SOD BOTTOMS UNLESS OTHERWISE INSTRUCTED BY THE DESIGN ENGINEER DURING CONSTRUCTION.
- 38.) A LETTER OF CREDIT FOR THE COST OF RE-VEGETATING ALL DISTURBED AREAS ON THE SITE SHALL BE SUBMITTED PRIOR TO ANY EARTH DISTURBING ACTIVITY OCCURS, AS MAY BE APPLICABLE.
- 39.) A PRE-CONSTRUCTION CONFERENCE WITH THE DEVELOPER, THE DESIGN ENGINEER, THE EARTHWORK CONTRACTOR AND ROCHESTER DPW AND PLANNING STAFF SHALL OCCUR PRIOR TO ANY EARTH DISTURBING ACTIVITY.

- 42.) WENTEN DIMENSION ON THIS PLAN TAKE PROCEEDING OVER SCALED DIMENSIONS. THE CONTRACTOR SHALL USE CAUTION WHEN SCALING REPRODUCED THAN IN THE EVENT OF A CONFLICT BETWEEN THIS FLAN SET AMD ANY OTHER DRAWNIGS AND/OR SPECIFICATIONS, THE ENGINEET SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CONTRACTOR IS TO CONFIRM ALL ELEVATIONS. CONFLICTS WILL BE REPORTED TO THE DESIGN ENGINEET PRIOR TO CONSTRUCTION.
- 43.) IF, DURING CONSTRUCTION, IT BECOMES APPARENT THAT DEFICIENCIES EXIST IN THE APPROVED DESIGN DRAWNOS, THE CONTRACTOR SHALL BE REQUIRED TO ORRECT THE DEFICIENCIES TO MEET THE REQUIREMENTS OF THE REQUIREMENTS.
- 44.) THIS PLAN PROPOSES 88,000 Sq. Ft. OF DISTURBANCE FOR THE CONSTRUCTION OF THE ROAD AND RAIN GARDENS.
- 45.) CONTRACTOR IS TO FULLY CONSTRUCT THE ROADWAY, ROADSIDE SWALES AND RAIN GARDENS PRIOR TO ANY RESIDENTIAL LOT CONSTRUCTION.


X X


BE


m

KENNETH BERRY No. 14243 KICENSED!

SHEET 14 OF 35







BIORETENT	ION FILTER M	EDIA MI	XTURES
	Percent of	Gradation of material	
Component Material	Mixture by Volume	Sieve No.	Percent by Weight Passing Standard Sieve
Bioreter	tion Filter Med	dia Optic	n A
ASTM C-33 concrete sand	50 to 55		
Loamy sand topsoil, with fines as indicated	20 to 30	200	15 to 25
Moderately fine shredded bark or wood fiber mulch, with fines as indicated	20 to 30	200	< 5

3/8" WASHED	CRUSHED STONE*	3/4" WASHED	CRUSHED STONE *
SIEVE SIZE 1/2" 3/8" # 4 # 8	% PASSING BY WEIGHT 100 95 - 100 22 - 55 0 - 10	SIEVE SIZE 1" 3/4" 1/2" # 10	% PASSING BY WEIGHT 100 90 - 100 15 - 55 0 -5
STONE - SE	TO STANDARD WASHED CTION 702 OF NHDOT IDARD SPECIFICATIONS	STONE - SEC	TO STANDARD WASHED CTION 702 OF NHDOT DARD SPECIFICATIONS

- WHEN CONTRACTOR EXCAVATES RAIN CARDEN AREA TO SUBGRADE, DESIGN ENGINEER SHALL PERFORM SUBSURFACE EVALUATION PRIOR TO THE PLACEMENT OF ANY SELECT MATERIAL OR OTHER BACKFILL.

 SOIL BIORETHION FILTER MEDIA SHALL BE AS SHOWN ABOVE, "BIO MEDIA" MAKEN BIORETHION FILTER MADIA. COMPACTION IS NOT TO OCCUR IN THE RAIN CARDEN AREAS PRIOR TO CONSTRUCTION. SCARFICATION REQUIRED IN THE EVENT COMPACTION TAKES PLACE.

 DO NOT PLACE THE BIORETHATION SYSTEM INTO SERVICE UNTIL THE BMP HAS BEEN PLANTED AND ITS CONTRIBUTION AFORMACE SHAVE BEEN PLANT STABILIZED.

 DO NOT DISCHARGE SEMBRIT-LUCH NATES.

 DO NOT THATFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION ACTIVITIES (RUNOFT WATER FROM EXCAVATIONS) THE DIVIDITION OF THE SYSTEM.

- SYSTEMS SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND FOLLOWING ANY RAINFALL EXCEEDING 2.5 INCHES IN A 24-HOUR PERIOD, WITH MAINTENANCE OR REHABILITATION CONDUCTED AS A WARRANTED BY SUCH INSPECTION.

DESIGN REFERENCES


RAIN CARDEN MIX
THE GRASS THAT IS PLANTED WITHIN A RAIN CARDEN BIO-FILTRATION SYSTEM WITHIN THE BIO-MEDIA MUST CONSIST OF A COMBINATION OF WARM SEASON GRASS SEED AND COLD SEASON GRASS SEED IN ORDER FOR THE GRASS TO START GROWING FOR STABILIZATION AND CONTINUE GROWING IN THE SANDY WELL-DRAINED ENVIRONMENT. PLANTING SPECIFICATION WILL MEET THE RECOUREMENTS AS OUTLINED IN "VECETATION INEW HAMPSHIRE SAND AND GRAVEL PITS" MIX 1 (WARM SEASON GRASSES) (15 LBS/AC) AND INCLUDE ANNUAL AND PERENNAL RYE GRASS SEED (15 LBS/AC) AND INCLUDE ANNUAL AND PERENNAL RYE GRASS MIX 180-1 (20 LBS/AC) AND INCLUDE ANNUAL AND PERENNAL RYE GRASS MIX 180-1 (2


- UNH STORMWATER CENTER
 NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 2, DECEMBER 2008 AS AMENDED.


TOP OF 15" PIPE & TOP OF STRUCTURE = 221.25 OUTLET STRUCTURE #101 NOT TO SCALE -SEE DRIEGE SCHEMATIC #101 15" HOPE N-12 RISER POND BOTTOM TOP VIEW 15" DIA. HDPE N-12 RISER W/ "T" STRUCTURE OUTLET STRUCTURE #101 NOT TO SCALE

7.0% UNIT 11 UNIT 9 PROP. CATCH BASIN &S 4 FLAT TOP REXUS GRATE JRBM - 225.50 INV. N = 223.30 (12" HDPE N-12) INV. OUT = 223.20 (12" HDPE N-12) I W/ 4 SUAP & HOCO I SUMP - 219.20










SECTION OF RAIN GARDEN R101




VERTICAL SCALE: 1" = 4'

R101

BE

KENNETH

SHEET 18 OF 35



3/8" WASHED CRUSHED STONE * 22 - 55

0 - 10

EQUIVALENT TO STANDARD WASHED STONE - SECTION 702 OF NHDOT NHDOT STANDARD SPECIFICATIONS

3/4" WASHED	CRUSHED STONE*
SIEVE SIZE	% PASSING BY WEIGHT
3/4"	90 - 100
1/2"	15 - 55
# 10	0 -5

STONE - SECTION 702 OF NHOOT NHOOT STANDARD SPECIFICATIONS

- WHEN CONTRACTOR EXCAVATES PAIN GARDON AREA TO SUBGRADE, DESIGN ENGINEER SMALL PERFORM SUBSURFACE EVALUATION PRIOR TO THE PLACEMENT OF ANY SELECT MATERIAL OR OTHER BACKFILL.

 COMPACTION IS NOT TO OCCUR IN THE RAIN GARDEN AREAS PRIOR TO CONSTRUCTION. SCARFICATION FILTER MADIA. COMPACTION IS NOT TO OCCUR IN THE RAIN GARDEN AREAS PRIOR TO CONSTRUCTION. SCARFICATION REQUIRED IN THE EVENT COMPACTION THE SELECT.

 DO NOT PLACE THE BIORETENION SYSTEM INTO SERVICE UNTIL THE BMP HAS BEEN PLANTED AND ITS CONTRIBUTION ACRES HAVE BEEN FULLY STABILIZED.

 DO NOT DISCHARES SEMENT—LUCEN MATERS FROM CONSTRUCTION ACTIVATIES (RUNOFF WATER FROM EXCAVATIONS) TO NOT TRACTICE EXPOSED. DOS. SUBFACE WITH CONSTRUCTION.

 ON NOT TRACTICE EXPOSED. SOL, SURFACE WITH CONSTRUCTION CONFIDENTIAL IF FLASBULE PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION COMPONENTS OF THE SYSTEM.

MAINTENANCE REQUIREMENTS

- SYSTEMS SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND FOLLOWING ANY RAINFALL EXCEEDING 2.5 INCHES IN A 24-HOUR PERIOD, WITH MAINTENANCE OR REHABILITATION CONDUCTED AS A WARRANTED BY SUCH INSPECTION.
- PRETREATMENT MEASURES SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND CLEANED OF ACCUMULATED SEDIMENT AS WARRANTED BY INSPECTION, BUT NO LESS THAN ONCE ANNUALLY.
- AT LEAST ONCE ANNUALLY, SYSTEM SHOULD BE INSPECTED FOR DRAWDOWN TIME. IF BIORETENTION SYSTEM DOES NOT DRAIN WITHIN 72-HOURS FOLLOWING A RAMPALL EVENT, THEN A QUALIFIED PROFESSIONAL SHOULD ASSESS THE CONDITION OF THE FACILITY TO DETERMINE MEASURES REQUIRED TO RESTORE INTRAINOR FUNCTION OR INFILITATION FUNCTION OF OR PETUL MEDIA.

 REQUIRED TO RECONSTRUCTION OF THE FILTER MEDIA.

DESIGN REFERENCES

RAIN CARDEN MIX

THE GRASS THAT IS PLANTED WITHIN A RAIN GARDEN BIO-FILTRATION SYSTEM WITHIN THE BIO-MEDIA MUST CONSIST OF A COMBINATION OF WARM SEASON GRASS SEED AND COLD SEASON GRASS SEED IN ORDER FOR THE CRASS TO START GROWING FOR STABILIZATION AND CONTINUE GROWING IN THE SANDY WELL-DRAINED ENVIRONMENT. PLANTING SPECIFICATION WILL MEET THE REQUIREMENTS AS OUTLINED IN "VECETATION INCH HAMPSHIRE SAND AND GRAVEL PITS" MIX 1 (WARM SEASON GRASSES) (15 LBS/AC) AND INCLUDE ANNUAL AND PERENNIAL RYE GRASS SEED (15 LBS/AC); THE NEW ENGLAND NATIVE WARM SEASON GRASS MIX (23 LBS/AC) BY NEW ENGLAND WELT-LAND PLANTS, INC.; RAIN GARDEN MIX 180 (15 LBS/AC & 15 LBS/AC OF RYE) BY ERNST CONSERVATION SEEDS; OR APPROVED EQUAL.

UNH STORMWATER CENTER
NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 2, DECEMBER 2008 AS AMENDED.

1.) 2' CORE IS TO BE CONSTRUCTED OF COMPACTED LOW PERM CLAY MATERIAL. 2.) CORE IS TO BE INSTALLED & COMPACTED IN 12" LIFTS. 3.) INSTALLATION OF ENTIRE DRAINAGE STRUCTURE IS TO BE OVERSEEN BY DESIGN ENGINEER. & COMPACTED IN 12" LIFTS. LOW PERMEABILITY MATERIAL GRADATION % PASSING BY WEIGHT EXCAVATE TO RELATIVELY IMPERVIOUS SOIL LAYER, BUT NOT LESS THAN 3'

Angle Grates For Manholes



AG0808-58 Part No. AG0808-58


Save Trees

Angle Grates are designed to cover inlet orifices and prevent small to medium debris from passing through. The top angled design helps to minimize the amount of debris that settles on top after the water receeds. All grates are made from plate for a clean and smooth contact surface.

- · Plate design for a clean appearance
- . Standard 2" openings (other sizes can be made)
- Angled top/front plate to maximize debris deflection
- . Mounting flanges on 3 sides allows grate to be mounted at floor level
- · Galvanized steel construction. Can be made from aluminum or stainless steel


MUST BE HAALA INDUSTRIES INC. OR FOUAL.


ANGLE GRATE




PLAN VIEW RAIN GARDEN #102 -48" CONE GRATE SET ATOP A OUTLET STRUCTURE #102 12" HDPE N-12 OUTLET PIF TOP VIEW 4" ORIFICE = 206.25

OUTLET STRUCTURE #102







SECTION OF RAIN GARDEN R102

BERRY



SHEET 19 OF 35

R102

418

BIORETENT	ION FILTER ME	EDIA MI	XTURES
	Percent of	Gr	adation of material
Component Material	Mixture by Volume	Sieve No.	Percent by Weight Passing Standard Sieve
Bioreter	ntion Filter Med	dia Optio	n A
ASTM C-33 concrete sand	50 to 55		
Loamy sand topsoil, with fines as indicated	20 to 30	200	15 to 25
Moderately fine shredded bark or wood fiber mulch,	20 to 30	200	< 5

3/8" WASHED	CRUSHED STONE*	3/4" WASHED	CRUSHED STONE*
SIEVE SIZE 1/2" 3/8" # 4 # 8	% PASSING BY WEIGHT 100 95 - 100 22 - 55 0 - 10	SIEVE SIZE 1" 3/4" 1/2" # 10	% PASSING BY WEIGHT 100 90 - 100 15 - 55 0 -5
	TO STANDARD WASHED CTION 702 OF NHDOT DARD SPECIFICATIONS	STONE - SE	TO STANDARD WASHED CTION 702 OF NHOOT IDARD SPECIFICATIONS

- MEN. CONTRACTOR EXCAVATES RAIN GARDEN AREA TO SUBGRADE, DESIGN DIGNEER SHALL PERFORM SUBSURFACE
 EVALUATION PRIOR TO THE PLACEMENT OF MAY SELECT MATERIAL, DR OTHER BACKFILL.
 SOLL BIGGETENTION FLITER MEDIA SHALL BE AS SHOWN ABOVE. BIG MEDIAT MEANS BIGGETENTION FILTER MADIA,
 COMPACTION IS NOT TO DECUR IN THE RAIN CARGEN AREAS PRIOR TO CONSTRUCTION. SCARPICATION REQUIRED IN
 THE EVENT COMPACTION TASSES PLACE.
 DO NOT PLACE THE BIGGETENTION SYSTEM INTO SERVICE UNIL THE BUP HAS BEEN PLANTED AND ITS
 CONTRIBUTING AREAS HAVE BEEN FILLY STRABULZED,
 DO NOT DISCHARCE SEDIMENT—LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF WATER FROM EXCAVATIONS)
 TO THE BIGGETENTION AREA DIANG ANY STAN FOR OF CONSTRUCTION ACTIVITIES (RUNOFF WATER FROM EXCAVATIONS)
 TO THE BIGGETENTION AREA DIANG ANY STAN FOR OF CONSTRUCTION STANDARD FOR FOR PERFORM EXCAVATIONS WITH
 EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INVESTIGATION OF THE SYSTEM.

MAINTENANCE REQUIREMENTS


- SYSTEMS SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND FOLLOWING ANY RAINFALL EXCEEDING 2.5 INCHES IN A 24-HOUSP PERIOD, WITH MAINTENANCE OR REHABILITATION CONDUCTED AS A WARRANTED BY SUCH INSPECTION.
- AT LEAST ONCE ANNUALLY, SYSTEM SHOULD BE INSPECTED FOR DRAMDOWN TIME. IF BIORETENTION SYSTEM DOES NOT DRAW MITHIN 72-HOURS FOLLOWING A RAMFALL EVENT, THEN A QUALIFIED PROFESSIONAL SHOULD ASSESS THE CONDITION OF THE FAQUITY TO DETERMINE MEXAURES REQUIRED TO RESTORE ILTRATION FUNCTION OR INFILITRATION FUNCTION (SA SPELICABLE), INCLUDING BUT NOT LIMITED TO REMOVAL OF ACCUMULATED SEDMENTS OR RECONSTRUCTION OF THE FILTER MEDIA.
- 4 VEGETATION SHOULD BE INSPECTED AT LEAST ANNUALLY, AND MAINTAINED IN HEALTHY CONDITION, INCLUDING, PRUNING. REMOVAL. AND REPLACEMENT OF DEAD OR DISEASED VEGETATION, AND CLIMOVAL OF INVASIVE SPECIES.


DESIGN REFERENCES

UNH STORMWATER CENTER
NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 2, DECEMBER 2008 AS AMENDED.


RAIN CARDEN MIX


THE GRASS THAT IS PLANTED WITHIN A RAIN GARDEN BIO-FILTRATION SYSTEM WITHIN THE BIO-MEDIA MUST CONSIST OF A COMBINATION OF WARM SEASON GRASS SEED AND COLD SEASON GRASS SEED IN ROPE FOR THE GRASS TO START GROWING FOR STABILIZATION AND CONTINUE GROWING IN THE SANDY WELL-DRAINED ENVIRONMENT. PLANTING SPECIFICATION MILL MEET THE REQUIREMENTS AS DUTLINED IN "VECETATION NEW HAMPSHIRE SAND AND GRAVEL PITS" MIX I (WARM SEASON GRASSES) (15 LBS/AC) AND INCLUDE ANNUAL AND PERENNAL RYE GRASS SEED (15 LBS/AC) AND INCLUDE ANNUAL AND PERENNAL RYE GRASS SEED (15 LBS/AC) AND INCLUDE ANNUAL AND PERENNAL RYE GRASS MIX (23 LBS/AC) BY NEW ENCLAND WELLAND PLANTS, INC.; RAIN GARDEN MIX 180 (15 LBS/AC & 15 LBS/AC OF RYE) BY ERNST CONSERVATION SEEDS; OR APPROVED EQUAL.







PLAN VIEW RAIN GARDENS #103 & #104













SHEET 20 OF 35


R103




















SHEET 26 OF 35









MINIMUM 48" LONG, SPACED A MAXIMUM 10' APART, AND DRIVEN A MINIMUM OF 16" INTO THE

GROUND.

WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY-PASSING. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF, SEE MAINTENANCE NOTE BELOW, REMOVAL OF SEDIMENT REQUIRED AT A DEPTH OF 6-INCHES.

PLACE THE ENDS OF THE SILT FENCE UP CONTOURT TO PROVIDE FOR SEDIMENT STORAGE.

SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENDINEER.

THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED.

TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, SILT FENCE, PAGE 90.

FILTER CLOTH

SILT FENCE MAINTENANCE

1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE

IMMEDIATELY.

IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH SIX-INCHES IN DEPTH. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS

MOUNTABLE BERM

10' MIN. EXISTING PAVEMENT

BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND

E5 STABILIZED CONSTRUCTION ENTRANCE

PROFILE

PLAN VIEW

75' SEE NOTE 2

SILT FENCE/HAYBALE BARRIER DETAIL THIS METHOD TO BE USED ALONG THE REAR OF THE PROPERTY NOT TO SCALE

E3GRASS TREATMENT SWALE

NOT TO SCALE NSPECT ANNUALLY FOR EROSION, SEDIMENT ACCUMULATIONS, VEGETATION LOSS, & INVASIVE SPECIES. REPAIR AS NECESSARY.


MOW GRASS ANNUALLY TO A DEPTH OF 4".

INSTALL STABILIZATION MATTING DURING CONSTRUCATION

TO BE CONSTRUCTED IAW NH SWM #2 CHAPTER 4, #5 TREATMENT SWALES, PAGE 123.

CONSTRUCTION SAFETY FENCE

NOT TO SCALE



I. ALL SENSITIE AREAS SHALL BE PROTECTIO AS PER PLAN.


Q. ALL TREES IN THE CONSTRUCTION AREA NOT SPECIFICALLY DESIGNATED FOR REMOVAL SHALL BE
PRESENDED AND PROTECTED WITH HIGH MISBUILTY FERICE AS PER PLAN.

MENT PRACTICABLE, INSTALL HON' VISBUILTY STEED (UTISED OF THE DRIP LINE OF THE TIPEZ.

4. SAPETY FONCE SHOULD BE FASTENED SCURRELY TO THE T-POSTS.

THE TREICHS, MESST FRAME IN THE PLACE DIRING ALL PRIMES OF CONSTRUCTION; ANY CHANGE OF THE

EROSION CONTROL MIX BERM



EROSION CONTROL MIX BERMS SHALL BE USED ONLY AS FOLLOWS:


1. BERMS SHALL BE USED IN AREAS WHERE EROSION WILL OCCUR ONLY IN THE FORM OF SHEET EROSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY

ABOVE THE BERM.
THE BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSLY AS

THE BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSLY AS POSSIBLE.

THE BERMS SHALL BE INSTALLED ON SLOPES LESS THAN 5%.
SUBJECT TO (E), BELOW, THE MIX SHALL HAVE AN ORGANIC PORTION BETWEEN 80 AND 100%, DRY WEIGHT BASIS, AND BE FIBROUS AND ELONGATED SUCH AS FROM SHREDDED BARK, STRUMF GRINDINGS, COMPOSED BARK, OR EQUIVALENT MANUFACTURED PRODUCTS.
WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS SHALL NOT BE USED AS ORGANIC MATERIAL.
THE MIX SHALL HOT CONTAIN SILTS, CLAY, OR FINE SANDS.
THE MIX SHALL HAVE A PARTICLE SIZE BY WEIGHT OF 70 TO 85% PASSING A 6-INCH SCREEN AND A MAXIMUM OF 85% PASSING THE 0.75-INCH SCREEN.
THE MIX SHALL HAVE A EBTWEEN 5.0 AND 8.0.
THE BERM SHALL BE AT LEAST 12 INCHES HIGH AND AT LEAST 2 FEET WIDE.
TO BE CONSTRUCTED LAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, EROSION CONTROL MIX BERMS, PAGE 106.

E7



MAINTENANCE

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS MADE AS NECESSARY. SEDIMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDIMENT HAS REACHED A MAXIMUM OF ONE HALF THE DEPTH OF THE TRAP. THE SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURE OR VEGETATIVE MEANS. THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE CONTRIBUTING DRAINAGE AREA TO THE INLET HAS BEEN COMPLETELY STABILIZED.

BLOCK & GRAVEL DROP INLET SEDIMENT FILTER

NOT TO SCALE

TO BE USED IN ALL AREAS WHERE THERE WILL BE NO TRAFFIC.

E4

E8 TEMPORARY EROSION CONTROL MEASURES

THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME.

EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER.

ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4° OF LOAM AND SECDED WITH NOT LESS THAN ONE POUND OF SEED PER DO SQUARE YARDS OF AREA. (SEE SEED SPECIFICATIONS THIS SHEET)

ALL DISTURBED AREAS WILL BE RESTABILIZED WITHIN 45 DAYS. AT ANY ONE TIME, NO MORE THAN 5 ACRES, $(217,800~S_{\rm F}.t.)$ WILL BE DISTURBED.

SILT FENCES AND PERIMETER BARRIERS SHALL BE INSPECTED PERIODICALLY AND AFTER EVERY RAIN DURING THE LIFE OF THE PROJECT, ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF.

AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VEGETATED.

PER THE EPA CGP REQUIREMENTS THERE WILL BE REPORTS OF THE EROSION CONTROL INSPECTIONS IAW SWPPP PREPARED BY BS&E ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.25° OR GREATER RAIN EVENT.

DITCHES, SWALES, AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.

DO NOT TRAFFIC EXPOSED SOIL SURFACES WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION SYSTEM.

10. DRIVEWAYS AND CUT AND FILL SPLOPES MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINAL GRADE.

11. STABILIZATION MEANS:

A MINIMUM OF 85% OF VEGETATIVE COVER HAS BEEN ESTABLISHED.
 A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED, OR
 EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.

12. THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

13. THE NHDES STORMWATER MANUAL, IN THREE VOLUMES, DATED DECEMBER 2008, IS A PART OF THIS PLAN SET AND THE MORE RESTRICTIVE WILL GOVERN. (NH SWM)

FOR DOV STEF

<u>~</u> ~

m

TO BE CONSTRUCTED IAW NH SWM #3 4-2



PLAN VIEW PLAN VIEW PLAN FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT. 2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3—INCH TO 6—INCH BERM IS INSTALLED AT THE ENTRANCE OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES. 3. THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES. 4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR GERES OCCURS OR TO FEET, WHICH EVER IS GREATER. 5. GENERALE FOR THE STANDES OCCURS OR TO FEET, WHICH EVER IS GREATER. 6. GENERALE FOR THE THE THE STANDES OF THE STANDES SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS MAY BEAD PRIOR TO PLACING. 6. SHALL SUPPRED SENEATH THE ENTRANCE. IF PIPING IS MAY BE AS PRIOR WITH 51 SLOPES THAT ON BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE. 7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAN WE REVENUE THACKING OR FLOWING OF SEDIMENT ONTO PUBLIC MINISTER ALL SEDIMENT SHILLED, WASHED, OR TRACKED ONTO PUBLIC SUCKEYS—OF—WAY MAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND FOR THACKED ONTO PUBLIC SIGNIFICATION. SIGNIFICATION OF THE STANDES OF THE STANDER OF THACKED ONTO PUBLIC. SIGNIFICATION TO THE STANDES OF THE STANDER OF THACKED ONTO PUBLIC. SIGNIFICATION EXIT, PAGE 124. STONE CHECK DAM

THE DISTANCE SUCH THAT POINTS A AND B ARE OF EQUAL ELEVATION

7 SPACING BETWEEN STRUCTURES

1.) CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS

UNION DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH.

THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE DAM SHOULD BE LESS THEN ONE ACRE.

THE MAXIMUM HEIGHT OF THE DAM SHOULD BE TWO FEET.

THE CENTER OF THE DAM SHOULD BE AT LEAST SIX INCHES LOWER THAN THE OUTER EDGES.

THE MAXIMUM SPACING IS AS SHOWN ON THE PROJECT SITE PLANS.

PLANS.
CHECK DAMS WILL NOT BE USED IN A FLOWING STREAM.
TEMPORARY CHECK DAMS WILL BE REMOVED ONCE THE
SWALE OR DITCH IS DETERMINED STABLE.

SWALE OR DITCH IS DETERMINED STABLE.

8.) TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY CHECK DAMS, PAGE 114.


NOT TO SCALE




NOTE: KEY STONE INTO CHANNEL BANKS AND EXTEND IT BEYOND TO ABUTMENTS A MINIUM OF 18° TO PREVENT FLOW AROUND THE DAM.

E9

FYISTING GRADE



STONE GRADE STABILIZATION STRUCTURE



(SEE SECTION) E10X -FILTREXX SOXX (12" TYPICAL) AREA TO BE PROTECTED WATER FLOW WORK AREA

2"X2"X36" WOODEN STAKES PLACED 10' O.C.

ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
FILTER MEDIA FILL TO MEET APPLICATION REQUIRMENTS.
COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.
SILTSOXX MAY BE USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT
BARRIERS.

PLAN NOT TO SCALE

BARRIERS.
SLITSOXX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS NECESSARY TO MEET THE REQUIRMENTS OF THE SPECIFIC APPLICATION.
FILTREXX SOXX IS A REGISTRED TRADEMARK OF FILTREXXIN TERNATIONAL, LLC.
SLIT FENCE IS NOT A SUBSTITUTION FOR SLIT SOXX AND PAY EQUAL
TO BE CONSTRUCTED IAW FILTREXX, SECTION 1:EROSION & SEDIMENT CONTROL
(PAGE 323) — CONSTRUCTION ACTIVITIES, SWPPP CUT SHEET: FILTREXX
SEDIMENT CONTROL

FILTREXX SEDIMENT

Filtrexx International, LLC 35481 Grafton Eastern Rd | Grafton, Oh 44044 440–926–2607 | fax: 440–926–4021 WWW.FLITREXX.COM OR APPROVED EQUAL

NOTE: FOR AREAS REQUIRING DOUBLE PERIMETER

 $\underline{SECTION}$ NOT TO SCALE

CONTROL- 30' NOT TO SCALE 2"X2"X36" WOODEN STAKES PLACED 10' O.C. -FILTREXX SOXX BLOWN /PLACED FILTER MEDIA -AS NOTED) Mandachan handrachand

TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.

CONTROL WITHIN 50' OF JURISDICTIONAL WETLANDS AND NOT FOR ALL SILT SOXX APPLICATIONS. THIS DUPLICATION MAY BE SPECIFIED AS 12" SILT SOXX OR ORANGE CONSTRUCTION FENCE AS NOTED.

SILTSACK DETAIL

SHEET 30 OF 35

00

E11

AREA TO BE PROTECTED






-THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF CORD IS COVERED WITH SEDIMENT, THE SILTSACK SHOULD BE EMPTIED.


-TO BE USED IN ALL AREAS WHERE THERE WILL BE


- ARE SUBJECT TO DAMAGE BY SNOW PLOWS, AND MUST BE INSPECTED AFTER ANY SNOW EVENT AND REPLACED AS REQUIRED.

SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.

E - 101







SECTION A-A

PIPE OUTLET TO WELL-DEFINED CHANNEL

PIPE OUTLET TO FLAT AREA

WITH NO DEFINED CHANNEL

NOTE: THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF PEA 430-53 AND CHAPTER ACR 3800 RELATIVE TO INVASIVE SPECIES. SEEDING RATES POUNDS POUNDS PER PER ACRE 1,000 Sq. Ft MIXTURE


OR FLAT PEA TOTAL

TALL FESCUE FLAT PEA TOTAL

TALL FESCUE CREEPING RED FESCUE BIRDS FOOT TREFOIL

CREEPING RED FESCUE 1/ 50
KENTUCKY BLUEGRASS 1/ 50
TOTAL 100

CONSERVATION MIX



SEEDING SPECIFICATIONS

- GRADING AND SHAPING . SLOPES SHALL NOT BE STEEPER THAN 2:1;3:1 SLOPES OR FLATTER ARE WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED
- SEEDBED PREPARATION
 A. SUFFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM
 THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.
 B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE
 THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA. WHERE
 FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO
 PREPARE A SEED BED AND MIX FERTILIZER AND LIME INTO THE SOIL. THE
 SEEDBED SHOULD BE LETT IN REASONABLY FIRM AND SMOOTH CONDITION. THE
 LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER
 PRACTICAL. SEEDBED PREPARATION
- ESTABLISHING A STANE LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF

AND INCORPORATED INTO THE SOIL KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST IS NOT

AVAILABLE,
THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED:
AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100LBS. PER 1,000 SQ.FT.
NITROGEN(N), 50LBS. PER ACRE OR 1.1LBS. PER 1,000 SQ.FT. PHOSPHATE(P205), 100LBS, PER ACRE OR 2,2LBS, PER 1,000 SQ.FT. POTASH(K20), 100LBS. PER ACRE OR 2.2LBS. PER 1,000 SQ.FT.
(NOTE: THIS IS THE EQUIVALENT OF 500LBS. PER ACRE OF 10-20-20 FERTILIZER OR 1,000LBS. PER ACRE OF 5-10-10.)

RAIN CARDEN MIX
THE GRASS THAT IS PLANTED WITHIN A RAIN GARDEN BIO-FILTRATION SYSTEM WITHIN THE BIO-MEDIA MUST CONSIST OF A COMBINATION OF WARM SEASON GRASS SEED AND COLD SEASON GRASS SEED IN ORDER FOR THE GRASS TO START GROWNIC FOR STABILIZATION AND CONTINUE GROWNIG IN THE SANDY WELL—DRAINED ENVIRONMENT. PLANTING SPECIFICATION MILL MEET THE REQUIREMENTS AS OUTLINED IN "VEGETATION NEW HAMPSHEE SAND AND GRAVEL PIST MIX! (WARM SEASON GRASSES) (15 LBS/AC); THE NEW ENGLAND WATTE WARM SEASON GRASSES) (15 LBS/AC) AND INCLUDE ANNUAL AND PERENNIAL RYE GRASS SEED (15 LBS/AC); THE NEW ENGLAND WATTE WARM SEASON GRASS MIX (23 LBS/AC) BY NEW ENGLAND WETLAND PLANTIS, INC.; RAIN GARDEN MIX 180 (15 LBS/AC & 15 LBS/AC OF RYE) / RAIN GARDEN GRASS MIX (30 LBS/AC & 15 LBS/AC OF RYE) / RAIN CONSERVATION SEEDS; OR APPROVED EQUAL

PIPE OUTLET PROTECTION CONSTRUCTION SPECIFICATIONS

- . THE SUB GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS. SPECIFIED GRADATION.
- 2. THE ROCK OR GRAVEL USED FOR FILTER OF RIP RAP SHALL CONFORM TO NHDOT
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC, ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- 4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.
- TO BE CONSTRUCTED IAW NH SWM #2 4-6 CONVEYANCE PRACTICES, 6. OUTLET PROTECTION, PAGE 172.

E 16

E14

d50 SIZE=	0.5	FEET	6	INCHES
% OF WEIGHT S THAN THE GIVE		SIZE (OF STON	IE (INCHES) TO
100%		9		12
85%		8		11
50%		6		9
15%		2		3

E17 CONSTRUCTION SEQUENCE:

- 1) CUT AND REMOVE TREES IN CONSTRUCTION AREA ONLY AS REQUIRED, RELOCATE ANY PROJECT T.B.M.
- 2.) CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SEDIMENT EROSION AND DETENTION CONTROL FACILITIES AS SPECIFIED, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SOIL LAND DISTURBANCE AND MUST BE REVIEWED AND APPROVED BY THE COMMUNITY SERVICES DEPARTMENT.
- 3.) EROSION, SEDIMENT AND DETENTION CONTROL FACILITY SHALL BE INSTALLED & STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM TEMPORARY DIVERSIONS MAY BE REQUIRED. POST CONSTRUCTION STORM WATER MANAGEMENT PRACTICES MUST BE INITIATED AND STABILIZED EARLY IN THE PROCESS.
- 4.) CLEAR, CUT AND DISPOSE OF DEBRIS IN APPROVED FACILITY
- 5.) CONSTRUCT TEMPORARY CULVERTS AS REQUIRED, OR DIRECTED
- 6.) CONSTRUCT ROADWAYS FOR ACCESS TO DESIRED CONSTRUCTION AREAS. ALL ROADS SHALL BE STABILIZED IMMEDIATELY
- 8.) INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. INSTALL RAIN GARDENS. ALL DISTURBED AREAS SHALL STABILIZED IMMEDIATELY AFTER GRADING.
- 9.) BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SEEDED OR MULCHED AS REQUIRED, OR DIRECTED. NO AREA IS ALLOWED TO BE DISTURBED FOR A LENGTH OF TIME THAT EXCEEDS 60 DAYS BEFORE BEING STRBUZED. DAILY, OR AS REQUIRED. ALL ROADWAYS AND PARKING AREAS SHALL BE STABLIZED. THIN THIN 72 HOURS OF ACHIEVING FINISHED GRADES. ALL CUT AND FILL SLOPES SHALL BE STABLIZED WITHIN 72 HOURS OF ACHIEVING FINISHED.
- 10.) CONSTRUCT TEMPORARY BERMS, DRAINS DITCHES, SILT FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.
- 11.) INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION. ALL SWPPP INSPECTIONS MUST BE CONDUCTED BY A QUALIFIED PROFESSIONAL SUCH AS A PROFESSIONAL ENGINEER (PE). A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CIPECO). A CERTIFIED EROSION SEDIMENT AND STORM WATER INSSECTIOR (CESSIV) AC CERTIFIED PROFESSIONAL STORM WATER QUALITY (CPSWQ). INSPECTION REPORTS SHALL BE SUBMITTED TO THE COMMUNITY SERVICES DEPARTMENT.
- 12.) COMPLETE PERMANENT SEEDING AND LANDSCAPING.
- 13.) REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE
- 14.) SMOOTH AND REVEGETATE ALL DISTURBED AREAS.
- 15.) FINISH PAVING ALL ROADWAYS.
- NOTE: CITY OF DOVER'S "CONSTRUCTION GUIDELINES, PERMITS, RULES AND REGULATIONS" ARE A PART OF THIS PLAN SET AND THE MORE RESTRICTIVE WILL GOVERN. (D-CGPRR)

POUNDS POUNDS PER PER ACRE 1,000 S.F.

OCTOBER. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.

- . MULCH A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER
- SEEDING.

 B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANACEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90LBS PER 1000 S.F.
- 5. MAINTENANCE TO ESTABLISH A STAND A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH.
- B FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTA
- FERTILIZE IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHED.

 FERTILIZE IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHED.

 BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.

 IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED,

 OCCASIONAL MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

 TO BE CONSTRUCTED IAW NH SWM #3 4-1 EROSION CONTROL PRACTICES, PERMANENT VEGETATION, PAGE 60.

E18 DEFINITION OF STABLE:

PER ENV-WQ 1500 ALTERATION OF TERRAIN

- BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED.
 A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED.
 A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP-ARP HAS BEEN INSTALLED.

ADDITION STABILIZATION NOTES:

- HAY MULCH OR OTHER APPROVED METHODS SHALL BE USED TO CONTROL
- HAY MULCH OR OTHER APPROVED METHODS SHALL BE USED TO CONTROL EROSION OF NEWLY GRADED AREAS. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS AFTER THEIR CONSTRUCTION. DISTURBED SOIL AREAS SHALL BE EITHER TEMPORARILY OR PERMANENTLY STABILIZED. IN AREAS WHERE FINAL GRADING HAS NOT OCCURRED, TEMPORARY STABILIZED TO MEASURES SHOULD BE IN PLACE WITHIN SEVEN (7) CALENDAR DAYS FOR EXPOSED SOIL AREAS THAT ARE WITHIN ONE HUNDRED (100) FEET OF A SURFACE WATER BODY OR A WETLAND AND NO MORE THAN 14 CALENDAR DAYS FOR ALL OTHER AREAS, PERMANENT STABILIZATION SHOULD BE IN PLACE WITHIN THREE (3) CALENDAR DAYS FOLLEDAR DAYS FOLLEDAR DAYS FOLLEDAR AREAS.

WINTER STABILIZATION NOTES

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR TO OCTOBER 15TH SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES OR DETENTION BASINS, SHALL BE LINED WITH BIODEGRADABLE/PHOTODEGRADABLE "JUTE MATTING" (EXCELSIOR'S CURLEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL AREAS WILL BE STABILIZED, AS DIRECTED ABOVE.

3. PRIOR TO OCT. 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS ELEVATIONS ARE PROPOSED TO REMAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE ROUGHLY CROWNED AND A 3" LAYER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND WILL REDUCE ROADWAY EROSION. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 304-3, BUT SHALL HAVE BETWEEN 15-25% PASSING THE #200 SIEVE AND THE LARGEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT MILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH, ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT FENCING.

E21

2. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPRAP WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED.

OF NEW HAY KENNETH BERRY No. 14243 LICENSED IN SHEET 31 OF 35

E - 102

RIN(ROAD 8 m

00

CREEPING RED FESCUE (24%) 15 0.12 ANNUAL RYEGRASS (8.5%) PERENNIAL RYEGRASS (8.5%) 5 KENTUCKY BLUEGRASS (24%) 15 WHITE CLOVER (11%) B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE.

METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING, WHERE BROADCASTING IS

USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.

C. REFER TO TABLE(G-E1 THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-E1 THIS SHEET) FOR RATES OF SEEDING. ALL LEGUMES (CROWNVETCH, BIRDSFOOT TREFOIL, AND FLATTEA) MUST BE INOCLULATED WITH THEIR SPECIFIC INOCULANT.

D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY

0.45 0.45 0.05 0.95

0.35 0.25 0.35

0.45 0.75

30 0.75 40 0R 55 0.95 OR 1.35

E204" TOPSOIL (MIN.) AND SEED TO ESTABLISH APPROVAL. 1.) NAG BIONET S 150 BN 3:1 TO 2:1 SLOPE 2.) NAG BIONET SC 150 BN 2:1 TO 1:1 SLOPE

ANCHOR HOOK PER 3.) NAG BIONET SC 125 BN 1:1 AND GREATER MANUFACTURER'S REQUIREMENTS

TO BE CONSTRUCTED IAW NH SWM #3 4-1 EROSION CONTROL PRACTICES, TEMPORARY EROSION CONTROL BLANKET, PAGE 68.
ANOHOR PATTERN AND INSTALLATION INSTRUCTIONS FROM


ROLLED EROSION CONTROL BLANKET (RECB) SLOPE STABILIZATION DETAIL


INSTALL ROLLED EROSION CONTROL BLANKET WITH ANCHOR HOOKS AS PER MANUFACTURES REQUIREMENTS. SUBMIT SHOP DRAWINGS FOR


4.) AFC CURLEX II 1.5H TO 1V

NORTH AMERICAN GREEN (NAG) AND AMERICAN EROSION
COMPANY (AEC) WILL BE FOLLOWED FOR EACH APPLICATION
AND SLOPE CONDITIONS WILL APPLY.

NOT TO SCALE








NOT TO SCALE

U-101SHEET 34 OF 35



PERENNIAL PLANTING DETAIL

TYPICAL POST & RAIL FENCE DETAIL

NOTES: SCARIFY ROOT MASS OF CONTAINERIZED PLANT MATERIAL. INSTALL CONTAINERIZED PLANTS AT FINSHED GRADE TAMP PLANTING MIX FIRMLY AS PIT IS FILLED AROUND EACH PLANT BALL. 4. OMIT COLLAR AROUND EACH SHRUB WHEN IRRIGATION SYSTEM IS PRESENT. SOAK EACH PLANT BALL AND PIT IMMEDIATELY AFTER INSTALLATION. TYPICAL PLANTING BED DETAIL 000000

SHRUB & HEDGE PLANTING

L6

- CALL DIG SAFE PRIOR TO BEGINNING WORK. (1-888-344-7233). THE LANDSCAPE CONTRACTOR IS ADVISED OF THE PRESENCE OF UNDERGROUND UTILITIES AND SHALL VERIFY THE EXISTENCE AND LOCATION OF THE SAME BEFORE COMMENCING AND DIGGING OPERATIONS. THE LANDSCAPE CONTRACTOR SHALL REPLACE OR REPAIR UTILITIES, PAVING, WALKS, CURBING, ETC DAMAGED IN PERFORMANCE OF THIS JOB AT NO ADDITIONAL COST TO THE OWNER OR GENERAL CONTRACTOR.
-) CONTRACTOR SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH ALL SITE CONDITIONS PRIOR TO CONSTRUCTION BIDDING. SEE NOTE XXX ON OVERALL SITE PLAN.
-) PROVIDED SMOOTH TRANSITION WHERE NEW WORK MEETS EXISTING CONDITIONS
- ALL PLANT MATERIAL INSTALLED SHALL MEET THE SPECIFICATIONS OF "AMERICAN STANDARD FOR NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
-) ALL PLANTINGS SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING STAKING OR GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNTIL ACCEPTANCE FROM OWNER.
- ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING
-) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF EXISTING AND NEWLY PLANTED TREES AND SHRUBS DURING THE CONSTRUCTION PROCESS. WHERE REQUIRED, THE CONTRACTOR SHALL INSTALL TEMPORARY FENCING (SNOW OR EQUAL) AROUND EXISTING THE CONSTRUCTION PROCESS. STORAGE OF CONSTRUCTION EQUIRENT, CONSTRUCTION MATERIALS, SNOW STORAGE AND OR VEHICLE PARKING SHALL NOT BE PERMITTED WITHIN THE DRIP LINE OF TREES OR TWENTY FEET WHICH
-) NEW PLANTINGS SHALL BE INSTALLED PER PROJECT DRAWINGS AND SPECIFICATION THAT INCLUDE FERTILIZATION AND MULCHING AS REQUIRED.
-) WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR GROUND COVER AND PERENNIAL BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL, TWO PARTS SPHAGNUM PEAT MOSS, AND ONE PART HORTICULTURAL PERLITE BY VOLUME. PEAT MOSS MAY BE SUBSTITUTED WITH WELL-ROTTED OR DEHYDRATED MANURE OR COMPOST. ROTOTILL BEDS TO A DEPTH OF 8 INCHES.
-) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY EROSION CONTROL MEASURES DURING THE CONSTRUCTION PHASE AND UNTIL ALL AREAS HAVE BEEN STABILIZED AND ACCEPTED BY THE OWNER. THE GENERAL CONTRACTOR SHALL PROVIDE WEEKLY INSPECTIONS OF EROSION MEASURE AND IMMEDIATELY AFTER STORM EVENTS AND REPAIR AS NECESSARY.
- .) THE GENERAL CONTRACTOR AND OR THE LANDSCAPE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL THREE GUYING MATERIAL ONCE PLANT MATERIAL HAS BEEN ESTABLISHED. (MINIMUM OF ONE GROWING SEASON). ALL TEMPORARY EROSION CONTROL MEASURE SHALL BE REMOVED ONCE STABILIZATION OF DISTURBANCE HAS BEEN ACCEPTED BY OWNER.
-) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM OF TWO MOWINGS FOR ALL TURF AREAS OR UNTIL ACCEPTANCE BY THE OWNER. A MINIMUM UNIFORM 75% CATCH OF TURF IS REQUIRED FOR ACCEPTANCE.
- 16.) ALL PLANTINGS SHALL BE WATERED REGULARLY DURING THEIR FIRST YEAR AND MAINTAINED PERMANENTLY IN GOOD GROWING CONDITION AS AN EFFECTIVE VISUAL SCREEN.
-) SHRUBS OR TREES WHICH DIE SHALL BE REPLACED WITHIN ONE GROWING SEASON WITH NEW SHRUBS OR TREES TO ENSURE CONTINUED COMPLIANCE WITH APPLICABLE LANDSCAPING REQUIREMENTS.
- 18.) ALL REQUIRED LANDSCAPING SHALL BE INSTALLED BEFORE OCCUPANCY, OR WITHIN SIX MONTHS IF OCCUPANCY OCCURS DURING WINTER CONDITIONS.
-).) TREES ARE TO BE 2-2.5" CALIPER 6" OFF THE ROOT BALL.
- 20.) ALL PLANT STOCK SHALL CONFORM TO ANSI Z260.1 NURSERY STOCK, LATEST EDITIONS (AMERICAN ASSOCIATION OF NURSERYMEN, INC.)
- .) 4" AGED PINEBARK MULCH AND A WEED BARRIER (TY-PAR FABRIC OR APPROVED EQUAL) SHALL BE APPLIED TO ALL SHRUB AND GROUND COVER BEDS. INSTALL WEED BARRIER AS PER MANUFACTURERS RECOMMENDATIONS.
- 22.) PLANT-PIT BACK-FILL SHALL BE MIXED AT A RATE OF 7 PARTS OF TOPSOIL TO 2 PARTS OF DEHYDRATED COW MANURE. SLOW RELEASE FERTILIZER SHALL BE APPLIED AS PER MANUFACTURERS RECOMMENDATIONS. USE EXISTING ON—SITE TOPSOIL AS PART OF BACK FILL WHEN AVAILABLE.
- 5.) ALL LANDSCAPED AREAS NOT PLANTED WITH TREES, SHRUBS OR GROUNDCOVER SHALL BE RESTORED WITH SEED OR SOD AS INDICATED ON PLANS.

TYPICAL PLANTING BED PLAN

ECOND TON, 335 BARRII



L-101