



NONRESIDENTIAL SITE PLAN APPLICATION BY_

City of Rochester, New Hampshire

Date: 11-10-20 Is a	conditional use needed? Yes: No:_X
	o, we encourage you to submit an application as soon as possible.
Property information	
Tax map #: <u>246</u> ; Lot #('s)	: 22 ; Zoning district: Highway Commercial (HC)
Property address/location: Wash	ington Street
Name of project (if applicable): _H	domeless Center for Strafford County
Size of site: 19.24 acres; over	lay zoning district(s)? Wetland
Property owner	
Name (include name of individual	l): Homeless Center For Strafford County
Mailing address: 9 Isinglass Drive P.O	
Telephone #: 603-332-3065	Email: Execdirshelter@gmail.com
Applicant/developer (if different Name (include name of individual	ent from property owner)
Mailing address:	
Telephone #:	S.
Engineer/designer Name (include name of individual)	
	n Point Rd, Barrington, NH 03825
Telephone #: 603-332-2863	Fax #:
K.Berry@BerrySur crberry@metrocas	veying.com Professional license #: 14243
Proposed activity (check all that New building(s): X Site de	at apply) evelopment (other structures, parking, utilities, etc.): X
Addition(s) onto existing building(s	s): Demolition: Change of use:
	Page 1 (of 3 pages)
\\roch-fileshare\plan\$\Forms\Applications\Site Plan - No 3/27/2019	onresidential doc Updated

Proposed post-development disposition of site (should total 100%)			
Square footage % overall s			
Building footprint(s) – give for each building	2,680	0.32	
Parking and vehicle circulation	7,837	0.94	
Planted/landscaped areas (excluding drainage)	34,455	4.11	
Natural/undisturbed areas (excluding wetlands)	566,265	67.53	
Wetlands	226,986	27.10	
Other – drainage structures, outside storage, etc.	0	0	

100%

Updated

Page 2 (of 3 pages)

Comments	
Please feel free to add any comments, additional information, or requests for waivers h	nere:
	,0,0,
Submission of application	
This application must be signed by the property owner, applicant/developer (if different property owner), and/or the agent.	from
I(we) hereby submit this Site Plan application to the City of Rochester Planning Board	
pursuant to the <u>City of Rochester Site Plan Regulations</u> and attest that to the best of me knowledge all of the information on this application form and in the accompanying applications and documentation is true and accurate. As applicant/developer (if different the property owner)/as agent, I attest that I am duly authorized to act in this capacity.	ination
Signature of property owner: Tay I Hard Korl - 8	?, D.
Date: 1/19/2000	Appendix of the second
Signature of applicant/developer:	
Signature of agent:	
Date: 11-10-7020	
Authorization to enter subject property	
hereby authorize members of the Rochester Planning Board, Zoning Board of Adjustm Conservation Commission, Planning Department, and other pertinent City departments, to boards and agencies to enter my property for the purpose of evaluating this application including performing any appropriate inspections during the application phase, review placet-approval phase, construction phase, and occupancy phase. This authorization appropriately to those particular individuals legitimately involved in evaluating, reviewing, conspecting this specific application/project. It is understood that these individuals must use assonable care, courtesy, and diligence when entering the property.	hase, olies
ignature of property owner:	D.
och-fileshare\plan\$\Forms\Applications\Site Plan - Nonresidential.doc Updated	



BERRY SURVEYING & ENGINEERING

335 Second Crown Point Road Barrington, NH 03825 Phone: (603) 332-2863 Fax: (603) 335-4623 www.BerrySurveying.Com crberry@metrocast.net

November 10, 2020

City of Rochester Planning Board Attention: Chief Planner, Seth Creighton 33 Wakefield Street Rochester, NH 03867

Re:

Homeless Center for Strafford County (HCSC) Route 202 / Washington Street & Chesley Hill Road

Rochester Tax Map 246, Lot 22

Mr. Creighton,

On behalf of our client, HCSC, Berry Surveying & Engineering (BS&E) is submitting for TRG review a proposed homeless shelter within the Highway Commercial (HC) Zone located at 202 Washington Street (US Route 202).

Background and General Narrative:

HCSC has purchased the property on the corner of Chesley Hill Road and Washington Street (Route 202) the property is located within the HC Zone where the Shelter use is being proposed. BS&E has completed a full topographic survey and John P. Hayes, CWS, CSS has delineated wetlands on site in addition to providing soils data on an as needed basis. The Axe Handle Brook is located on site and has a corresponding flood zone, with an obvious wetlands complex surrounding it. Axe Handle Brook has a 100' local buffer protection, with the surrounding wetlands being afforded a 50' setback requirement. There is a small tributary which crosses Washington Street, with surrounding wetlands which also require a 50' setback. There is a small wetland located near the municipal easement on the property in south west corner. This wetland is likely man made during the construction and maintenance of the easement and is under a half an acre in size. This area was evaluated by John Hayes and determined not to be a vernal pool based on the contributing topography and underlying soils conditions not supporting ponding for long periods of time.

There is a flatter area onsite with a small looping entrance onto and off Washington Street. Test holes on site as well as geotechnical borings have revealed that this area is comprised of general fill materials with varying depths. Due to this, the design uses the flat area for access and potential parking only. Due to the curvature and vertical alignment of Washington Street, the proposed driveway was chosen as the safest location to enter the site. It

Project Narrative, HCSC Washington Street, Rochester, NH

November 10, 2020 Page 2 of 3

offers 400 feet of sight distance in both directions (NHDOT Standard). This location is approximately 375 linear feet from the intersection of Chesley Hill Road.

The Proposal:

The proposal is to construction a 2,584 SF building foot print that contains two stories for the purposes of temporarily housing up to 40 individuals. This maximum of 40 individuals will be housed within 10 temporary housing units. These are often times families housed in these units. The building design has an approximate total of 5,168 SF plus a full walk out basement for storage and mechanical items. The current location for this use and facility is located at Waste Management, which is slated for demolition in 2021 due to an expansion taking place on Rochester Neck Road. An operation plan will be submitted for review for a full understanding of the day to day operations of the facility.

In general the site has one or two employees on site during critical hours only and the residents need very little parking. There is a large reliance on buses, taxis and other public transit to and from school or work. The operation plan includes providing shuttling services to and from the Coast Bus Stop up the street from the project site. The use of "Assisted Living" was used in the parking calculations whereas this seemed to be the closest parking land use code. A conservative assumption was made that each temporary housing unit will contain two driving adults/room. Using the Assisted Living Use code, it is determined that 15 parking spaces are required. Based on the current HCSC parking demands, the client feels this is an adequate number of parking spaces.

Municipal water will be provided to the site and onsite septic facilities will be required. A NHDES Sewage Disposal permit will be required. Stormwater will be handled using standard methodology for detention, volume and treatment standards prescribed in Chapter 218. Porous asphalt pavement will provide treatment and attenuation of post construction stormwater flows. A NHDOT permit is required and has been applied for. A NOI is required for this project and will be applied for.

Several modifications to the project site have occurred since TRG submission. The most notable change is the mirroring of the site in order to save construction costs. By placing the building along the eastern side of the fill slope, the existing slope can be used to provide a basement walkout. This building placement also is more conducive for the construction of an effluent disposal area (EDA). This allows the prior building location to be filled and used as recreational space. From a stormwater perspective, the site has been modified from utilizing a series of rain gardens and level spreaders to a single porous asphalt pavement system with infiltration. The infiltration provided from the porous asphalt pavement allows the post-construction stormwater peak rate and runoff volume for all events to be less than the existing condition. Stormwater management taking place under the pavement also creates less overall disturbance by reducing the need for above ground stormwater best management practices. There is one lamp down lit proposed and it will be shielded. There will be residential style on the lights

BERRY SURVEYING & ENGINEERING

335 Second Crown Pt. Rd., Barrington, NH 03825
Y SURVEYING
& ENGINEERING

(603) 332-2863 / (603) 335-4623 FAX
WWW.BerrySurveying.Com



Project Narrative, HCSC Washington Street, Rochester, NH

November 10, 2020 Page 3 of 3

on the building. A street tree buffer will be placed along the right-of-way, but allow architectural features to show through. Evergreens will be placed along the right-of-way for the recreation area.

Respectfully submitted,
BERRY SURVEYING & ENGINEERING

Kevin, R. Poulin, EIT Project Engineer

Christopher R. Berry, SFT Principal, President



BERRY SURVEYING & ENGINEERING

335 Second Crown Pt. Rd., Barrington, NH 03825 (603) 332-2863 / (603) 335-4623 FAX www.BerrySurveying.Com



Project Information:

Our shelter and programming addresses the growing problem of family homelessness in New Hampshire as housing costs for rentals continue to climb and as the percentage of income needed for housing increases for New Hampshire families and individuals. Vacancies for low income housing is limited; the impact that this is having is a decrease in the number of housing rentals in the Seacoast Area.

The outcome we expect from this project is both an increased capacity to serve New Hampshire residents experiencing homelessness and the ability to continue our mission into the third decade of existence. We further expect to be located in a location that better serves the clientele with increased access to services, transportation and employment opportunities.

MISSION, VISION and VALUES

The Homeless Center for Strafford County (HCSC) provides community members and families with shelter, case management, and educational programs that lead to self-sufficiency and permanent housing.


Our Vision is to provide the best evidence based, two generational approach to eliminating community homelessness in a dignified and respectful manner.

The Homeless Center for Strafford County Operates with compassion and inclusivity resulting in:

- Safe Environment: Home-like, Secure, Clean, and Communal
- Community Connection: Engagement, Funding, Staffing, and Resource Sharing
- Effectiveness: Goal-Oriented and Family-Focused Educational Programs

Structure: There are seven employees reporting directly to the Executive Director who reports to the Board of Directors for this 501 (C) 3 and the Board operates using Robert's Rules of Engagement. The Center has 42 Volunteers that perform various project work on an as needed basis or greet sheltered clients as they come and go weekdays.

Governance: The Homeless Center for Strafford County is governed by a Board of Director's with an Executive Director leading all operational goals and providing input to Mission, Vision and Values. Our financial well being is overseen by a CPA firm that also performs all bookkeeping duties.



Entry Requirements for Client: Sheltered clients participate in entry by telephone contact first. Walk In sheltering is not allowed. Phone intake processes of 30 minutes to an hour occur before entry. Clients are to be substance free upon entry and testing is performed on site randomly and as needed. Clients are expected to fully participate in all programming and to be working with case management at full capacity to find and obtain permanent housing.

Clients are expected to be able to self care at all times as medical services and homemaker services are not offered at the facility. All clients are screened using a state criminal background check.

Adult Clients are actively involved in work, work search, housing search or schooling daily.

Programming Offered On Site:

All residents participate daily in multiple areas of our programming. This is required of all sheltered clients.

Comprehensive Programming Areas:

- -Resume Creation -Job Interview Skills -Employment Searches -Housing Searches
- -Landlord Advocacy -Financial Literacy -Reading Literacy -Bridge to External Services
- -Budgeting Skills -Nutritional Classes -Nurturing Parenting Classes
- -Support for obtaining High School Equivalency -Support for College Enrollment
- -Connections to Work Apprenticeships -Support for obtaining and reinstating Driver's Licensing
- -Physical and Mental Health Insurance Enrollment -Childhood reading programming
- -Children's Enrichment Classes (Cooking, Yoga, Karate, Crafts)

Organization Size: Currently HCSC (The Homeless Center for Strafford County) offers sheltering for up to 26 individuals in six family style rooms at the location of 9 Isinglas Drive, Rochester, New Hampshire.

At the new location on Washington Street in Rochester, New Hampshire ten family style rooms in five pods with a shared bath between two rooms, will shelter up to 40 individuals. Most often in family units with parents and school aged children.

Additional Size: On site 24/7 is a single staff member or a trained volunteer. Staff overlap shifts and use electronic files and communications to trade off information shift to shift.

Operations:

Cooking is scheduled and staggered for families each night. This allows the kitchen to have just two adults at time cooking meals.

	110

Laundering is staggered weekly and families or individuals are designed a day of laundering.

Each of two family bedrooms shares a bathroom which is cleaned daily.

Upon entry all soft items are run through dryers to ensure no pests are brought into the facility. Clients are all provided new bedding, new pillows and take these items with them when placed in permanent housing.

Trash is take out to the dumpster daily.

Each pod consisting of two bedrooms has a fridge/freezer for food storage.

Rigid rules exists to ensure a trauma free environment that is family like with dignified and respectful language and behaviors expected from clients and staff at all times.

Meetings with Case Management occurs frequently throughout weekdays.

A library and computer access is available each day.

Television viewing exists for two hours daily after dinners and chores are complete.

School Vacations are scheduled with school age specific activities off site.

Operational Flow to/from the physical location:

HCSC has some clientele with owned vehicles. These owned vehicles will be parked on site. Vehicles may only be parked on site if currently *registered* and *inspected* based on New Hampshire state requirements. School aged children residing at the shelter will be bused/taxied to school from the Facility.

Meals are provided on-site from the operational funding and groceries are brought in weekly and monthly from store purchases or USDA pick up by staff only. Meals are not communal, each family or individual prepares their own food.

Each morning and Afternoon a staff member brings adult clients to and from the bus stop at the park and ride area using vehicles owned by staff and the shelter.

Each morning, afternoon and evening clients leave for work roles or work searches or for appointments.

With only an exception for work schedules or school trips, adult clients must be in the building between 10pm and 6pm. Children of all ages are in bed between 7:30pm and 9:00pm nightly dependent on age.

Safety and Safety Training: All staff and volunteers are trained in Emergency Operations for Fire Alarms and Building Evacuation, Usage of Fire Extinguishers and Staff are trained in CPR and Mental Health First Aid.

Means of Egress are monitored throughout each shift. Sprinkler systems will be installed throughout the building.

Rules and Safety are covered weekly at house meetings. The Cleanliness of the communal facility is handled by a rigorous chore program that involves residents and staff in the daily cleaning of the facility.

The interior layout and gating for small children, along with cabinet locks, outlet coverings and other typical family style safety measures are used to protect small children. Bunk beds are screwed to wall structures and only lower centered furniture is used in rooms.

The external and internal camera systems allows for viewing of the property and building.

The shelter locks all medications both prescribed and over the counter in a vaulted area with sign outs by clients as needed.

There has been two ambulance calls in the past 24 months and zero police calls during the same period of time.

Design Build Process:

The Homeless Center for Strafford County has chosen a Design/Build Process and after conducting a spaces needs assessment the New Building Task Force developed a Request For Proposal that is being distributed in July/August 2020.

Upon return of the Proposals from area Design Builders the company will be selected.

Many In Kind donations have been committed by community businesses and the Board of Directors has specifically chosen to obtain funding in a manner that will allow the community shelter to be built by community businesses and volunteers.

The lighting fixtures, foundation, playground equipment and installation, network cabling, interior painting, water hook ups, site surveying and engineering have all be committed as in kind donations to the build.

Site Studies including Geo Technical and Environmental Studies have been performed and DOT traffic studies submitted.

All construction management will be done by the selected design builder with oversight by the HCSC new building task force. (made up of staff, board of directors and community members)

The Project Budget is \$1,000,000 with 25% of funding for land and 75% of funding for the expected 5300 sq. ft. building.

New Furnishings have been obtained via donations from various funding sources and meet all code requirements for furnishings.


1		
1		

Playground Placement behind the building has been intentional to ensure that children are safe and that neighbors will not hear children at play.

Attached please find the RFP for the design build process Appendix A and the proposed conceptual drawings for floors one and two Appendix B.

Summary: A successful shelter creates a pleasant environment for the clients served, the public, and the staff/volunteers. Controlling noise and vehicle traffic plays a significant role in the design of this community and neighbor friendly facility. The design build process and operations of this building have been intentional in the planning stages to increase the practical performance of the operations at this new location.

l		
1		



NOTE:


#2 11-10-20 REWSED PER CLIENT REQUEST #1 9-9-20 SUBMITTED FOR NHOOT DRIVEWAY PERMIT FVISION DATE


MAJOR SITE PLAN
AND OF HOMELESS CENTER FOR STRAFFORD COUNTY
U.S. ROUTE 202 / 202 WASHINGTON STREET
ROCHESTER, N.H.
TAX MAP 246, LOT 22


SURVEYING & ENGINEERING OND CROWN POINT ROAD N. NH 03825 (603)332-2863

BERRY SUI












CLE 11-10-20 9-9-20 ##

CONDITIONS PLAN
NTER FOR STRAFFOR
202 WASHINGTON S
IESTER, N.H.
P 246, LOT 22 HOMELE LAND OF U.S.

S OND ON HN







244

240

1+75

E 253.65

1+25

1+50

244

240

0+00

0+25

E 253.33

0+50

0+75


1+00


REQUES


#2

DRIVEWAY PLAN & P
F HOMELESS CENTER FOR S1
ROUTE 202 / 202 WASHIN
ROCHESTER, N.H.
TAX MAP 246, LOT

LAND OF U.S.







GRAPHIC SCALE

(IN FEET)

1 inch = 20 ft.

VERTICAL SCALE: 1" = 4'



REQUEST RIVEWAY PE

** S

Y PLAN & F CENTER FOR 2 / 202 WAS OCHESTER, N MAP 246, 1

HOMELE ROUTE


LAND OF U.S.


BERR


335 BARRING

KENINETH

Const







NOTES:

- CALL DIG SAFE PRIOR TO BEGINNING WORK. (1-BBB-344-7233). THE LANDSCAPE CONTRACTOR IS ADVISED OF THE PRESENCE OF UNDERGROUND UTILITIES AND SHALL VERIFY THE EXISTENCE AND LOCATION OF THE SAME BEFORE COMMENCING AND DIGGING OPERATIONS. THE LANDSCAPE CONTRACTOR SHALL REPLACE OR REPAIR UTILITIES, PAWNO, WALKS, CURBING, ETC. DAMAGED IN PERFORMANCE OF THIS JOB AT NO ADDITIONAL COST TO THE OWNER OR GENERAL CONTRACTOR.
- 2. CONTRACTOR SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH ALL SITE CONDITIONS PRIOR TO CONSTRUCTION BIDDING.
- THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTINGS SHOWN ON THE DRAWINGS. VARIATIONS IN QUANTITIES ARE TO BE APPROVED BY THE DESIGN ENGINEER.
- PROVIDED SMOOTH TRANSITION WHERE NEW WORK MEETS EXISTING CONDITIONS
- ALL PLANT MATERIAL INSTALLED SHALL MEET THE SPECIFICATIONS OF "AMERICAN STANDARD NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN
- 6. ALL PLANT MATERIALS SHALL BE FREE FROM INSECTS AND DISEASE.
- 7. ALL PLANTINGS SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING STAKING OR GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNTIL ACCEPTANCE FROM OWNER.
- ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF EXISTING AND NEWLY PLANTED TREES AND SHRUBS DURING THE CONSTRUCTION PROCESS. WHERE REQUIRED, THE CONTRACTOR SHALL INSTALL TEMPORARY FENCING (SNOW OR EQUAL) AROUND EXISTING TREES AND SHRUBS THAT COULD BE IMPACTED BY THE CONSTRUCTION PROCESS. STORAGE OF CONSTRUCTION EQUIPMENT, CONSTRUCTION MATERIALS, SNOW STORAGE AND OR VEHICLE PARKING SHALL NOT BE PERMITTED WITHIN THE DRIP LINE OF TREES OR TWENTY FEET WHICH EVER IS GREATER.
- NEW PLANTINGS SHALL BE INSTALLED PER PROJECT DRAWINGS AND SPECIFICATION THAT INCLUDE FERTILIZATION AND MULCHING AS REQUIRED.
- 11. ALL SHRUB BEDS AND TREE PITS SHALL BE MULCHED WITH 3" CLEAN SHREDDED BLACK MULCH

- 12. WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR GROUND COVER AND PERENNIAL BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL, TWO PARTS SPHAGNUM PEAT MOSS, AND ONE PART HORTICULTURAL PERUTE BY VOLUME. PEAT MOSS MAY BE SUBSTITUTED WITH WELL—ROTTED OR DEHYDRATED MANURE OR COMPOST. ROTOTILL BEDS TO A DEPTH OF 8 INCHES.
- 13. MAINTENANCE OF NEW PLANTINGS AND LAWNS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR AND OR LANDSCAPE SUBCONTRACTOR UNTIL ACCEPTANCE BY THE OWNER. RESPONSIBILITIES SHALL INCLIDE WATERING WEEDING AND MOWING AS NECESSAY, ALL PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE, REPLACEMENT MATERIAL SHALL BE GUARANTEED FOR AND ADDITIONAL YEAR FROM TIME OF INSTALLATION.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY EROSION CONTROL MEASURES DURING THE CONSTRUCTION PHASE AND UNTIL ALL AREAS HAVE BEEN STABILIZED AND ACCEPTED BY THE OWNER. THE GENERAL CONTRACTOR SHALL PROVIDE WEEKLY INSPECTIONS OF EROSION MEASURE AND IMMEDIATELY AFTER STORM EVENTS AND REPAIR AS NECESSARY.
- 15. THE GENERAL CONTRACTOR AND OR THE LANDSCAPE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL THREE GUYING MATERIAL ONCE PLANT MATERIAL HAS BEEN ESTABLISHED. (MINIMUM OF ONE GROWING SEASON). ALL TEMPORARY EROSION CONTROL MEASURE SHALL BE REMOVED ONCE STABILIZATION OF DISTURBANCE HAS BEEN ACCEPTED BY OWNER.
- 16. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM OF TWO MOWINGS FOR ALL TURE AREAS OR UNTIL ACCEPTANCE BY THE OWNER. A MINIMUM UNIFORM 75% CATCH OF TURE IS REQUIRED FOR ACCEPTANCE.
- ALL PLANTINGS SHALL BE WATERED REGULARLY DURING THEIR FIRST YEAR AND MAINTAINED PERMANENTLY IN GOOD GROWING CONDITION AS AN EFFECTIVE VISUAL SCREEN.
- ALL REQUIRED LANDSCAPING SHALL BE INSTALLED BEFORE OCCUPANCY, OR WITHIN SIX MONTHS IF OCCUPANCY OCCURS DURING WINTER CONDITIONS.
- 20. TREES ARE TO BE 6' TALL AT PLANTING.
- 21. ALL PLANT STOCK SHALL CONFORM TO ANSI Z260.1 NURSERY STOCK, LATEST EDITIONS (AMERICAN ASSOCIATION OF NURSERYMEN, INC.)
- 22. 4" AGED PINEBARK MULCH AND A WEED BARRIER (TY-PAR FABRIC OR APPROVED EQUAL)

- L BE APPLIED TO ALL SHRUB AND GROUND COVER BEDS. INSTALL WEED BARRIER AS MANUFACTURERS RECOMMENDATIONS.
- 23. PLANT-PIT BACK-FILL SHALL BE MIXED AT A RATE OF 7 PARTS OF TOPSOIL TO 2 PARTS OF DEHYDRATED COW MANURE. SLOW RELEASE FERTILIZER SHALL BE APPLIED AS PER MANUFACTURERS RECOMMENDATIONS. USE EXISTING ON-SITE TOPSOIL AS PART OF BACK FILL WHEN AVAILABLE. FILL WHEN AVAILABLE.
- 24. ALL LANDSCAPED AREAS NOT PLANTED WITH TREES, SHRUBS OR GROUNDCOVER SHALL BE RESTORED WITH SEED OR SOD AS INDICATED ON PLANS.
- 25. TOPSOIL WILL BE TESTED FOR FERTILIZATION REQUIREMENTS, AND SLOW RELEASE ENVIRONMENTALLY FRIENDLY FERTILIZER WILL BE APPLIED AT THE RECOMMENDED RATES.
- 26. ALL DISTURBED WETLAND BUFFER AREAS, EXCEPT FOR AREAS THAT ARE PART OF THE DRAINAGE SYSTEM, ARE TO BE RESEEDED WITH A CONSERVATION SEED MIX AND ONLY MOWED TIMES PER YEAR.
- 27. ALL PLANT SUBSTITUTIONS MUST BE APPROVED BY THE ENGINEER.
- 28. PLANTS SHALL BE SUBJECT TO INSPECTION AND APPROVAL AT THE PLACE OF GROWTH, UPON DELIVERY OR AT THE JOB SITE WHILE WORK IS ONGOING TO CONFORMITY TO SPECIFIED QUALITY, SIZE AND VARIETY.
- 29. PLANTS FURNISHED IN CONTAINERS SHALL HAVE THE ROOTS WELL ESTABLISHED IN THE SOIL MASS AND SHALL HAVE AT LEAST ONE (1) GROWING SEASON. ROOT-BOUND PLANTS OR INADEQUATELY SIZED CONTAINERS TO SUPPORT THE PLANT MAY BE DEEMED UNACCEPTABLE.
- 30. ALL PLANTS SHALL BE GUARANTEED BY THE CONTRACTOR FOR NO LESS THAN ONE FULL YEAR FROM THE TIME OF INSTALLATION. DURING THIS TIME, THE OWNER SHALL MAINTAIN ALL PLANT MATERIALS IN THE ABOVE MANNER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT THE PLANTS TO ENSURE PROPER CARE. IF THE CONTRACTOR IS DISSATISFED WITH THE CARE GIVEN, HE SHALL IMMEDIATELY, AND IN SUFFICIENT TIME TO PERMIT THE CONDITION TO BE RECTIFIED, NOTIFY THE OWNER IN WRITING OR OTHERWISE FORFEIT HIS
- 31. BY THE END OF THE GUARANTEE PERIOD, THE CONTRACTOR SHALL HAVE REPLACED ANY PLANT MATERIAL THAT IS MISSING, NOT TRUE TO SIZE AS SPECIFIED, THAT HAS DIED, THAT HAS DIED, THAT HAS DIED, THAT HAS DIED, THAT OR IMPROPER CARE, OR IS, IN THE OPINION OF THE OWNER, IN UNHEALTHY OR UNSIGHTLY
- 32. THE CONTRACTOR IS TO USE TEMPORARY MEASURES FOR WATERING PLANTS DURING THE ESTABLISHMENT PERIOD. INCLUDING CONNECTING TEMPORARY HOSES TO THE STRUCTURE WATER SUPPLY LINE AND UTILIZING SPRINKLERS UNTIL 85% GROWTH OCCURS.

- LAYOUT OF ALL PLANTING BEDS AND LOCATION OF PLANTS TO BE APPROVED BY LA. ON SITE PRIOR TO INSTRUCTION AND INSTALLATION.

6. ALL REDG TO BE MULCHED WITH 3" DEPTH SHEEDED BARK MERCH UNLESS NOTED OTHERWISE

E ALL PLANT MATERIAL TO COMPLY WITH THE CITY OF DOVER'S SITE PEVEW REQULATIONS, 148-14(G), SUCH THAT THERE SHALL BE DECOUDLES SHADE THEES PLANTED 40 FEET D.C. ALONG THE PERMITTER OF THE PARKING LOTS AND SHRUES PLANTED 5 FEET D.C. WITHIN THE PERMITTER SUFFER. SEE PLANT LIST FOR SPECIES AND SIZE OF PLANTS.

- 1 CONTRACTOR IS RESPONSIBLE FOR MAKING SURE ALL PLANT MATERIAL HAS ADEQUATE WATER GURING THE ESTABLISHMENT PERIOD.

Size

3" Cal.

3" Cal

3" Cal.

3" Cal.

2-3' B&B

terrain

Qty Label

6

L TEMPORARY IRRIGATION SYSTEMS CAN BE SET UP TO ASSIST IN WATERING ACTIVITIES

PLANTING SCHEDULE

Washington Street Botanical Name / Common Name

Quercus rubra / Red Oak

Platanus Acerifolia/ London Plane Tree

Acer Rubrum / Red Maple

Picea glauca / White Spruce

Shrubs Comus sanguina 'Winter Flame' / Winter Flame Dogwood

terrain planning & design IIc

311 kast hill road hopkinton, nh 03229 603. 491. 2322 terrainplanning.com

WASHINGTON STREET

Site Location: Washington Street Rochester, NH Tax Map 246, Lot 22

Prepared For: Berry Surveying & Engineering 335 Second Crown Point Rd Barrington, NH 03825

LANDSCAPE PLAN

DATE:

SCALE: 1" = 20'

PROJECT #: 19-042

Drawn By: ID

Checked By: ERB

REVISIONS: DATE: Issued for Client Review

This plan is the property of Terrain Planning & Design LLC. Use or reproduction of this plan by any means without permission or purchase from Terrain Planning & Design LLC is prohibited.



SHEET 11 OF 24



General Plant Maintenance Guide

All paint instrumentor section or performed or a quamera increasariament or increase among under material autor of the planting bell of the fail heigh bell pitter from building up around the plantin and in power case. Willing the plantin. Watership the feet year during day periods will not get the plantin easts belief. Mulching every peer? Increa nocessary, hasting the cell without not strainful peer to sit material seadors. Mellon macessary sally install one linch of mulch and do not place the mulch closer than 1° to the trurks or stamm of woodly plantin.

The first year workning duting day periods will be necessary.


3º inches of mulch muybe used. The mulch should be kept 3 liches from the trank.

Familially in not measurary for the fixsy year. Familially is subsequent years only when and # the tollage is leading.

weak. Geriffizadion chould occur prior to Mon 31,5 or after trees have dropped their leaves for the year.

on should occur orier to Met 31" or efter struke have dropped their leaves or gone domaint for the

o not over reuids. Too reach muich will prohibit the grass from developing into a smoog clures.



NOTES:

HOMELESS CENTER FOR STRAFFORD COUNTY 9 ISNGLASS DR P.O. BOX 7306 ROCHESTER, NH 03839-7306 1. OWNER:

2. TAX MAP 246, LOT 32

3. LOT AREA: 838,223 Sq. Ft., 19.24 Ac.

4. S.C.R.D. BOOK 4748, PAGE 605

5. THE INTENT OF THIS PLAN IS TO PROVIDE THE LIGHTING SCHEME FOR THE PROPOSED SITE PLAN.


ALL LAMPS ARE SHOWN ON THE SITE PLAN WITH LOCATION, TYPE AND HEIGHT.

7. SEE CONSTRUCTION DETAILS FOR PRODUCT CUT SHEETS.

8. LAMP "A" MOUNTED 8' ON BUILDING LAMP "B" MOUNTED 18' ABOVE THE GROUND



hedule											
Symbol	Label	Quantity	Manufactur er	Catalog Number	Description	Lamp	Number Lamps	Filename	Lumens Per Lamp	Light Loss Factor	Wattage
	A MOUNTED @ 8'	5	Lithonia Lighting	ODSL10 SRC		ONE 13- WATT T4 SPIRAL COMPACT FLUORESCEN T, VERTICAL BASE UP POSITION.	1	ODSL10_SR C.ies	900	1	12.6
₽	B MOUNTED @ 18'	1	Lithonia Lighting	KAD 150S R4 HS	150W HPS,	ONE 150- WATT CLEAR ET-23.5 HIGH PRESSURE SODIUM, HORIZONTAL POSITION.	1	KAD_150S_R 4_HS.ies	16000	. 1	189




- HOMELESS CENTER FOR S.
ROUTE 202 / 202 WASHIN
ROCHESTER, N.H.
TAX MAP 246, LOT LAND OF U.S.


REVISED PER CLIENT REQUEST SUBMITTED FOR NHDOT DRIVEWAY PERMI


#2


KENINETH S Const

SHEET 12 OF 24










CENTERLINE AND EDGELINE "CUTS" AT SIDE ROAD



DETAIL-3

NOTES CONT .:

PM-9 GENERAL NOTES

EDGELINE TREATMENTS,

1.) EDGELINE DETAILS ARE SHOWN FOR MAINLINE ROADWAYS WITHOUT TURN LANE. THE PRESENCE OF TURN LANES MAY REQUIRE DIFFERENT

2.) EDGELINES ON THE SIDE ROADS, WHEN CALLED FOR, SHALL FOLLOW THE ABOVE MAINLINE TYPICALS. EDGELINES SHALL NOT BE CONTINUOUS AROUND THE MAINLINE/SIDE ROAD RADIUS. EDGELINES SHALL END AT STOP BARS.

3.) CENTERLINE AND EDGELINE SHALL BE CONTINUOUS PAST RESIDENTIAL DRIVEWAYS. CENTERLINE AND EDGELINE SHALL BREAK FOR COMMERCIAL DRIVES W/TRAFFIC CONTROLS, MINOR SIDE ROADS, OR PRIVATE INTERSECTIONS.

4.) LOCATION OF THE STOP LINE MAY VARY DUE TO INTERSECTION SIGHT DISTANCE AND VEHICLE TURNING RADIUS AND MAY NOT ALWAYS COINCIDE WITH THE LOCATION OF THE STOP SIGN.

5.) IF THERE IS NO EDGELINE, END STOP BAR 12" FROM EDGE OF PAVEMENT.

6.) STOP BARS, WORDS, LANE LINES, SYMBOLS AND ARROWS SHALL BE THERMOPLASTIC (T).

10.) THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERRIFLE BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO LOCATE EXACTLY AND TO PRESERVE ANY AND ALL UNDERGROUND UTILITIES CALL "DIG-SARE" 1-888-DIGSAFE (344-7233) AT LEAST 72 HOURS BEFORE COMMENCING CONSTRUCTION

11.) WHERE AN EXISTING UNDERGROUND UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION PURNISHED TO THE ENGINEER FOR RESOLUTION OF THE CONFLICT.

NOTES CONT .:

12.) THE CONTRACTOR SHALL MAKE ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENT OF GAS, ELECTRIC, TELEPHONE AND ANY OTHER PRIVATE UTILITIES BY THE UTILITY COMPANIES.

13.) AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.

14.) THE TERM "PROPOSED" (PROP.) MEANS WORK TO BE CONSTRUCTED USING NEW MATERIALS, OR, WHERE APPLICABLE. RE-USING EXISTING MATERIALS IDENTIFIED AS "REMOVE & RESET"

15.) ALL EXISTING SIGNS WITHIN THE PROJECT LIMITS SHALL BE RETAINED UNLESS NOTED OTHERWISE.

NOTES CONT .:

16.) ALL SYMBOLS, WORDS, TRANSVERSE MARKINGS (STOP BARS, CROSSWALK LINES, AND RAILROAD SYMBOLS), LANE LINES, AND ALL OTHER MARKINGS NOTED WITH (T) SHALL BE THERMOPLASTIC.

17.) ALL DISTURBED AREAS NOT DESIGNATED TO BE PAYED SHALL HAVE LOAM PLACED AND SEEDED. THE LOAM SHALL HAVE A MINIMUM DEPTH OF 4 INCHES AND SHALL BE PLACED FLUSH WITH THE TOP OF THE ADJACENT CURB, EDGING, BERM OR PAYEMENT SURFACE.

18.) THE CONTRACTOR SHALL CONTACT THE NHDOT BUREAU OF TRAFFIC AT (603) 271-2291 ONE WEEK PRIOR TO PAVEMENT MARKINGS.

19.) ALL PAVEMENT MARKINGS TO BE PAINTED TO NHDOT STANDARD NO. PM-9.

20.) THE SPEED LIMIT ON US ROUTE 202 IS 45 MPH.

SURVE SURVE ND CROWN SECOND BERRY 335 9 BARRING SCALE :

CLIENT REQUEST

11 9

#2


ORD COUNT

NHC HOMELESS ROUTE 202

LAND OF U.S.

KENNETH SONAL ENG SHEET 15 OF 24

NHDOT-3






REVISED PER CLIENT REQUEST TTED FOR NHDOT DRIVEWAY PERMIT

11-10-20 9-9-20


BERRY SURVEYING

& ENGINEERING
335 SECOND CROWN POINT ROAD
BARRINGTON, NH 03825 (603)332–2863
SCALE : 1 IN. EQUALS 20 FT.

DATE : JULY 7, 2020



SHEET 16 OF 24




- SILT FENCE CONSTRUCTION SPECIFICATIONS

 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8" THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A MAXIMUM 6' APART, AND DRIVEN A MINIMUM OF 16" INTO THE
- MINIMOM 48 CIVING, SFACED A MAXIMOM OF APART, AND DINVEYA MINIMOM OF TO THAT CHARL BE GROUND.
 WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY-PASSING. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERTY DISPOSED OF, SEE MAINTENANCE NOTE BELOW, REMOVAL OF SEDIMENT REQUIRED AT A DEPTH OF 6-INCHES.
 PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE FOR SEDIMENT STORAGE.
 SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENDINEER.
 THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED.
 TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, SILT FENCE, PAGE 90.

- SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE IMMEDIATELY.
- IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING
- THE FABRIC ON A SILT PENCE SHOULD DECOMPOSE OF BECOME INCIPELITY DUTING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH SIX-INCHES IN DEPTH. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND

SILT FENCE DETAIL

E5 STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE



- STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, C

- IE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, OR CLED CONCRETE EQUIVALENT.
 LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 75 FEET, EXCEPT THAT THE FUND LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 8-INCH BERM IS INSTALLED AT THE ANCE OF THE PROBLET SITE.
 THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES. WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WE INGRESS OR CERES SOCCURS OR TO FEET, WHICH EVER S GREATER, TO PLACING SUPFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE LE PIPED ENTRANCE SHALL BE MAY BE SUBSTITUTED FOR THE THE CONTROL OF THE STABLE SHALL BE MANTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF ENTRANCE SHALL BE MANTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF MENT ONTO PUBLIC RIGHTS—OF—WAY, THIS MAY REQUIRE PREVENT TRACKING OR FLOWING OF MENT ONTO PUBLIC RIGHTS—OF—WAY, THIS MAY REQUIRE PRODUCT OF DRESSING WITH TO THAT WELL PROBLEMS OF THE STABLE SHALL BE MANTAINED IN A CAN PREVAIL AND FOR THE AND FOR THE AND TH
- TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC—WAY MUST BE REMOVED PROMPTLY.
 NOSTRUCTED IAW NH SWM #3 4—2 SEDIMENT CONTROL PRACTICES, TEMPORARY
 DION EXIT, PAGE 124.


STONE CHECK DAM

THE DISTANCE SUCH THAT POINTS A AND B ARE OF EQUAL ELEVATION. SPACING BETWEEN STRUCTURES

- CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH.
- DIRECTED TO THE SWALE OR DRAINAGE DITCH.
 THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE DAM
 SHOULD BE LESS THEN ONE AGRE.
 THE MAXIMUM HEIGHT OF THE DAM SHOULD BE TWO FEET.
- THE CENTER OF THE DAM SHOULD BE AT LEAST SIX INCHES LOWER THAN THE OUTER EDGES.

 THE MAXIMUM SPACING IS AS SHOWN ON THE PROJECT SITE.

PLANS.
CHECK DAMS WILL NOT BE USED IN A FLOWING STREAM.
CHECK DAMS WILL BE REMOVED ONCE THE
SWALE OR DITCH IS DETERMINED STABLE.
TO BE CONSTRUCTED IAM NH SWM #3 4-2 SEDIMENT
CONTROL PRACTICES, TEMPORARY CHECK DAMS, PAGE 114.




E6

XISTING GRADE

E9

CONSTRUCT AT

ANGLE OF REPOSE



$E2^{{\scriptscriptstyle{\mathrm{CATCH}}}\,{\scriptscriptstyle{\mathrm{BASIN}}}\,{\scriptscriptstyle{\mathrm{OR}}}}$ STONE TO ALLOW-DAYLIGHT DRAINAGE 2.0" (A) (A) (A) (A) -RIP RAP APRON UT 3.0' TABLE 7-24-RECOMMENDED RIP RAP GRADATION RANGES STABLE OUTLET d50 SIZE= 0.5 FEET 6 SIZE OF STONE (INCHES) 85%

- 1. CONSTRUCT THE LEVEL SPREADER LIP ON A 0% GRADE TO INSURE UNIFORM SPREADING OF RUNOFF
- 2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON FILL.
- 3. THE ENTIRE LEVEL LIP AREA SHALL BE PROTECTED BY PLACING EXCELSIOR ENFORCER MATTING BENEATH THE STONE. EACH STRIP SHALL OVERLAP BY AT LEAST SIX INCHES. 4, THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- 5. MAINTENANCE: THE LEVEL SPREADER SHOULD BE CHECKED PERIODICALLY AND AFTER EVERY MAJOR STORM TO DETERMINE IF THE LIP HAS BEEN DAMAGED AND THE DESIGN CONDITIONS HOT CHANGED. ANY DETRIMENTAL SEDIMENT ACCUMULATION SHOULD BE REMOVED. IF STONE REMOVAL HAS TAKEN PLACE ON THE LIP, THEN THE DAMAGE SHOULD BE REPAIRED.
- 6 REFERENCE IS MADE TO NHDES SWM VOL. 2, 4-6, STONE BERM LEVEL SPREADERS, PAGE 162

STONE BERM LEVEL SPREADER NOT TO SCALE

EROSION CONTROL MIX

1'-0" MIN.

EROSION CONTROL MIX BERM

NOT TO SCALE

2'-0" MIN.

SION CONTROL MIX BERMS SHALL BE USED ONLY AS FOLLOWS: BERMS SHALL BE USED IN AREAS WHERE EROSION WILL OCCUR ONLY IN THE FORM OF SHEET EROSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY

BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSLY AS

THE BERMS SHALL BE INSTALLED ON SLOPES LESS THAN 5%.

THE BERMS SHALL BE INSTALLED ON SLOPES LESS THAN 5%.

SUBJECT TO (E), BELOW, THE MIX SHALL HAVE AN ORGANIC PORTION BETWEEN 80 AND 100%, DRY WEIGHT BASIS, AND BE FIBROUS AND ELONGATED SUCH AS FROM SHREDDED BARK, STUMP GRINDINGS, COMPOSED BARK, OR EQUIVALENT MANUFACTURED PRODUCTS. WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS SHALL NOT BE USED AS ORGANIC MATERIAL.

THE MIX SHALL NOT CONTAIN SILTS, CLAY, OR THE SANDS. THE MIX SHALL HAVE A PRATICLE SIZE BY WEIGHT OF 70 TO 85% PASSING A 6-INCH SCREEN. THE MIX SHALL HAVE A PRETICLE SIZE BY WEIGHT OF 70. TO REFEN. THE MIX SHALL BE AT LEAST 12 INCHES HIGH AND AT LEAST 2 FEET WIDE. TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, EROSION CONTROL MIX BERMS, PAGE 106.

E3

GRASS CONVEYANCE SWALE NOT TO SCALE

MOW GRASS ANNUALLY TO A DEPTH OF 4".

INSTALL STABILIZATION MATTING DURING CONSTRUCATION

MAINTENANCE

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY KAIN STORM AND REPAIRS MADE AS NECESSARY. SEDIMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDIMENT HAS REACHED A MAXIMUM OF ONE HALF THE DEPTH OF THE TRAP. THE SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURE OF VEGETATIVE MEANS. THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE CONTRIBUTING DRAINAGE AREA TO THE INLET HAS BEEN COMPLETELY

BLOCK & GRAVEL DROP

INLET SEDIMENT FILTER

NOT TO SCALE

TO BE CONSTRUCTED IAW NH SWM #2 CHAPTER 4, #5 TREATMENT SWALES, PAGE 123.

E4CONSTRUCTION SAFETY FENCE NOT TO SCALE

LEGEND

-48" HIGH DENSITY ORANGE POLYETHELENE SAFETY FER WRE OR ZIP TIES TO SEC 48" Safety Fence, 72" T-Posts

ALL TREES IN THE CONSTRUCTION AREA NOT SPECIFICALLY DISJUNCTION FOR DESCRIPCION OF PROTECTION WITH HOW VISIOUTLY FREEZE AS PER PLAN. WHEN PRACTICABLE, INSTALL HIGH VISSIBILITY 3 FEET DUTISISE OF THE DRIP LINE OF THE TREE. SAFETY FROME SOULD BE FASTIOND SECURIELY TO THE T-POSTS.

THE FENCING MUST REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION; ANY CHANGE OF THE

E8

- THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME.
- . EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER.
- ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS, DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN ONE POUND OF SEED PER 50 SQUARE YARDS OF AREA. (SEE SEED SPECIFICATIONS THIS SHEET;
- ALL DISTURBED AREAS WILL BE RESTABILIZED WITHIN 45 DAYS. AT ANY ONE TIME, NO MORE THAN 5 ACRES, (217,800~Sq.~Ft.) WILL BE DISTURBED.
- SILT FENCES AND PERIMETER BARRIERS SHALL BE INSPECTED PERIODICALLY AND AFTER EVERY RAIN DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF.
- AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VEGETATED.
- DITCHES, SWALES, AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- O. ROADWAYS, PARKING AND CUT AND FILL SLOPES MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINAL GRADE.
- 11. STABILIZATION MEANS:

- 13. THE NHDES STORMWATER MANUAL, IN THREE VOLUMES, DATED DECEMBER 2008, IS A PART OF THIS PLAN SET AND THE MORE RESTRICTIVE WILL GOVERN. (NH SWM)

TEMPORARY EROSION CONTROL MEASURES

- . PER THE EPA CGP REQUIREMENTS THERE WILL BE REPORTS OF THE EROSION CONTROL INSPECTIONS LAW SWPPP PREPARED BY BS&E. ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.25" OR GREATER RAIN EVENT.
- D. DO NOT TRAFFIC EXPOSED SOIL SURFACES WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION SYSTEM.

- 11.1. A MINIMUM OF 85% OF VEGETATIVE COVER HAS BEEN ESTABLISHED.
 11.2. A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED, OR 11.3. EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.
- 12. THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

TO BE USED IN ALL AREAS WHERE THERE WILL BE NO TRAFFIC.

LIFTING STRAPS GRATE

-IF THERE HAVE BEEN NO MAJOR EVENTS, SILTSACK SHOULD BE INSPECTED EVERY 2-3 WEEKS.

ARE SUBJECT TO DAMAGE BY SNOW PLOWS. AND

TO BE CONSTRUCTED IAW NH SWM #3 4-2

E - 101

IG-ERING NT ROAD N3)332-28 8 335 RRIN OF NEW HAND

SEE

#2

COUNTY REET

CON FOR S WASHIN N.H.

ER(OF J.S.

KENNETH a single SONAL ENG

SHEET 17 OF 24

2"X2"X36" WOODEN STAKES PLACED 10' O.C. (SEE SECTION) E10 × FILTREXX SOXX (12" TYPICAL) AREA TO BE PROTECTED WATER FLOW \underline{PLAN} not to scale

ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
FILTER MEDIA FILL TO MEET APPLICATION REQUIRMENTS.
COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.
SILTSOXX MAY BE USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT

BARRIES SITSONX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS NECESSARY TO MEET THE REQUIRMENTS OF THE SPECIFIC APPLICATION. ILLIEXX SOXX IS A REGISTERED TRADEAMARK OF FILEXXIN TERMATIONAL, LLC. SILT FENCE IS NOT A SUBSTITUTION FOR SILT SOXX AND ANY EQUAL SUBSTITUTION TO BE APPROVED. TO SUBSTITUTION FOR SILT SOXX AND ANY EQUAL TO BE CONSTRUCTED LAW FILTEXX, SECTION 1:EROSION & SEDIMENT CONTROL (PAGE 323) — CONSTRUCTION ACTIVITIES, SWPPP CUT SHEET: FILTREXX SEDIMENT CONTROL

CONTROL2"X2"X36" WOODEN STAKES PLACED 10' O.C. HARDWOOD FILTREXX SOXX SILT FENCE-BLOWN/PLACED FILTER MEDIA-What have have been to min. AREA TO BE PROTECTED WORK AREA

Filtrexx International, LLC 35481 Grafton Eastern Rd | Grafton, Oh 44044 440–926–2607 | fox: 440–926–4021 WWW.FILTREXX.COM OR APPROVED EQUAL

E7

BLOCK AND GRAVEL DROP

GRAVEL FILTER

O BE CONSTRUCTED LAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.

THE CONTRIL


FILTREXX SEDIMENT

- CONCRETE BLOCK

NOTE: FOR AREAS REQUIRING DOUBLE PERIMETER

 $\underline{SECTION}$ NOT TO SCALE

E11



RECOMMENDED MAINTENANCE SCHEDULE
-EACH SILTSACK SHOULD BE INSPECTED AFTER EVERY
MAJOR RAIN EVENT, AND MUST BE MAINTAINED.


-THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF CORD IS COVERED WITH SEDIMENT, THE SILTSACK SHOULD BE EMPTIED.

-TO BE USED IN ALL AREAS WHERE THERE WILL BE

MUST BE INSPECTED AFTER ANY SNOW EVENT AND REPLACED AS REQUIRED.

SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.

SILTSACK DETAIL NOT TO SCALE



PIPE OUTLET PROTECTION CONSTRUCTION SPECIFICATIONS PIPE OUTLET PROTECTION

THE SUB GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS. SPECIFIED GRADATION

2. THE ROCK OR GRAVEL USED FOR FILTER OF RIP RAP SHALL CONFORM TO NHDOT

3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.

4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

5. TO BE CONSTRUCTED IAW NH SWM #2 4-6 CONVEYANCE PRACTICES, 6. OUTLET PROTECTION, PAGE 172.

E14

d50 SIZE=	0.5	FEET	6	INCHES
% OF WEIGHT S THAN THE GIVE		SIZE FROM	OF STON	IE (INCHES)
100%		9		12
85%		8		11
50%		6		9
15%		2		3

CONSTRUCTION SEQUENCE:

1.) CUT AND REMOVE TREES IN CONSTRUCTION AREA ONLY AS REQUIRED, RELOCATE ANY PROJECT T.B.M.

2.) CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SEDIMENT EROSION AND DETENTION CONTROL FACILITIES AS SPECIFIED, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SOIL LAND DISTURBANCE AND MUST BE REVIEWED AND APPROVED BY THE COMMUNITY SERVICES DEPARTMENT.

EROSION, SEDIMENT AND DETENTION CONTROL FACILITY SHALL BE INSTALLED & STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.TEMPORARY DIVERSIONS MAY BE REQUIRED, POST CONSTRUCTION STORM WATER MANAGEMENT PRACTICES MUST BE INITIATED AND STABILIZED EARLY IN THE PROCESS, RUNOFF MUST BE DIRECTED TO TEMPORARY PRACTICES UNITS TORWARTE MAYS ARE STABILIZED.

- 4.) CLEAR, CUT AND DISPOSE OF DEBRIS IN APPROVED FACILITY
- 5.) CONSTRUCT TEMPORARY CULVERTS AS REQUIRED, OR DIRECTED
- 6.) CONSTRUCT ROADWAYS FOR ACCESS TO DESIRED CONSTRUCTION AREAS. ALL ROADS SHALL BE STABILIZED IMMEDIATELY. SEE BEST MANAGEMENT PRACTICES FOR BLASTING ON SHEET C-102.
- 7.) START BUILDING CONSTRUCTION.
- 8.) INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. INSTALL RAIN GARDENS. ALL DISTURBED AREAS SHALL STABILIZED IMMEDIATELY AFTER GRADING.
- BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SEEDED OR MULCHED AS RECOURED, OR DIRECTED. NO AREA IS ALLOWED TO BE DISTURBED FOR A LENGTH OF TIME THAT EXCEDS 45 DAYS BEFORE BEING STABILIZED, DAILY, OR AS RECUIRED. ALL ROADWAYS AND PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADES. LIMIT THE LENGTH OF EXPOSURE OF UNSTABILIZED SOIL TO 45 DAYS OR LESS.
- 1D.) CONSTRUCT TEMPORARY BERMS, DRAINS DITCHES, SILT FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED
- 11.) INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION. ALL SWPPP INSPECTIONS MUST BE CONDUCTED BY A QUALIFIED PROFESSIONAL SUCH AS A PROFESSIONAL ENGINEER (PE), A CERTIFED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (OPESC), A CERTIFED EROSION SEDIMENT AND STORM WATER INSPECTION (CESSIN), OR A CERTIFED PROFESSIONAL IN STORM WATER QUALITY (CPSWO), INSPECTION REPORTS SHALL BE SUBMITTED TO THE COMMUNITY SERVICES DEPARTMENT. EROSION AND SEDIMENT CONTROL PRACTICES ARE TO BE INSPECTION WERLY AND ATTER 0.5" OR FAINFALL.
- 12.) COMPLETE PERMANENT SEEDING AND LANDSCAPING.
- 13.) REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE COMPLETE 14.) SMOOTH AND REVEGETATE ALL DISTURBED AREAS.
- 15.) FINISH PAVING ALL ROADWAYS.
- 16.) LOT DISTURBANCE, OTHER THAN THAT SHOWN ON THE APPROVED PLANS, SHALL NOT COMMENCE UNTIL AFTER THE ROADWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE.

POUNDS PER 1,000 S.F.

B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE.

METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING, WHERE BROADCASTING IS

USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.

C. REFER TO TABLE(CH-ET THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-ET THIS

SHEET) FOR RATES OF SEEDING, ALL LEGUMES (CROWNVETCH, BIRDSFOOT TREFOIL, AND

FLATFEA) MUST BE INCOLLIATED WITH THEIR SPECIFIC INDCULLANT.

D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY

COTOBER WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM

EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.

INSTALL ROLLED EROSION CONTROL BLANKET WITH ANCHOR HOOKS AS PER MANUFACTURES

REQUIREMENTS. SUBMIT SHOP DRAWINGS FOR

SLOPE STABILIZATION DETAIL

NOT TO SCALE

ANCHOR HOOK PER

MANUFACTURER'S REQUIREMENTS

4" TOPSOIL (MIN.) AND SEED TO ESTABLISH

NOTE : GEOTEXTILE FABRIC

POORLY DRAINED

EXCELLENT EXCELLENT FAIR
EXCELLENT EXCELLENT FAIR

FAIR EXCELLENT EXCELLENT 2/ FAIR EXCELLENT EXCELLENT 2/

SECTION A-A

PIPE OUTLET TO WELL-DEFINED CHANNEL

NOTE: THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS

SEEDING RATES

POUNDS PER PER ACRE 1,000 Sq. Ft.

30 0.75 40 DR 55 0.95 OR 1.35

0.45 0.45 0.05

0.35 0.25 0.35

0.45 0.75 1.20

1.15 1.15 2.30

3.60

20 20 2

15 10 15

30 50

THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGE 3800 RELATIVE TO INVASIVE SPECIES.

A. TALL FESCUE
CREEPING RED FESCUE
RED TOP
TOTAL

TALL FESCUE
CREEPING RED FESCUE
CROWN VETCH
OR
FLAT PEA
TOTAL

TALL FESCUE CREEPING RED FESCUE BIRDS FOOT TREFOIL

CREEPING RED FESCUE 1/ 50
KENTUCKY BLUEGRASS 1/ 50
TOTAL

FLAT PEA TOTAL

F. TALL FESCUE 1

CONSERVATION MIX

TALL FESCUE (35%)

CREEPING RED FESCUE (25%) 15 ANNUAL RYEGRASS (12%) 5 PERENNIAL RYEGRASS (10%) 5

KENTUCKY BLUEGRASS (10%) 15 WHITE CLOVER (3%)

-La-

т 1888

SECTION A-A

SEEDING GUIDE

SEEDING WELL DROUGHTY DRAINED

A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER

SEEDING.

B. MULCH MILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90LBS PER

E 18 DEFINITION OF STABLE:

PER ENV-WQ 1500 ALTERATION OF TERRAIN

BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED. A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED.. A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP-RAP HAS BEEN INSTALLED. OR, EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

ADDITION STABILIZATION NOTES:

HAY MULCH OR OTHER APPROVED METHODS SHALL BE USED TO CONTROL EROSION OF NEWLY GRADED AREAS. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS AFTER THEIR CONSTRUCTION. DISTURBED SOIL AREAS SHALL BE EITHER TEMPORARILY OR PERMANENTLY STABILIZED. IN AREAS WHERE FINAL GRADING HAS NOT OCCURRED, TEMPORARY STABILIZATION MEASURES SHOULD BE IN PLACE WITHIN SEVEN (7) CALENDAR DAYS FOR EXPOSED SOIL AREAS THAT ARE WITHIN ONE HUNDRED (100) FEET OF A SURFACE WATER BODY OR A WELLAND AND NO MORE THAN 14 CALENDAR DAYS FOR ALL OTHER AREAS. PERMANENT STABILIZATION SHOULD BE IN PLACE WITHIN THREE (3) CALENDAR DAYS FOLLOWING COMPLETION OF FINAL GRADING OF EXPOSED SOIL AREAS.

WINTER STABILIZATION NOTES

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR TO OCTOBER 15TH SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES OR DETENTION BASINS, SHALL BE LINED WITH BIODEGRADABLE/PHOTODEGRADABLE "JUTE MATTING" (EXCELSIOR'S CURLEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL AREAS MILL BE STABILIZED, AS DIRECTED ABOVE.

2. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS MILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPRAP WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED.

PRIOR TO OCT. 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN 5. PHIOR TO OCI. 15 HA ALL KOADWAY AND PARKING AREAS SHALL BE BROUGHI UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS ELEVATIONS ARE PROPOSED TO REWAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE ROUGHLY CROWNED AND A 3" LAYER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND MILL REDUCE ROADWAY FROSION. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 3D4.3, BUT SHALL HAVE BETWEEN 15-25% PASSING THE \$200 SIEVE AND THE LARGEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT MILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH, ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT MILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT FENCING.

OF NEW HAMO KENNETH ALL THE STATE OF T SONAL ENG SHEET 18 OF 24

E - 102

AP AP SON HI 35 ZIN BE BAR SCAI DAT

REQUE VEWA)

200

#2

ETAILS ORD COUI

TROL DE STRAFFC

EDIMENT CONTR CENTER FOR ST 2 / 202 WASHIN OCHESTER, N.H. MAP 246, LOT

JSION & HOMELESS ROUTE 202 RC

PF S.

OCHE MAP

E17

A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE

WEED GROWTH.


FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZATION NEEDS AND SETTING THE STAND BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.


CIN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION, TO BE CONSTRUCTED IAW NH SWM

\$\frac{\pmathrm{\pmathrm{B}}}{3} 4—1 EROSION CONTROL PRACTICES, PERMANENT VEGETATION, PAGE 50.

SEE RAIN GARDEN AND INFILTRATION DETAIL SHEETS FOR SPECIFIC PLANTING INSTRUCTIONS AND SFEDING.

E22







NOT TO SCALE

U-101

SHEET 20 OF 24





NOT TO SCALE

REVISED PER CLIENT REQUEST TTED FOR NHDOT DRIVEWAY PERMIT


##

UTILITY CONSTRUCTION DETAILS
HOMELESS CENTER FOR STRAFFORD COUNTY
ROUTE 202 / 202 WASHINGTON STREET
ROCHESTER, N.H.
TAX MAP 246, LOT 22

LAND OF U.S.



U-102



NOTES:

1. SCARIFY ROOT MASS OF CONTAINERIZED PLANT MATERIAL.

2. INSTALL CONTAINERIZED PLANTS AT FINSHED GRADE

3. TAMP PLANTING MIX FIRMLY AS PIT IS FILLED AROUND EACH PLANT BALL

4. OMIT COLLAR AROUND EACH SHRUB WHEN IRRIGATION SYSTEM IS PRESENT.

5. SOAK EACH PLANT BALL AND PIT IMMEDIATELY AFTER INSTALLATION.

CROWN HEIGHT IN INCHES EDUALS MEDIAN WOM HE TETT TO 12' MAX.

CROWN HEIGHT IN INCHES EDUALS MEDIAN WOM HE TETT TO 12' MAX.

FINAL GRADE

FINAL G

SHRUB & HEDGE PLANTING

L6

TYPICAL BED CROWNING

NOTES:

1.) CALL DIG SAFE PRIOR TO BEGINNING WORK. (1-888-344-7233). THE LANDSCAPE CONTRACTOR IS ADVISED OF THE PRESENCE OF UNDERGROUND UTILITIES AND SHALL VERIFY THE EXISTENCE AND LOCATION OF THE SAME BEFORE COMMENCING AND DIGGING OPERATIONS. THE LANDSCAPE CONTRACTOR SHALL REPLACE OR REPAIR UTILITIES, PAVING, WALKS, CURBING, ETC DAMAGED IN PERFORMANCE OF THIS JOB AT NO ADDITIONAL COST TO THE OWNER OR GENERAL CONTRACTOR.

TYPICAL PLANTING BED PLAN

- 2.) CONTRACTOR SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH ALL SITE CONDITIONS PRIOR TO CONSTRUCTION BIDDING.
- 3.) PROVIDED SMOOTH TRANSITION WHERE NEW WORK MEETS EXISTING CONDITIONS.
- 4.) ALL PLANT MATERIAL INSTALLED SHALL MEET THE SPECIFICATIONS OF "AMERICAN STANDARD FOR NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
- 5.) ALL PLANT MATERIALS SHALL BE FREE FROM INSECTS AND DISEASE
- 6.) ALL PLANTINGS SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING STAKING OR GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNITL. ACCEPTANCE FROM OWNER.
- 7.) ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING.
- 8.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF EXISTING AND NEWLY PLANTED TREES AND SHRUBS DURING THE CONSTRUCTION PROCESS. WHERE REQUIRED, THE CONTRACTOR SHALL INSTALL TEMPORARY FENCING (SNOW OR EQUAL) AROUND EXISTING TREES AND SHRUBS THAT COULD BE IMPACTED BY THE CONSTRUCTION PROCESS. STORAGE OF CONSTRUCTION EQUIPMENT, CONSTRUCTION MATERIALS, SNOW STORAGE AND OR VEHICLE PARKING SHALL NOT BE PERMITTED WITHIN THE DRIP LINE OF TREES OR TWENTY FEET WHICH EVER IS GREATER.
- 9.) NEW PLANTINGS SHALL BE INSTALLED PER PROJECT DRAWINGS AND SPECIFICATION THAT INCLUDE FERTILIZATION AND MULCHING AS REQUIRED.
- D.) ALL SHRUB BEDS AND TREE PITS SHALL BE MULCHED WITH 3" CLEAN SHREDDED BLACK MULCH.
- 11.) WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR GROUND COVER AND PERENNIAL BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL, TWO PARTS SPHAGNUM PEAT MOSS, AND ONE PART HORTICULTURAL PERLITE BY VOLUME. PEAT MOSS MAY BE SUBSTITUTED WITH WELL-ROTTED OR DEVIPORATED MANURE OR COMPOST. ROTOTILL BEDS TO A DEPTH OF 8 INCHES.
- 12.) MAINTENANCE OF NEW PLANTINGS AND LAWNS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR AND OR LANDSCAPE SUBCONTRACTOR UNTIL ACCEPTANCE BY THE OWNER. RESPONSIBILITIES SHALL INCLUDE WATERING WEEDING AND MOWING AS NECESSARY. ALL PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE, REPLACEMENT MATERIAL SHALL BE GUARANTEED FOR AND ADDITIONAL YEAR FROM TIME OF INSTALLATION.
- 13.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY EROSION CONTROL MEASURES DURING THE CONSTRUCTION PHASE AND UNTIL ALL AREAS HAVE BEEN STABILIZED AND ACCEPTED BY THE OWNER. THE GENERAL CONTRACTOR SHALL PROVIDE WEEKLY INSPECTIONS OF EROSION MEASURE AND IMMEDIATELY AFTER STORM EVENTS AND REPAIR AS NECESSARY.
- 14.) THE GENERAL CONTRACTOR AND OR THE LANDSCAPE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL THREE GUYING MATERIAL ONCE PLANT MATERIAL HAS BEEN ESTABLISHED. (MINIMUM OF ONE GROWING SEASON). ALL TEMPORARY EROSION CONTROL MEASURE SHALL BE REMOVED ONCE STABILIZATION OF DISTURBANCE HAS BEEN ACCEPTED BY OWNER.
- 15.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM OF TWO MOWINGS FOR ALL TURF AREAS OR UNTIL ACCEPTANCE BY THE OWNER. A MINIMUM UNIFORM 75% CATCH OF TURF IS REQUIRED FOR ACCEPTANCE.
- 16.) ALL PLANTINGS SHALL BE WATERED REGULARLY DURING THEIR FIRST YEAR AND MAINTAINED PERMANENTLY IN GOOD GROWING CONDITION AS AN EFFECTIVE VISUAL SCREEN.
- 17.) SHRUBS OR TREES WHICH DIE SHALL BE REPLACED WITHIN ONE GROWING SEASON WITH NEW SHRUBS OR TREES TO ENSURE CONTINUED COMPLIANCE WITH APPLICABLE LANDSCAPING REQUIREMENTS.
- 18.) ALL REQUIRED LANDSCAPING SHALL BE INSTALLED BEFORE OCCUPANCY, OR WITHIN SIX MONTHS IF OCCUPANCY OCCURS DURING WINTER CONDITIONS.
- 19.) TREES ARE TO BE 3" CALIPER 6" OFF THE ROOT BALL
- 20.) ALL PLANT STOCK SHALL CONFORM TO ANSI Z260.1 NURSERY STOCK, LATEST EDITIONS (AMERICAN ASSOCIATION OF NURSERYMEN, INC.)
- 21.) 4" AGED PINEBARK MULCH AND A WEED BARRIER (TY-PAR FABRIC OR APPROVED EQUAL) SHALL BE APPLIED TO ALL SHRUB AND GROUND COVER BEDS. INSTALL WEED BARRIER AS PER MANUFACTURERS RECOMMENDATIONS.
- 22.) PLANT-PIT BACK-FILL SHALL BE MIXED AT A RATE OF 7 PARTS OF TOPSOIL TO 2 PARTS OF DEHYDRATED COW MANURE. SLOW RELEASE FERTILIZER SHALL BE APPLIED AS PER MANUFACTURERS RECOMMENDATIONS. USE EXISTING ON-SITE TOPSOIL AS PART OF BACK FILL WHEN AVAILABLE.
- 23.) ALL LANDSCAPED AREAS NOT PLANTED WITH TREES, SHRUBS OR GROUNDCOVER SHALL BE RESTORED WITH SEED OR SOD AS INDICATED ON PLANS.

#2 11-10-20 REWSED PER CLIENT REQUEST SUBMITTED FOR NHOOT DRIVEWAY PERMIT DESCRIPTION


LANDSCAPING CONSTRUCTION DETAILS
OF HOMELESS CENTER FOR STRAFFORD COUNTY
S. ROUTE 202 / 202 WASHINGTON STREET
N.S. ROUTE 202 / 202 WASHINGTON STREET


BERRY SURVEYING
335 SECOND CROWN POINT ROAD
BARRINGTON, NH 03825 (603)332-2863
SCALE: AS NOTED
DATE: JULY 7, 2020




L-101

SHEET 22 OF 24







HOMELESS CENTER FOR STRAFFORD COUNTY

9 Isinglass Drive / P.O. Box 7306 Rochester, NH 03839 603.332.3065 Execdirshelter@gmail.com

DESIGN BUILDER:



Careno Construction Company, LLC

Origin Build Construction Managery (General Contractors
270 West Road - Seile 4A
Promocoli, NY 0'0'01
p. 651-86 to fee Left - 348-8620
c. build-searn-construction com

PORT NE ARCHITECTS

959 Islington Street Portsmouth, NH 03801 603.436.8891 Info@portonearchitects.com

BERRY SURVEYING & ENGINEERING

335 Second Crown Point Road Barrington, NH 03825 603.332.2863

DATE ISSUANCE

USE DISCLAIMER:

COPYRIGHT © BY PORTONE ARCHITECTS, INC. 2020 NO RE-USE WITHOUT PERMISSION.

LOCUS MAP:




PROJECT NAME: HOMELESS SHELTER OF STRAFFORD COUNTY 202 WASHINGTON ST. ROCHESTER, NH

FIRST FLOOR PLAN

NOVEMBER, 2020

A1.1



SECOND FLOOR PLAN
SCALE: 1/4" = 1'-0"

HOMELESS CENTER FOR STRAFFORD COUNTY

9 Isinglass Drive / P.O. Box 7306 Rochester, NH 03839 603.332.3065 Execdirshelter@gmail.com



Carein Construction Company, LLC

Regg Build Construction Vasager / General Contractors
200 West Reed - Suit: 4A

Produced, STI (200)

p. 6012-lb (100: Lb) Alaco20

c. build Guerneconstruction com

PORTONE ARCHITECTS

959 Islington Street Portsmouth, NH 03801 603.436.8891 info@portonearchitects.com

BERRY SURVEYING & ENGINEERING

335 Second Crown Point Road Barrington, NH 03825 603.332.2863

REVISION HISTORY:

DATE ISSUANCE

COPYRIGHT © BY PORTONE ARCHITECTS, INC. 2020 NO RE-USE WITHOUT PERMISSION.

LOCUS MAP:



PROJECT NAME:
HOMELESS SHELTER OF STRAFFORD COUNTY
202 WASHINGTON ST.
ROCHESTER, NH

SECOND FLOOR PLAN

NOVEMBER, 2020

A1.2

