



LANDSCAPING NOTES

- THE CONTRACTOR SHAL FOLLOW BEST MANAGEMENT PRACTICES DURING CONSTRUCTION AND SHALL TAKE ALL MEANS NECESSARY TO STABILIZE AND PROTECT THE SITE FROM EROSION.
- 2) EROSION CONTROL SHALL BE IN PLACE PRIOR TO CONSTRUCTION.
- 3) EROSION CONTROL TO CONSIST OF HAY BALES AND EROSION CONTROL FABRIC SHALL BE STAKED IN PLACE BETWEEN THE WORK AND WATER BODIES, WETLANDS AND/OR DRAINAGE WAYS PRIOR TO ANY CONSTRUCTION.
- 4) THE CONTRACTOR SHALL VERIFY LAYOUT AND GRADES AND INFORM THE LANDSCAPE ARCHITECT OR CLIENT'S REPRESENTATIVE OF ANY DISCREPANCIES OR CHANGES IN LAYOUT AND/OR GRADE RELATIONSHIPS PRIOR TO CONSTRUCTION.
- 5) THE CONTRACTOR SHALL VERIFY EXACT LOCATION AND ELEVATION OF ALL UTILITIES WITH RESPECTIVE UTILITY OWNERS PRIOR TO CONSTRUCTION. CALL DIGSAFE AT 1-888-344-7233.
- THE CONTRACTOR SHALL GUARANTEE ALL PLANTS FOR NOT LESS THAN ONE YEARS FROM THE TIME OF ACCEPTANCE.
- 7) ALL LANDSCAPING SHALL BE PROVIDED WITH EITHER OF THE FOLLOWING:
- 7)1) AN UNDERGROUND SPRINKLER SYSTEM
 7)2) AN OUTSIDE HOSE ATTACHMENT WITHIN 150 FEET
- 8) TREES, GROUND COVER, AND SHRUB BEDS SHALL BE MULCHED TO A DEPTH OF 2" WITH ONE-YEAR-OLD, WELL-COMPOSTED, SHREDDED NATIVE BARK NOT LONGER THAN 4" IN LENGTH AND 1/2" IN WIDTH, FREE OF WOODCHIPS AND SAW DUST. MULCH FOR FERNS AND HERBACEOUS PERENNIALS SHALL BE NO LONGER THAN 1" IN LENGTH. TREES IN LAWN AREAS SHALL BE MULCHED IN A 5' DIAMETER MIN. SAUCER.
- 9) ALL DISTURBED AREAS WILL BE DRESSED WITH 4" OF TOPSOIL AND PLANTED AS NOTED ON THE PLANS OR SEEDED EXCEPT PLANT BEDS. PLANT BEDS SHALL BE PREPARED TO A DEPTH OF 12" WITH 75% LOAM AND 25% COMPOST.

PLANT LIST

TREES

SMYBOL BOTANICAL NAME COMMON NAME SIZE ACER SACCHARUM 'BONFIRE' SMALL FLOWERING TREE BONFIRE SUGAR MAPLE

> **LEGEND** PROPERTY LINE SETBACK EXT. ABUTTER LINE PRP. RIGHT-OF-WAY EXT. PAVEMENT PRP. PAVEMENT PRP. BUILDING #2000 as EXT. WETLAND BNDY EXT. WETLAND AREA



DESCRIPTION

TAX MAP 221, LOT


LANDSCAPING PLAN INTEC AUTOMATION 6 INDUSTRIAL WAY, ROCHESTER, NH

DATE

INTEC AUTOMATION INC. PO BOX 1653 ROCHESTER NH, 03867


ATTAR ENGINEERING, INC.


CIVIL ♦ STRUCTURAL ♦ MARINE
1284 STATE ROAD — ELIOT, MAINE 03903
PHONE: (207) 439—6023 FAX: (207) 439—2128 SCALE: APPROVED BY: DRAWN BY: REVISION DATE: 04/06/20 JOB NO: C164-20 FILE: IRM BASE.DWG SHEET: 7 OF 14



EROSION & SEDIMENTATION CONTROL NOTES

- SILTATION FENCE OR HAY BALE BARRIERS WILL BE INSTALLED DOWNSLOPE OF ALL STRIPPING OR CONSTRUCTION OPERATIONS. A DOUBLE SILT FENCE BARRIER SHALL BE INSTALLED DOWNSLOPE OF ANY SOIL MATERIAL STOCKPILES. SILT FENCES SHALL BE INSPECTED AFTER EACH RAIN EVENT AND DOILY DURING PROLONGED RAIN. SILT AND SOIL PARTICLES ACCUMULATING BEHIND THE FENCE SHALL BE REMOVED AFTER EACH SIGNIFICANT RAIN EVENT AND IN NO INSTANCE SHOULD ACCUMULATION EXCEED 1/2 THE HEIGHT OF THE FENCE. TORN OR DAMAGED AREAS SHALL BE REPAIRED.
- TEMPORARY AND PERMANENT VEGETATION AND MULCHING IS AN INTEGRAL COMPONENT OF THE FROSION AND SEDIMENTATION CONTROL PLAN. ALL AREAS SHALL BE INSPECTED AND MAINTAINED UNTIL THE DESIRED VEGETATIVE COVER IS ESTABLISHED. THESE CONTROL MEASURES ARE ESSENTIAL TO EROSION PREVENTION AND ALSO REDUCE COSTLY REWORK
- 3. SEEDING, FERTILIZER AND LIME RATES AND TIME OF APPLICATION WILL BE DEPENDENT ON SOIL REQUIREMENTS. TEMPORARY VEGETATION SHALL BE MAINTAINED IN THESE AREAS UNTIL PERMANENT SEEDING IS APPLIED. ADDITIONALLY, EROSION AND SEIMENTATION MEASURES SHALL BE MAINTAINED UNTIL PERMANENT VEGETATION IS ESTABLISHED.
- ALL LAWN AREA, OUTER POND SIDE SLOPES AND SWALES SHALL BE PERMANENTLY SEEDED WITH THE FOLLOWING MIXTURE: 20 LB/ACRE CREEPING RED FESCUE, 2 LB/ACRE REDTOP AND 20 LB/ACRE TALL FESCUE FOR A TOTAL OF 42 LB/ACRE. FERTILIZER AND LIME RATES SHALL BE DEPENDENT ON SOIL TESTING. IN THE ABSENCE OF SOIL TESTS, FERTILIZE WITH 10-20-20 (N-P205-K201) AT 800 LB/ACRE AND LIME AT 3 TONS/ACRE. MULCH WITH HAY AT 70-90 LB/1000 S.F. 4" OF LOAM SHALL BE APPLIED PRIOR TO
- 5. POND BOTTOMS AND INNER POND SIDESLOPES SHALL BE PERMANENTLY SEEDED WITH THE FOLLOWING MIXTURE: 20 LB/ACRE CREEPING RED FESCUE, 8 LB/ACRE BIRDSFOOT TREFOL AND 20 LB/ACRE TALL FESCUE FOR A TOTAL OF 48 LB/ACRE. SEE THE ABOVE NOTE FOR FERTILIZER, LIME AND MULCHING RATES.
- . TEMPORARY VEGETATION OF ALL DISTURBED AREAS, MATERIAL STOCKPILES AND OTHER SUCH AREAS SHALL BE ESTABLISHED BY SEEDING WITH EITHER WINTER RYE AT A RATE OF 112 LB/ACRE OR ANNUAL RYEGRASS AT A RATE OF 40 LB/ACRE. WINTER RYE SHALL BE USED FOR FALL SEEDING AND ANNUAL RYEGRASS FOR SHORT DURATION SEEDING. SEEDING SHALL BE ACCOMPLISHED BEFORE OCTOBER 1.
- TEMPORARY SEEDING OF DISTURBED AREAS SHALL BE ACCOMPLISHED BEFORE OCTOBER 1 PERMANENT SEEDING SHALL BE ACCOMPLISHED BEFORE SEPTEMBER 15.
- ALL SEEDED AREAS SHALL BE MULCHED WITH HAY AT A RATE OF 2 BALES (70-90 LB) PER 1000 S.F. OF SEEDED AREA.
- 9. SLOPES 2:1 OR STEEPER SHALL BE TREATED WITH POLYJUTE OPEN WEAVE GEOTEXTILE (OR EQUIVALENT) AFTER SEEDING. JUTE MATS SHALL BE ANCHORED PER MANUFACTURER'S SPECIFICATIONS.
- EXCESSIVE DUST CAUSED BY CONSTRUCTION OPERATIONS SHALL BE CONTROLLED BY APPLICATION OF WATER OR CALCIUM CHLORIDE.
- 11 THE CONTRACTOR MAY OPT TO USE FROSION CONTROL MIX BERM AS A SEDIMENT BARRIER IN LIEU OF SILTATION FENCE OR HAY BALE BARRIERS WITH APPROVAL FROM THE INSPECTING ENGINEER.
- 12. MINIMIZE DISTURBED AREAS AND PROTECT NATURAL DOWNGRADIENT BUFFER AREAS TO THE EXTENT PRACTICABLE. CONTROL STORMWATER VOLUME AND VELOCITY WITHIN THE SITE TO MINIMIZE SOIL EROSION. MINIMIZE THE DISTURBANCE OF STEEP SLOPES. CONTROL STORWWATER DISCHARGES, INCLUDING BOTH PEAK FLOW RATES AND VOLUME, TO MINIMIZE EROSION AT OUTLETS. THE DISCHARGE MAY NOT RESULT IN EROSION OF ANY OPEN DRAINAGE CHANNELS, SWALES, SITEAM CHANNELS OR STREAM BANKS, UPLAND, OR COASTAL OR FRESHWATER WETLANDS OFF THE PROJECT SITE.
- 13. THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.
- 14. PERIMETER CONTROLS SHALL BE INSTALLED PRIOR TO EARTH MOVING OPERATIONS.
- 15. TEMPORARY WATER DIVERSION MUST BE USED AS NECESSARY UNTIL AREAS ARE STABILIZED. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS NEEDED TO BE PAVED; A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED; A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL (SUCH AS STONE OR RIPRAP) HAS BEEN INSTALLED; EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.





EROSION CONTROL MIX COMPOSITION STANDARDS - THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80 AND 100%, DRY WEIGHT BASIS. - THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED - LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX - SOLUBLE SALTS CONTENT SHALL BE <4.0 mmhos/cm THE pH SHOULD FALL BETWEEN 5.0 AND 8.0

FROSION CONTROL MIX BERM (NTS)

EROSION & SED CONTROL NOTES (CONT.)

- 16. PRIOR TO CONSTRUCTION, PROPERLY INSTALL SEDIMENT BARRIERS AT THE DOWNGRADIENT . PRIOR TO CONSTRUCTION, PROPERLY INSTALL SEDIMENT BARRIERS AT THE DOWNGRADIENT EDGE OF ANY AREA TO BE DISTURBED AND ADJACENT TO ANY DRAINAGE CHANNELS WITHIN THE DISTURBED AREA. SEDIMENT BARRIERS SHOULD BE INSTALLED DOWNGRADIENT OF SOIL OR SEDIMENT STOCKPILES AND STORMWATER PREVENTED FROM RUNNING ONTO THE STOCKPILE. MAINTAIN THE SEDIMENT BARRIERS BY REMOVING ACCUMULATED SEDIMENT, OR REMOVING AND REPLACING THE BARRIER, UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. WHERE A DISCHARGE TO A STORM DRAIN INLET OCCURS, IF THE STORM DRAIN CARRIES WATER DIRECTLY TO A SURFACE WATER AND YOU HAVE AUTHORITY TO ACCESS THE STORM DRAIN INLET, YOU MUST INSTALL AND MAINTAIN PROTECTION MEASURES THAT REMOVE SEDIMENT FROM THE DISCHARGE.
- 17. WHENEVER PRACTICABLE, NO DISTURBANCE ACTIVITIES SHOULD TAKE PLACE WITHIN 50 FEET OF ANY PROTECTED NATURAL RESOURCE. IF DISTURBANCE ACTIVITIES TAKE PLACE BETWEEN 30 FEET AND 50 FEET OF ANY PROTECTED NATURAL RESOURCE, AND STORMWATER DISCHARGES THROUGH THE DISTURBED AREAS TOWARD THE PROTECTED NATURAL RESOURCE, PERIMETER EROSION CONTROLS MUST BE DOUBLED. IF DISTURBANCE ACTIVITIES TAKE PLACE LESS THAN 30 FEET FROM ANY PROTECTED NATURAL RESOURCE, AND STORMWATER DISCHARGES THROUGH THE DISTURBED AREAS TOWARD THE PROTECTED NATURAL RESOURCE, PERIMETER EROSION CONTROLS MUST BE DOUBLED AND DISTURBED AREAS MUST BE TEMPORARILY OR PERMANENTLY STABILIZED WITHIN 7 DAYS.
- 18. PRIOR TO CONSTRUCTION, PROPERLY INSTALL A STABILIZED CONSTRUCTION ENTRANCE (SGE) AT ALL POINTS OF EGRESS FROM THE SITE. THE SCE IS A STABILIZED PAD OF AGGREGATE, UNDERLAIN BY A GEOTEXTILE FILTER FABRIC, USED TO PREVENT TRAFFIC FROM TRACKING MATERIAL AWAY FROM THE SITE ONTO PUBLIC ROW'S. MAINTAIN THE SCE UNTIL ALL DISTURBED AREAS ARE STABILIZED.
- 19. WITHIN 7 DAYS OF THE CESSATION OF CONSTRUCTION ACTIVITIES IN AN AREA THAT WILL NOT BE WORKED FOR MORE THAN 7 DAYS, STABILIZE ANY EXPOSED SOIL WITH MULCH, OR OTHER NON-EROBIBLE COVER. STABILIZE AREAS WITHIN 75 FEET OF A WETLAND OR WATERBODY WITHIN 48 HOURS OF THE INITIAL DISTURBANCE OF THE SOIL OR PRIOR TO ANY STORM EVENT, WHICHEVER COMES FIRST.
- 20. REMOVE ANY TEMPORARY CONTROL MEASURES, SUCH AS SILTATION FENCE, WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED. REMOVE ANY ACCUMULATED
- 21. IF THE AREA WILL NOT BE WORKED FOR MORE THAN ONE YEAR OR HAS BEEN BROUGHT TO FINAL GRADE, THEN PERMANENTLY STABILIZE THE AREA WITHIN 7 DAYS BY PLANTING VECETATION, SEEDING, SOD, OR THROUGH THE USE OF PERMANENT MULCH, OR RIPRAP, OR ROAD SUB—BASE. IF USING VECETATION FOR STABILIZATION, SELECT THE PROPER VEGETATION FOR THE LIGHT, MOISTURE, AND SOIL CONDITIONS; AMEND AREAS OF DISTURBED SUBSOILS WITH TOPSOIL, COMPOST, OR FERTILIZERS; PROTECT SEEDED AREAS WITH MULCH OR, IF NECESSARY, EROSION CONTROL BLANKETS; AND SCHEDULE SODDING, PLANTING, AND SEEDING SO TO AVOID DIE—OFF FROM SUMMER DROUGHT AND FALL EROSTS. NEWLY SEEDED OR SONDEN APERS MILTS THE PROTECTION OF THE PROPERTY OF THE FROSTS. NEWLY SEEDED OR SODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC FROSTS. NEWLT SELDED ON SODDED AREAS MUST BE PROJECTED FROM VEHICLE IRAPH EXCESSIVE PEDESTRIAN TRAFFIC, AND CONCENTRATED RUNOFF UNITL THE VECETATION IS WELL-ESTABLISHED WITH 90% COVER BY HEALTHY VEGETATION. IF NECESSARY, AREAS MUST BE REWORKED AND RESTABILIZED IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY, OR TOPSOIL EROSION IS EVIDENT. ONE OR MORE OF THE FOLLOWING MAY APPL TO A PARTICULAR SITE.
- 22. FOR SEEDED AREAS, PERMANENT STABILIZATION MEANS A 90% COVER OF THE DISTURBED AREA WITH MATURE, HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.
- 23. FOR SODDED AREAS, PERMANENT STABILIZATION MEANS THE COMPLETE BINDING OF THE SOD ROOTS INTO THE UNDERLYING SOIL WITH NO SLUMPING OF THE SOD OR DIE-OFF.
- 24. FOR MULCHED AREAS, PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL. EROSION CONTROL MIX MAY 8E USED AS MULCH FOR PERMANENT STABILIZATION ACCORDING TO THE APPROVED APPLICATION RATES AND LIVITATIONS.
- 25. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADEQUATE HOUSEKEEPING PRACTICES DURING THE CONSTRUCTION OF THE PROJECT. THESE CAN BE FOUND IN THE FOLLOWING DOCUMENT: MODE CHAPTER SOO (STORWATER MANAGEMENT), APPENDIX C. HOUSEKEEPING, HOUSEKEEPING PRACTICES INCLUDE, BUT ARE NOT LIMITED TO, SPILL PREVENTION, GROUNDWATER PROTECTION, FUGITIVE SEDIMENT AND DUST, DEBRIS AND OTHER MATERIAS, EXCAVATION DEWATERING, AUTHORIZED NON-STORMWATER DISCHARGES AND UNAUTHORIZED NON-STORMWATER DISCHARGES AND UNAUTHORIZED NON-STORMWATER DISCHARGES.
- 26. TEMPORARY WATER DIVERSION MUST BE USED AS NECESSARY UNTIL AREAS ARE STABILIZED. PONDS AND SWALES SHALL BE INSTALLED EARLY ON IN THE CONSTRUCTION SEQUENCE.
- 27. STORMWATER PONDS, INFILTRATION BASINS, DITCHES AND SWALES MUST BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- 28. ROADWAYS AND PARKING LOTS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING
- 29. CUT AND FILL SLOPES SHALL BE SEEDED/ LOAMED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

PLACE AND STAKE BALE, USE TWO STAKES PER BALF

1=11=

EROSION & SED. CONTROL NOTES (CONT.)

- 30. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.
- 31. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE. LIMIT THE LENGTH OF EXPOSURE OF STABILIZED SOIL TO 45 DAYS OR LESS.
- 32. STORMWATER PONDS, INFILTRATION BASINS, AND SWALES MUST BE INSTALLED BEFORE
- 33. RUNOFF MUST BE DIRECTED TO TEMPORARY PRACTICES UNTIL STORMWATER BMPS ARE
- 34. DEFINITION OF STABILIZED: IN AREAS TO BE PAVED, BASE COURSE GRAVELS MEETING THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM 304.2 HAVE BEEN INSTALLED.
- 35. DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION SYSTEM. AFTER THE INFILTRATION SYSTEM AREA IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING DRAG. DO NOT PLACE INFILITATION SYSTEMS INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.

WINTER CONSTRUCTION NOTES

- AN AREA SHALL BE CONSIDERED STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH HAY AT A RATE OF 100 LB/1000 S.F. OR DORMANT SEEDED, MULCHED AND ADEQUATELY ANCHORED BY AN APPROVED ANCHORING TECHNIQUE. IN ALL CASES, MULCH SHALL BE APPLIED SO THAT THE SOIL SURFACE IS NOT VISIBLE THROUGH THE MULCH.
- 2. FROM OCTOBER 15 TO APRIL 1, LOAM AND SEED WILL NOT BE REQUIRED. DURING PERIODS OF TEMPERATURES ABOVE FREEZING, DISTURBED AREAS SHALL BE FINE GRADED AND PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL PERMANENT SEEDING CAN BE APPLIED. AFTER NOVEMBER 1, DISTURBED AREAS MAY BE LOAMED, FINE GRADED AND DORMANT SEEDED AT A RATE 200-300% HIGHER THAN THE SPECIFIED PERMANENT SEEDING RATE. IF CONSTRUCTION CONTINUES DURING FREEZING WEATHER, DISTURBED AREAS SHALL BE GRADED BEFORE FREEZING AND TEMPORARILY STABILIZED WITH MULCH. DISTURBED AREAS SHALL NOT BE LEFT OVER THE WINTER OR FOR ANY OTHER EXTENDED PERIOD OF TIME UNLESS STABILIZED WITH MULCH.
- 3. FROM NOVEMBER 1 TO APRIL 15 ALL MULCH SHALL BE ANCHORED BY EITHER PEG LINE, MULCH NETTING, ASPHALT EMULSION CHEMICAL, TRACK OR WOOD CELLULOSE FIBER. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH SLOPES GREATER THAN 3%, SLOPES GREPOSED TO DIRECT WINDS AND FOR SLOPES GREATER THAN 8%. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL AREAS WITH SLOPES GREATER THAN 15%. AFTER OCTOBER 1, THE SAME APPLIES TO ALL SLOPES GREATER THAN 15%.
- 4. SNOW SHALL BE REMOVED FROM AREAS OF SEEDING AND MULCHING PRIOR TO PLACEMENT.
- FOR WINTER STABILIZATION, HAY MULCH SHALL BE APPLIED AT TWICE THE STANDARD TEMPORARY STABILIZATION RATE. AT THE END OF EACH CONSTRUCTION DAY, AREAS THAT HAVE BEEN BROUGHT TO FINAL GRADE SHALL BE STABILIZED. MULCH SHALL NOT BE SPREAD ON TOP OF SNOW.
- ALL AREAS WITHIN 75 FEET OF A PROTECTED NATURAL RESOURCE SHALL BE PROTECTED WITH A DOUBLE ROW OF SEDIMENT BARRIERS.
- 7. ALL VEGETATED DITCH LINES THAT HAVE NOT BEEN STABILIZED BY NOVEMBER 1, OR WILL BE WORKED DURING THE WINTER CONSTRUCTION PERIOD, SHALL BE STABILIZED WITH AN APPROPRIATE STONE LINING BACKED BY AN APPROPRIATE GRAVEL BED OR GEOTEXTILE UNLESS SPECIFICALLY RELEASED FROM THIS STANDARD BY THE MDEP.
- 8. MULCH NETTING SHALL BE USED TO ANCHOR MULCH ON ALL SLOPES GREATER THAN 8% UNLESS EROSION CONTROL BLANKETS OR EROSION CONTROL MIX IS BEING USED ON SUCH SLOPES.
- 9. AFTER OCTOBER 15. INCOMPLETE ROAD OR PARKING SURFACES (WHERE WORK HAS STOPPED FOR THE WINTER SEASON) SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHOOT ITEM 304.3
- 10. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE CROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND FOR ALL OTHER SLOPES BY SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT
- 11. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN

NHDES ACT PERMIT REVISIONS

DESCRIPTION

NO.


08/07/20


DATE

B. MAINTENANCE, IF BEST MANAGEMENT PRACTICES (BMPS) NEED TO BE REPAIRED, THE REPAIR WORK SHOULD BE INITIATED UPON DISCOVERY OF THE PROBLEM BUT NO LATER THAN THE END OF THE NEXT WORKDAY, IF ADDITIONAL BMPS OR SIGNIFICANT REPAIR OF BMPS ARE NECESSARY, IMPLEMENTATION MUST BE COMPLETED WITHIN 7 CALENDAR DAYS AND PRIOR TO ANY STORM EVENT (RAINFALL). ALL MEASURES MUST BE MAINTAINED IN EFFECTIVE OPERATING CONDITION UNTIL AREAS ARE PERMANENTLY STABILIZED. C. DOCUMENTATION, KEEP A LOG (REPORT) SUMMARIZING THE INSPECTIONS AND ANY CORRECTIVE ACTION TAKEN, THE LOG MUST INCLUDE THE NAME(S) AND QUALIFICATIONS OF THE PERSON MAKING THE INSPECTIONS, THE DATE(S) OF THE INSPECTIONS, AND MAJOR OBSERVATIONS ABOUT THE OPERATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROLS, MATERIALS STORAGE AREAS, AND VEHICLES ACCESS POINTS TO THE PARCEL. MAJOR OBSERVATIONS MUST INCLUDE BMPS THAT NEED MAINTENANCE, BMPS THAT FAILED TO PERROTE AS DESIGNED OF PROVED INADEQUATE FOR A PARTICULAR LOCATION, SO, WHERE ADDITIONAL BMPS ARE NEEDED, FOR EACH BMP REQUIRING MAINTENANCE, BMP NEEDING REPLACEMENT, AND LOCATION (SO, WHERE ADDITIONAL BMPS ARE NEEDED, FOR EACH BMP REQUIRING MAINTENANCE, BMP NEEDING REPLACEMENT, AND LOCATION NEEDING ADDITIONAL BMPS, NOTE IN THE LOG THE CORRECTIVE ACTION TAKEN AND WHEN IT WAS TAKEN. THE LOG BMLST BE MADE ACCESSIBLE TO DEPARTMENT STAFF AND A COPY MUST BE PROVIDED UPON REQUEST. THE PERMITTEE SHALL RETAIN A COPY OF THE LOG FINE OR PERMINENT STABILIZATION.

E&S INSPECTION/MAINTENANCE DURING CONSTRUCTION

A. INSPECTION AND CORRECTIVE ACTION, INSPECT DISTURBED AND IMPERVIOUS AREAS, EROSION CONTROL MEASURES, MATERIALS STORAGE AREAS THAT ARE EXPOSED TO PRECIPITATION, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE. INSPECT THESE AREAS AT LEAST ONCE A WEEK AS WELL AS BEFORE AND WITHIN 24 HOURS AFTER A STORM EVENT (RAINFALL), AND PRIOR TO COMPLETING PERMANENT STABILIZATION MEASURES. A PERSON WITH KNOWLEDGE OF EROSION AND STORMWATER CONTROL, INCLUDING THE STANDARDS AND CONDITIONS IN THE PERMIT, SHALL CONDUCT THE INSPECTIONS.






SITE DETAILS INTEC AUTOMATION 6 INDUSTRIAL WAY, ROCHESTER, NH

INTEC AUTOMATION

PO BOX 1653 ROCHESTER NH, 03867 ATTAR ENGINEERING, INC

FOR:

CIVIL ◆ STRUCTURAL ◆ MARINE 1284 STATE ROAD - ELIOT, MAINE 03903 PHONE: (207)439-6023 FAX: (207)439-2128 SCALE: APPROVED BY: DRAWN BY: NB REVISION DATE: 04/05/20 A: 08/07/20 JOB NO: C164-20 FILE: IRM_DET.DWG SHEET: 9 OF 14



PROFILE

NOTES:

GEOTEXTILE: PLACE FILTER CLOTH OVER ENTIRE AREA TO BE COVERED WITH AGGREGATE. FILTER CLOTH WILL NOT BE REQUIRED ON A SINGLE FAMILY RESIDENTIAL

2. PIPING OF SURFACE WATER UNDER ENTRANCE SHALL BE PROVIDED AS REQUIRED. PIPING IS IMPOSSIBLE, A MOUNTABLE BERM WITH A 5:1 SLOPE WILL BE PERMITTED.

STABILIZED CONSTRUCTION ENTRANCE

3. IN SLOPING AREAS WHERE SURFACE FLOW FOLLOWS THE BALE LINE, INSTALL PERPENDICULAR BALE CHECKS AT APPROPRIATE INTERVALS (100' MAX.) HAY BALE BARRIER

COMPACTED BACKELL

STAKE


WIDTH OF BALE


PLAN VIEW

PACKED STRAW


WEDGE LOOSE STRAW BETWEEN BALES TO CREATE A CONTINUOUS BARRIER.


1. PLACE BALES IN A SINGLE ROW, LENGTHWISE ON THE CONTOUR 2. PLACE BALES 10' AWAY FROM THE TOE OF SLOPE.






LONDONBOULDER FROM GENEST PRECAST OR APPROVED EQUAL — NO SETBACK GRAVITY WALL (NTS)







	S	STONE GRADATION REQUIREMENTS			
	SIEVE (METRIC)		SIEVE (US CUSTO	MARY)	% PASSING (BY WEIGHT)
	300 MM 150 MM 75 MM 25.4 MM		12 IN 6 IN 3 IN 1 IN		100 84-100 68-83 42-55

8-12

No. 4

4.75 MM


STONE TO MEET GRADATION
REQUIREMENTS GIVEN IN TABLE
AT LEFT.
STONE BERM BUILT ALONG
CONTOUR UPSTREAM OF BUFFER

18" FLOW

BUFFER

3'

LEVEL SPREADER - TYPE C (STONE BERM)



SITE DETAILS
INTEC AUTOMATION
6 INDUSTRIAL WAY, ROCHESTER, NH
DR: INTEC AUTOMATION
PO BOX 1653
ROCHESTER NH, 03867

ATTAR ENGINEERING, INC.


CIVIL + STRUCTURAL + MARINE


1284 STATE ROAD - ELIOT, MAINE 03903

PHONE: (207)439-5023 FAX: (207)439-2128

SCALE: DRAWN

SCALE:	APPROVED BY:	DRAWN BY:
1" = 50'		NB
DATE:		REVISION DATE:
04/06/20		-:-
IOB NO: C164-20	FILE: IRM DET,DWG	SHEET: 10 OF 1





-STEPS 12" O.C. SAFETY GRATE HINGE (TYP) SAFETY GRATE (TYP) 3" DI DISCHARGE 8" PVC INLET-3" DL DISCHARGE FLOAT RACK W/FLOAT SWITCH HYDRORANGER PUMP STATION PLAN

4" MUSHROOM VENT 36" X 48" H-10 ALUMINUM ACCESS HATCH-WITH SAFETY GRATES TOP (267.5) S/S LIFTING CHAIN S/S FLOAT RACK S/S GUIDE RAILS HYDRORANGER NON-MERCURY FLOAT SWITCH 3" DI DISCHARGE INV IN 8" PVC (265.20) --HIGH WATER ALARM (264.50) LAG PUMP ON (264.0) LEAD PUMP ON (263.50) 4" X 3" REDUCER PUMPS OFF (262.50) BOTTOM (261.50) BASE (261.00) -5'-0" PUMP STATION SECTION

NOTES:

1. JUNCTION BOXES TO BE MOUNTED OUTSIDE OF WET WELL.

- 2. ALL ELECTRICAL COMPONENTS AND ENCLOSURES SHALL BE EXPLOSION PROOF.
- 3. PUMPS TO BE BARNES 4SE, 2.8HP, 6.25" IMP. DIA. (4SE2824L), PUMP STATION IS DESIGN TO OPERATE AT APPROXIMATELY 55 GPM (32" TDH).
- 4. SHOP DRAWINGS AND OPERATION AND MAINTENANCE MANUALS TO BE PROVIDED BY MANUFACTURER
- 5. FLOAT SWITCHES TO BE NON-MERCURY.
- 6. ADDITIONAL REQUIREMENTS:
- THE CONTROL SYSTEM SHALL INCLUDE REDUNDANT PUMPING CAPACITY. REDUNDANT ALARM ACTIVATION.
- LOCAL ALARM.
- LOCAL ALARM.

 ELECTRICAL CONNECTION FOR EMERGENCY POWER (SEE NOTE 8).


 AUTOMATIC AND MANUAL PUMP ACTIVATION.

 RUN TIME METER.
- 7. THIS PUMP STATION WILL BE PRIVATELY OWNED AND MAINTAINED BY THE PROPERTY OWNER. IT IS RECOMMENDED THAT THE ASSOCIATION CONTRACT WITH A PUMP STATION MAINTENANCE COMPANY TO PROVIDE RECULAR MAINTENANCE AND EMERGENCY SERVICE. THE MAINTENANCE COMPANY SHALL HAVE THE CAPACITY TO PROVIDE A PORTABLE GENERATOR IN THE EVENT OF A POWER OUTAGE.
- 8. SEASONAL HIGH WATER TABLE ELEVATION = 260.5' SEE SOILS SHEET 5

INFILTRATOR WATER TECHNOLOGIES

QUICK4 PLUS STANDARD CHAMBER PRODUCT SPECIFICATIONS (NOT TO SCALE)

TOP VIEW




INSPECTION PORT 2" diam.

QUICK4 PLUS ALL-IN-ONE 12 END CAP





PRESSURIZED PIPE DRILL **POINTS LOCATIONS** (2 PLACES)


SIDE VIEW



END VIEW







PROVIDE INSULATION IF LESS THAN 4'-6 1'-0" TO 3'-0" -CLEANOUT 6" PVC WYE OR TEE MIN. SLOPE 1/4" PER FOOT BASEMENT FLOOR SEWER MAIN OBSERVATION TEE FLEX JOINT AND ADAPTER PER APPLICABLE PLUMBING CODE

TYPICAL SERVICE CONNECTION AND BUILDING LATERAL DETAIL SCALE: NTS

NOTE: HOUSE SEWER MAY BE LOCATED BENEATH BASEMENT FLOOR

TYPICAL BOOT GASKET

08/07/20

DATE

NHDES AOT PERMIT REVISIONS

DESCRIPTION

SITE DETAILS TEN ROD RD 6 INDUSTRIAL WAY, ROCHESTER, NH INTEC AUTOMATION

ROCHESTER NH, 03867 ATTAR ENGINEERING, INC.

APPROVED BY NB REVISION DATE: 04/08/20 JOB NO: C164-20 FILE: IRM_DET.DWG SHEET: 13 OF 14

PO BOX 1653

