



Amendment to Approved Project City of Rochester, New Hampshire

Case # 216-8, 9, 10 Property Address 60 Farmington Road	
Type of project: Site Plan <u>×</u> ; Subdivision; Lot Line Adjustment; Other	
Project name	
Date of original Planning Board approval February 22, 2016 (See enclosed Notice of Decision)	Deligibility of the Control of the C
Description of amendment	-
The project is proposing to amend the prior approved Phase 2 site plan with an updated master plan and a revised alignment for Marketplace Boulevard extension. The project proposes to split Phase	# into
two construction phases (A & B). The enclosed package includes detail site design for Phase IIA which consists of three (3) front out parcels along Route 11 and Marketplace Boulevard extension up to the pro-	posed
roundabout. The enclosed package includes schematic design of Phase IIB, as depicted on the overall sheets, to plan for future roadway and development improvements such as layout, grading, stormwater & unchanged to the overall sheets.	itilities.
Would this affect a wetland or wetland buffer or require a conditional use? Yes x No	
Name of applicant or agent filling out this form Patrick M. Crimmins, PE (Tighe & Bond)	
Mailing Address: 177 Corporate Drive, Portsmouth NH, 03801	
Phone Number: 603.433.8818 Email Address: PMCrimmins@TigheBond.com	
Please check box: Applicant Agent	
Please note: There is a \$125.00 fee for amendments. They are reviewed by the Planning Board as public hearing is held. Abutters must be renotified by the applicant. The applicant must submit supplementary materials necessary to explain and support the amendment, such as a narrative and plans. form, the abutter's list, the fee when applicable, and other necessary materials must be submitted at leas days prior to the Planning Board meeting at which the amendment will be presented (by the Friday, 2-1/2 we prior to the meeting to allow for public notice).	any This t 17
Signature of person completing form: Date: 2/23/2 Signature of property owner (if different): Date: 2/23/2	Z 1

\roch-fileshare\plan\$\Forms\Applications\Application for Amendment.doc

Revised

2	131	mo	110
- 1	/26	//11	114



PLANNING & DEVELOPMENT DEPARTMENT City Hall - Second Floor 31 Wakefield Street Rochester, New Hampshire 03867-1917 (603) 335-1338 - Fax (603) 335-7585 Web Site: www.rochesternh.net

Planning and Development Conservation Commission Historic District Commission Arts & Culture Commission FEB 2 9 2016

NOTICE OF DECISION

February 25, 2016

Josh Levy Farmington Associates, LLC 322 Reservoir Street Needham, MA 02494

Re:

Site plan and Conditional Use Permit to construct a 163,000 sq ft commercial development. Case# 216 – 8,9,10 – GRD – 15

Dear Applicant:

This is to inform you that the Rochester Planning Board at its February 22, 2016 meeting **APPROVED** your application referenced above.

"Applicant", herein, refers to the property owner, business owner, individual(s), or organization submitting this application and to his/her/its agents, successors, and assigns.

Precedent Conditions	[Office use only. Date certified:	; CO signed off?;
As- Builts received?	All surety returned?	

All of the precedent conditions below must be met by the applicant, at the expense of the applicant, prior to the plans being certified by the Planning Department. Certification of the plans is required prior to issuance of a building permit or recording of any plans. Once these precedent conditions are met and the plans are certified the approval is considered final.

Please note* If all of the precedent conditions are not met within 6 calendar months to the day of the board's approval – by August 22, 2016 - the board's approval will be considered to have lapsed and resubmission of the application will be required. It is the sole responsibility of the applicant (or his/her agent) to ensure that these conditions are met by this deadline. We urge the applicant to carefully track his/her progress in meeting the individual conditions. Also, a building permit must be issued and substantially acted upon within 1 year of plan certification or the Planning Board approval is considered null and void. See RSA 674:39 on vesting.

Page 1 of 8

- 1) Plan modifications. The plan drawings are to be modified as follows:
 - a) Add a "tree box filter" symbol and label to the legend.
 - b) Silt fence/erosion control is shown at the very rear of the site against the property line at the top of the proposed slope blasted slope/wall. If this erosion control is not necessary, please remove.
 - c) The final plans shall reflect any NH DOT required changes.
 - d) The final plans shall reflect any NH DES required changes.
 - e) Remove all references to the "100' tall sign".
 - f) Please resize/rescale sheet C-18 so that the southern property line is shown.
 - g) The sidewalk that is adjacent to the parking lot travel land which connects the roundabout to the dual 55,000 sq ft buildings is called out to be 6' wide concrete for ¾ of the length, and the remainder is called out to be 4' wide bituminous. Please change the bituminous to concrete.
 - h) Please call out a thrust block to be placed against the cap at the future connection.
 - i) Please get all colors on the plans to black and white to eliminate any possible shading confusion moving forward. There are some browns, blues, purples, and magentas on the plans.
 - j) Please adjust the warning tape elevation call out from 24" (min) to just read 24". The warning tape is to be located approximately 24" from the top of the pipe, not further if possible.
 - k) Please adjust the callout on the trench details for the storm drain and the sewer from "common fill" for the 12" above the pipe to "sand blanket" or a similar callout matching DOT 304.1.
 - Please provide a detail showing the rexus frames and grates for the CBs within the City right-of-way. There is a note in the NHDOT type B detail stating this, but it seems like it could be easy to miss.
 - m) Please provide a detail showing the pamrex frames and covers for the MHs within the city right-of-way. There is a note in the manhole frame and grate detail stating this, but it seems like it could be easy to miss.
 - n) Please adjust the fiberglass hydrant marker pole length from 24" to 48" (min).
 - o) Please adjust the insulation detail on C-12 from being titled "Sewer Pipe Insulation Detail" to "Utility Pinpe Insulation Detail" as this type of insulating is for all utility piping.

- p) On sheet C-2A, the stream crossing is called out as a culvert, please revise to call it a "bridge".
- q) Details of the decorative guardrail must be provided.
- 2) Plan notes. Add the following notes (or equivalent) to the plan drawings:
 - a) Please note on the plans that additional information and details regarding the proposed cascade and stream/wetland work can be found in the NH DES Wetlands Dredge and Fill application or relocation.
 - b) The "notes" section at the bottom of most plan sheets contains workds that are blurred or missing letters, please correct.
 - c) The "Plant Schedule" on Sheet 5-C uses the code "CA" for two different plants. Please correct.
 - d) Please add a note that the truncated domes on the detectable warning plates are to be installed in parallel with the direction of travel from the sidewalk to the crosswalk. The triangle pattern versus the square pattern is dependent on how the detectable warning plate is installed in reference to the crosswalk.
- 3) Please submit documentation of what storm event the cascade is designed to handle.
- 4) Please submit documentation of the water table in the location of the cascade, and provide a written response noting the depth (feet or inches) of earth between the bottom of the proposed cascade and the top of groundwater table.
- As has been done for Route 11, please submit a traffic study/traffic analysis that lists the projected levels of service at all Marketplace Blvd intersections. It is possible that additional plan revisions may result from a review of this document.
- 6) Please eliminate or reduce by ½ the amount of wall-mount scone lighting on the eastern sides of both the northern most 2,800 sq ft restaurant and the 17,900 sq ft retail.
- 7) Additional wall mounted lighting along the western side of the Indoor Recreation structure may be warranted (the additional lighting would light the immediately adjacent sidewalk).
- At the request of Staff, the applicant is producing a plan that shows all improvements that are slated to be paid for by the City as part of the TIF/Developers Agreement. This plan will be presented to the Planning Board at the public hearing.
 Staff must also review this plan because the City's land use regulations require the developer to make certain improvements; we will review for such compliance, and any resulting plan changes (if any) will be forwarded to the applicant and the applicant will incorporate them into the final plan set.

Farmington Assoc. - Case # 216-8,9,10-GRD-15

Page 3 of 8

- 9) Operation & Maintenance Documents:
 - a) Please specify that snow is not to be pushed into the cascade, wetland, or wetland buffer areas.
 - b) Please submit a more detailed monitoring and maintenance plan specific to the cascade and impacted stream buffer areas. These plans should specify inspection intervals, procedures relative to vegetation removal and planting, stabilization, and sediment removal.
- 10) Demo plans call for the drain line between the two CBs at the end of the Marketplace Blvd located beneath the power lines. Is this accurate? It appears to be in the other drawings as remaining.
- 11) What is the purpose of PDMH-142? It appears that it may be difficult to access and install along the edge of the steep slope.
- 12) How was the PUD modeled for the downstream treatment systems? Was there consideration taken that a constant groundwater inflow into the treatment system may cause saturation of the downstream systems and therefore decrease their functionality? While it may not greatly impact stormwater flows, it could impact the system overall.
- 2" is not a common size for ductile iron pipe. Please adjust this to 2" copper or 2" SDR9 (200psi) HDPE. If the HDPE is used, then the detail will need to show tracer wire in addition to the warning tape. If copper is used, then only the warning tape is required.
- 14) NFPA 1 required hydrants at a maximum spacing of 500' apart with a potential increase in frequency based on adjacent building usage. Please review Ch. 18 of NFPA 1 and Annex I for details on hydrant spacing and required fire flow, and revise plans as necessary.
- Please provide inline gate valves approximately every 500'. Please pair these valves with hydrants whenever feasible, away from the water source, to facilitate a directional flushing program.
- Detail for the spacing between the large river stones is called out to be both "Native Material" and "1 thick rip-rap", please reconcile the difference and determine which is desired.
- 17) Please submit a draft easement(s) that speak to placing drainage, access ways, and other improvements on the Eversource property.
- 18) The final plans must include the street addresses of each structure. Please work with City Staff on these address numbers.
- 19) The lots must be merged. A lot merger application is required.

- 20) Easement deeds. The applicant shall provide a copy of any and all draft easements regarding the proposed private drainage structures within a proposed City Right-of-Way ("Frontage Road") in addition to other necessary deeds, including Eversource.
- 21)# Notarized Deed. Not applicable to this application.
- Current use. The subject property or a portion of it is presently in Current Use. The applicant must provide to the City of Rochester Assessing Department a revised current use map and/or any other items needed to assure that the requirements of RSA 79-A and the New Hampshire Department of Revenue's Administration Rules are satisfied. We encourage you to contact the Assessing Department at 332-5109 as soon as possible to discuss with them the financial ramifications of converting current use land. It will facilitate the process for you if you contact the department well in advance of commencing the project. The applicant shall provide the Planning Department with written verification from the Assessor that this has been done.
- 23) <u>State Plane Coordinates.</u> The plan shall be tied into the State Plane Coordinates.
- Inspections. The applicant must sign the Agreement for Payment of Inspection Fees and make a cash deposit to cover the expected costs of inspections, in a amount that is determined by the Public Works Department. (The inspections will be conducted by the City of Rochester Public Works Department or its designee. The applicant must pay for inspections at an hourly rate as determined by the Public Works Department of the site, including all new infrastructure serving the site).
- 25) <u>Pre-construction meeting</u>. The pre-construction meeting agreement is to be signed by the property owner.
- Other permits. All required state and federal permits must be obtained including any water and sewer, as appropriate with copies of permits or confirmation of approvals delivered to the Planning Department.
- 27) <u>Drainage maintenance</u>. A drainage maintenance agreement approved by Public Works must be executed In addition, a stormwater operations and maintenance plan and schedule shall be submitted.
- Final Drawings. (a) three sets of large black-line plus (b) one set of 11"x17" final approved site plan drawings plus (c) one electronic version by pdf or CD must be on file with the City. (The applicant need only submit additional black-line sets of drawings or individual sheets, as needed, to make three complete sets consult with the Planning Department). At the discretion of the Planning Department minor changes to drawings (as required in precedent condition, above) may be marked by hand.
 - Note: If there are significant changes to be made to the plans, as specified above, one full size <u>paper check print</u> must be sent to the Planning Department for review prior to producing these final drawings. (The primary set of plans was last received February 9, 2015). An updated set of architectural drawings shall be included.

General and Subsequent Conditions

All of the conditions below are attached to this approval.

- As tenants are secured and the related building facades are determined, the applicant must submit architectural elevations to be reviewed and approved by City Staff and/or the Planning Board. Also, the building facades along the frontage road shall be designed so as to not appear as the backside of the building.
- As stated by the applicant, all exterior site lighting (except for security lighting) will be turned off outside of business operating hours.
- The bridge should be built to NH DOT standards. Please provide verification to DPW that this bridge will meet such standards.
- 4) Once the bridge is built, please send the following information to the NHDOT for their records:
 - Bridge location
 - Plans and shop drawings
 - Specifications and Calculations
- 5)# Site work. No site work may be undertaken until: a) all of the precedent conditions are met; b) the pre-construction meeting with City staff has taken place; c) the limits of the proposed tree line are marked; and d) all appropriate erosion and sedimentation control structures are in place. These erosion and sedimentation control measures and the orange fence must be in place prior to the pre-construction meeting in order that they may be inspected at the meeting. Contact the City of Rochester Planning Department to arrange for the pre-construction meeting.
- Performance quarantee. The applicant, prior to issuance of a building permit or beginning site work, shall provide site improvement and restoration security. The performance guarantee shall be an amount equal to 10% of the approved Construction Cost Estimate (including a 10% contingency) to ensure the proper and timely completion of site work and site restoration within the development. Before the subdivision/site plan can be recorded, lots deeded to third parties, or structure occupied the applicant shall provide a cost estimate of remaining site work including labor, and provide the City with a security equal to 110% of the estimated cost for remaining site work. (Any existing surety being held at this time may be considered toward this amount). This amount shall include preparation of as-built plans. Construction Cost estimate for this project shall be submitted for review and approval. Estimate shall be based on the Department of Public Works Construction Surety Schedule and shall include a 10% Contingency. Costs for items not specifically addressed in the Surety Schedule will be based on 1) City standards, 2) NHDOT weighted averages, 3) industry standards, or 4) contractor estimates.
- 7) <u>Variances</u>. Any and all variances must be adhered to.

- Erosion control. All erosion and sedimentation control structures must remain in place and be maintained until vegetation is established or ground surface is suitably stabilized. Note that the filter fabric on silt fences must be buried at least 12" below the ground surface in order to function properly. Best management practices must be followed for wetlands protection.
- 9) As builts. Three sets of full size (measuring at least 22" x 34") or black line paper plus on full size mylar plus 1 set of 11" x 17" plus on digital pdf copy of the as-built site plans (or "record drawings") stamped and signed by the Engineer or Surveyor are to be submitted to the Planning Department prior to issuance of the Certificate of Occupancy (or use/occupancy of the site where no CO is required). The as-built drawings must include the following language or equivalent: "This as-built drawing substantially conforms with the final plans approved by the City of Rochester Planning Board and certified by the Planning and Development Department except for the following significant modifications:....". If no significant modifications were made simply state "none". Otherwise, itemize the modifications on the as-built or on an accompanying letter. The Department relies on the good judgment and good faith of the Engineer/Surveyor in determining which modifications should be considered significant (for example, minor adjustments in locations of plant materials would not be significant whereas relocation of a catch basin would be).
- 10) <u>Execution.</u> The project must be built and executed exactly as specified in the approved application package unless changes are approved by the City.
- 11) Approval. All of the documentation submitted in the application package by the applicant and any requirements imposed by other agencies are part of this approval unless otherwise updated, revised, clarified in some manner, or superseded in full or in part. In the case of conflicting information between documents, the most recent documentation and this notice herein shall generally be determining.
- Violations. In the event of any violations of these conditions of approval or of any pertinent local, state, or federal laws such as those regarding erosion and sedimentation control, wetlands, stormwater management, and general site development standards the City of Rochester reserves the right to take any appropriate permissible action, including, but not limited to, withholding of building permits, withholding of certificates of occupancy, withholding of driveway permits, revocations of permits/approvals, referring violations to other agencies, and calling of bonds.
- Other Permits. It is the responsibility of the applicant to obtain all other local, state, and federal permits, licenses, and approvals which may be required as part of this project. Contact the City of Rochester's Building, Zoning, and Licensing Department at 332-3508 regarding building permits. Please also contact the City of Rochester Fire Department at 330-7182 to ensure that the proposed building meets all Fire Codes. Finally, please contact the Department of Public Works for any stormwater, sewer, or water permits or fees that are required.

(Note: in both sections above, the numbered condition marked with a # and all conditions below the # are standard conditions on all or most applications of this type).

Sincerely,

James Campbell,


Director of Planning & Development


Tighe & Bond J. Grant, BZL Services (via email) R. Vincent, Assessing (via email) O. Friend-Gray, City Engineer (via email) File


Farmington Assoc. - Case # 216-8,9,10-GRD-15


Page 8 of 8


























В	2/23/2021	Amended Site Plan Review Submission
Α	11/25/2019	Site Plan Review Submission
MARK	DATE	DESCRIPTION
PROJEC	T NO:	W5008-004
DATE:		11/25/2019
FILE:	W5	008-004_DSGN.DWG
DRAW	N BY:	CML
CHECK	ED:	PMC











В	2/23/2021	Amended Site Plan Review Submission
Α	11/25/2019	Site Plan Review Submission
MARK	DATE	DESCRIPTION
PROJE	CT NO:	W5008-004
DATE:		11/25/2019
FILE:	W5	008-004_DSGN.DWG
DRAW	N BY:	CML
CHECK	ED:	PMC
APPRO	VED:	BLM


C-105














322 RESERVOIR STREET NEEDHAM, MA 02494

PROPOSED COMMERCIAL DEVELOPMENT PROJECT ADDRESS: 60 FARMINGTON ROAD ROCHESTER, NH 03867 MAP 216 / LOTS 8, 9, 10

PROJECT LATITUDE: 43°-19'-45"N PROJECT LONGITUDE: 71°-00'-18"W

PROJECT DESCRIPTION
THE PROJECT CONSISTS OF THE CONSTRUCTION OF A COMMERCIAL DEVELOPMENT WITH ASSOCIATED PARKING, DRAINAGE, UTILITIES, LANDSCAPING AND A NEW FRONTAGE ROAD CONSISTENT WITH THE CITY OF ROCHESTER'S MASTER PLAN.

<u>DISTURBED AREA</u>
THE TOTAL AREA TO BE DISTURBED IS APPROXIMATELY ±25.0 ACRES.

SOIL CHARACTERISTICS
BASED ON SITE SPECIFIC SOIL SURVEY CONDUCTED BY NHSC, INC. THE SITE CONSISTS MAINLY
OF MODERATELY WELL TO POORLY DRAINED SOILS WITH HYDROLOGIC SOIL GROUPS A, B, C, AND

NAME OF RECEIVING WATERS
THE STORM WATER RUNOFF WILL BE DISCHARGED VIA OVERLAND FLOW TO UNNAMED STREAM WHICH ULTIMATELY FLOWS TO THE COCHECO RIVER.

CONSTRUCTION SEQUENCE OF MAJOR ACTIVITIES:

- CONSTRUCT TEMPORARY AND PERMANENT SEDIMENT, EROSION AND DETENTION CONTROL FACILITIES. EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH MOVING OPERATIONS THAT WILL INFLUENCE STORMWATER RUNOFF SUCH AS: NEW CONSTRUCTION
- DEVELOPMENT OF BORROW PIT AREAS
 DISPOSAL OF SEDIMENT SPOIL, STUMP AND OTHER SOLID WASTE
- FLOOD PLAIN EXCAVATION WORK
- STREAM CHANNEL MODIFICATIONS
- CONTROL OF DUST
- CONSTRUCTION OF ACCESS AND HAUL ROAD
- NEARNESS OF CONSTRUCTION SITE TO RECEIVING WATERS CONSTRUCTION DURING LATE WINTER AND EARLY SPRING
- ALL PERMANENT DITCHES, SWALES, DETENTION, RETENTION AND SEDIMENTATION BASINS TO BE STABILIZED USING THE VEGETATIVE AND NON-STRUCTURAL BMPS PRIOR TO
- DIRECTING RUNOFF TO THEM.
 CLEAR AND DISPOSE OF DEBRIS.
- CONSTRUCT TEMPORARY CULVERTS AND DIVERSION CHANNELS AS REQUIRED.
- GRADE AND GRAVEL ROADWAYS AND PARKING AREAS ALL ROADS AND PARKING AREA SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
- BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES
- SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

 DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINS, DITCHES, PERIMETER
 EROSION CONTROL MEASURES, SEDIMENT TRAPS, ETC., MULCH AND SEED AS REQUIRED.
- SEDIMENT TRAPS AND/OR BASINS SHALL BE USED AS NECESSARY TO CONTAIN RUNOF
- UNTIL SOILS ARE STABILIZED.

 10. FINISH PAVING ALL ROADWAYS AND PARKING LOTS.
- 11. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES.
- COMPLETE PERMANENT SEEDING AND LANDSCAPING.
 REMOVE TRAPPED SEDIMENTS FROM COLLECTOR DEVICES AS APPROPRIATE AND THEN
- REMOVE TEMPORARY EROSION CONTROL MEASURES.

- SPECIAL CONSTRUCTION NOTES:
 1. THE CONSTRUCTION SEQUENCE MUST LIMIT THE DURATION AND AREA OF DISTURBANCE. THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT
- OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES. LOT DISTURBANCE, OTHER THAN THAT SHOWN ON THE APPROVED PLANS, SHALL NOT COMMENCE UNTIL AFTER THE ROADWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE. - THIS NOTE IS APPLICABLE TO SINGLE/DUPLEX FAMILY SUBDIVISIONS, WHEN LOT DEVELOPMENT IS NOT PART OF THE

- FOR EROSION CONTROL MEASURES AS REQUIRED IN THE PROJECT MANUAL.
- CONTRACTOR SHALL INSTALL TEMPORARY FROSION CONTROL BARRIERS, INCLUDING HAY DANKIERS, SILT FENCES, MULCH BERMS, SILT SACKS AND SILT SOCKS AS SHOWN IN THESE DRAWINGS AS THE FIRST ORDER OF WORK.

 SILT SACK INLET PROTECTION SHALL BE INSTALLED IN ALL EXISTING AND PROPOSED CATCH
- BASIN INLETS WITHIN THE WORK LIMITS AND BE MAINTAINED FOR THE DURATION OF THI PERIMETER CONTROLS INCLUDING SILT FENCES, MULCH BERM, SILT SOCK, AND/OR HAY BALE
- BARRIERS SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT UNTIL NON-PAVED AREAS HAVE BEEN STABILIZED THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL TEMPORARY EROSION
- CONTROL DEVICES UPON COMPLETION OF CONSTRUCTION.
- ALL DISTURBED AREAS NOT OTHERWISE BEING TREATED SHALL RECEIVE 6" LOAM, SEED AND
- INSPECT ALL INLET PROTECTION AND PERIMETER CONTROLS WEEKLY AND AFTER EACH RAIN STORM OF 0.25 INCH OR GREATER. REPAIR/MODIFY PROTECTION AS NECESSARY TO MAXIMIZE EFFICIENCY OF FILTER. REPLACE ALL FILTERS WHEN SEDIMENT IS 1/3 THE FILTER
- CONSTRUCT EROSION CONTROL BLANKETS ON ALL SLOPES STEEPER THAN 3:1.

- STABILIZATION:

 1. AN AREA SHALL BE CONSIDERED STABLE WHEN ONE OF THE FOLLOWING HAS OCCURRED:

 1. AN AREA SHALL BE CONSIDERED STABLE WHEN ONE OF THE FOLLOWING HAS OCCURRED:
 - A. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;
 B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
 - A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED:

 - EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.;
 IN AREAS TO BE PAVED, "STABLE" MEANS THAT BASE COURSE GRAVELS MEETING THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, 2016. ITEM 304.2 HAVE BEEN INSTALLED.
 WINTER STABILIZATION PRACTICES:
- A. ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER
- ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE, THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS:
- VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS:

- C. AFTER OCTOBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3, OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT;
 STABILIZATION SHALL BE INITIATED ON ALL LOAM STOCKPILES, AND DISTURBED AREAS,
- WHERE CONSTRUCTION ACTIVITY SHALL NOT OCCUR FOR MORE THAN TWENTY-ONE (21) CALENDAR DAYS BY THE FOURTEENTH (14TH) DAY AFTER CONSTRUCTION ACTIVITY HAS PERMANENTLY OR TEMPORARILY CEASED IN THAT AREA. STABILIZATION MEASURES TO BE USED INCLUDE:
- TEMPORARY SEEDING;
- ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE.
- WHEN CONSTRUCTION ACTIVITY PERMANENTLY OR TEMPORARILY CEASES WITHIN 100 FEET OF NEARBY SURFACE WATERS OR DELINEATED WETLANDS, THE AREA SHALL BE STABILIZED WITHIN SEVEN (7) DAYS OR PRIOR TO A RAIN EVENT, ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN THESE AREAS, SILT FENCES, MULCH BERMS, HAY BALE BARRIERS AND ANY EARTH/DIKES SHALL BE REMOVED ONCE PERMANENT MEASURES ARE
- DURING CONSTRUCTION, RUNOFF WILL BE DIVERTED AROUND THE SITE WITH EARTH DIKES PIPING OR STABILIZED CHANNELS WHERE POSSIBLE. SHEET RUNOFF FROM THE SITE WILL BE FILTERED THROUGH SILT FENCES, MULCH BERMS, HAY BALE BARRIERS, OR SILT SOCKS. ALL STORM DRAIN BASIN INLETS SHALL BE PROVIDED WITH FLARED END SECTIONS AND TRASH RACKS. THE SITE SHALL BE STABILIZED FOR THE WINTER BY OCTOBER 15

- THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST THROUGHOUT THE
- CONSTRUCTION PERIOD.

 DUST CONTROL METHODS SHALL INCLUDE, BUT BE NOT LIMITED TO SPRINKLING WATER ON EXPOSED AREAS, COVERING LOADED DUMP TRUCKS LEAVING THE SITE, AND TEMPORARY
- DUST CONTROL MEASURES SHALL BE UTILIZED SO AS TO PREVENT THE MIGRATION OF DUST FROM THE SITE TO ABUTTING AREAS.

- STOCKPILES:

 1. LOCATE STOCKPILES A MINIMUM OF 50 FEET AWAY FROM CATCH BASINS, SWALES, AND
- ALL STOCKPILES SHOULD BE SURROUNDED WITH TEMPORARY EROSION CONTROL MEASURES PRIOR TO THE ONSET OF PRECIPITATION. 3. PERIMETER BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO
- ACCOMMODATE THE DELIVERY AND REMOVAL OF MATERIALS FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIER SHOULD BE INSPECTED AT THE END OF EACH WORKING DAY.
- PROTECT ALL STOCKPILES FROM STORMWATER RUN-OFF USING TEMPORARY EROSION CONTROL MEASURES SUCH AS BERMS, SILT SOCK, OR OTHER APPROVED PRACTICE TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILES.

OFF SITE VEHICLE TRACKING:

1. THE CONTRACTOR SHALL CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE(S) PRIOR TO ANY EXCAVATION ACTIVITIES.

VEGETATION: L. TEMPORARY GRASS COVER: A. SEEDBED PREPARATION:

- APPLY FERTILIZER AT THE RATE OF 600 POUNDS PER ACRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF THREE (3) TONS PER ACRE:
- UTILIZE ANNUAL RYE GRASS AT A RATE OF 40 LBS/ACRE;
 WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF TWO (2) INCHES BEFORE APPLYING FERTILIZER, LIME AND
- APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). HYDROSEEDINGS, WHICH INCLUDE MULCH, MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10% WHEN
- C. MAINTENANCE
- TEMPORARY SEEDING SHALL BE PERIODICALLY INSPECTED. AT A MINIMUM, 95% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND OTHER TEMPORARY MEASURES USED IN THE INTERIM (MULCH, FILTER BARRIERS, CHECK
- DAMS, ETC.).
 2. PERMANENT MEASURES AND PLANTINGS:
 - LIMESTONE SHALL BE THOROUGHLY INCORPORATED INTO THE LOAM LAYER AT A RATE OF
- THREE (3) TONS PER ACRE IN ORDER TO PROVIDE A PH VALUE OF 5.5 TO 6.5; FERTILIZER SHALL BE SPREAD ON THE TOP LAYER OF LOAM AND WORKED INTO THE SURFACE. FERTILIZER APPLICATION RATE SHALL BE 800 POUNDS PER ACRE OF 10-20-20
- SOIL CONDITIONERS AND FERTILIZER SHALL BE APPLIED AT THE RECOMMENDED RATES AND SHALL BE THOROUGHLY WORKED INTO THE LOAM. LOAM SHALL BE RAKED UNTIL THE SURFACE IS FINELY PULVERIZED, SMOOTH AND EVEN, AND THEN COMPACTED TO AN EVEN SURFACE CONFORMING TO THE REQUIRED LINES AND GRADES WITH APPROVED ROLLERS WEIGHING BETWEEN 4-1/2 POUNDS AND 5-1/2 POUNDS PER INCH OF WIDTH;
- SEED SHALL BE SOWN AT THE RATE SHOWN BELOW, SOWING SHALL BE DONE ON A CALM, DRY DAY, PREFERABLY BY MACHINE, BUT IF BY HAND, ONLY BY EXPERIENCED WORKMEN. IMMEDIATELY BEFORE SEEDING, THE SOIL SHALL BE LIGHTLY RAKED. ONE HALF THE SEED SHALL BE SOWN IN ONE DIRECTION AND THE OTHER HALF AT RIGHT ANGLES TO THE ORIGINAL DIRECTION, IT SHALL BE LIGHTLY RAKED INTO THE SOIL TO A DEPTH NOT OVER 1/4 INCH AND ROLLED WITH A HAND ROLLER WEIGHING NOT OVER 100 POUNDS PER LINEAR FOOT OF WIDTH;
- HAY MULCH SHALL BE APPLIED IMMEDIATELY AFTER SEEDING AS INDICATED ABOVE:
- THE SURFACE SHALL BE WATERED AND KEPT MOIST WITH A FINE SPRAY AS REQUIRED, WITHOUT WASHING AWAY THE SOIL, UNTIL THE GRASS IS WELL ESTABLISHED. ANY AREAS WHICH ARE NOT SATISFACTORILY COVERED WITH GRASS SHALL BE RESERVED AND ALL NOXIOUS WEEDS REMOVED
- THE CONTRACTOR SHALL PROTECT AND MAINTAIN THE SEEDED AREAS UNTIL ACCEPTED; A GRASS SEED MIXTURE CONTAINING THE FOLLOWING SEED REQUIREMENTS SHALL BE
- APPLIED AT THE INDICATED RATE:

SEED MIX APPLICATION RATE
CREEPING RED FESCUE 50 LBS/ACRE
KENTUCKY BLUEGRASS 100 LBS/ACRE

PERRENIAL RYE GRASS 50 LBS/ACRE
IN NO CASE SHALL THE WEED CONTENT EXCEED ONE (1) PERCENT BY WEIGHT. ALL SEED SHALL COMPLY WITH STATE AND FEDERAL SEED LAWS, SEEDING SHALL BE DONE NO LATER THAN SEPTEMBER 15. IN NO CASE SHALL SEEDING TAKE PLACE OVER SNOW RMANT SEEDING (SEPTEMBER 15 TO FIRST SNOWFALL):

FOLLOW PERMANENT MEASURES SLOPE, LIME, FERTILIZER AND GRADING REQUIREMENTS. APPLY SEED MIXTURE AT TWICE THE INDICATED RATE, APPLY MULCH AS INDICATED FOR PERMANENT MEASURES.

- CONCRETE WASHOUT AREA:

 1. THE FOLLOWING ARE THE ONLY NON-STORMWATER DISCHARGES ALLOWED. ALL OTHER NON-STORMWATER DISCHARGES ARE PROHIBITED ON SITE:

 A. THE CONCRETE DELIVERY TRUCKS SHALL, WHENEVER POSSIBLE, USE WASHOUT
 - FACILITIES AT THEIR OWN PLANT OR DISPATCH FACILITY IF IT IS NECESSARY, SITE CONTRACTOR SHALL DESIGNATE SPECIFIC WASHOUT AREAS AND DESIGN FACILITIES TO HANDLE ANTICIPATED WASHOUT WATER;
 - CONTRACTOR SHALL LOCATE WASHOUT AREAS AT LEAST 150 FEET AWAY FROM STORM DRAINS, SWALES AND SURFACE WATERS OR DELINEATED WETLANDS;
 INSPECT WASHOUT FACILITIES DAILY TO DETECT LEAKS OR TEARS AND TO IDENTIFY
 WHEN MATERIALS NEED TO BE REMOVED.

ALLOWABLE NON-STORMWATER DISCHARGES: 1. FIRE-FIGHTING ACTIVITIES;

- FIRE HYDRANT FLUSHING:

- WATER USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED; WATER USED TO CONTROL DUST; POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHING;
- ROUTINE EXTERNAL BUILDING WASH DOWN WHERE DETERGENTS ARE NOT USED; PAVEMENT WASH WATERS WHERE DETERGENTS ARE NOT USED;
 - UNCONTAMINATED AIR CONDITIONING/COMPRESSOR CONDENSATION
- UNCONTAMINATED GROUND WATER OR SPRING WATER:
- FOUNDATION OR FOOTING DRAINS WHICH ARE UNCONTAMINATED; UNCONTAMINATED EXCAVATION DEWATERING;
- LANDSCAPE IRRIGATION.

WASTE DISPOSAL: 1. WASTE MATERIAL

- . ALL WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED IN A DUMPSTER;
- NO CONSTRUCTION WASTE MATERIALS SHALL BE BURIED ON SITE: ALL PERSONNEL SHALL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR
- WASTE DISPOSAL BY THE SUPERINTENDENT. HAZARDOUS WASTE:
- ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER; SITE PERSONNEL SHALL BE INSTRUCTED IN THESE PRACTICES BY THE SUPERINTENDENT.
- 3 SANITARY WASTE. A. ALL SANTTARY WASTE SHALL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONCE PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

- SPILL PREVENTION:
 1. CONTRACTOR SHALL BE FAMILIAR WITH SPILL PREVENTION MEASURES REQUIRED BY LOCAL, STATE AND FEDERAL AGENCIES. AT A MINIMUM, CONTRACTOR SHALL FOLLOW THE BEST MANAGEMENT SPILL PREVENTION PRACTICES OUTLINED BELOW
- THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT SHALL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES DURING CONSTRUCTION TO STORMWATER RUNGER
 - GOOD HOUSEKEEPING THE FOLLOWING GOOD HOUSEKEEPING PRACTICE SHALL BE FOLLOWED ON SITE DURING CONSTRUCTION: . ONLY SUFFICIENT AMOUNTS OF PRODUCTS TO DO THE JOB SHALL BE STORED ON
 - SITE; ALL REGULATED MATERIALS STORED ON SITE SHALL BE STORED IN A NEAT, ORDERLY
 - MANNER IN THEIR PROPER (ORIGINAL IF POSSIBLE) CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE, ON AN IMPERVIOUS SURFACE;
 MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL SHALL BE
 - FOLLOWED: d. THE SITE SUPERINTENDENT SHALL INSPECT DAILY TO ENSURE PROPER USE AND
 - DISPOSAL OF MATERIALS; SUBSTANCES SHALL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER:
 - WHENEVER POSSIBLE ALL OF A PRODUCT SHALL BE USED UP BEFORE DISPOSING OF
 - g. THE TRAINING OF ON-SITE EMPLOYEES AND THE ON-SITE POSTING OF RELEASE RESPONSE INFORMATION DESCRIBING WHAT TO DO IN THE EVENT OF A SPILL OF REGULATED SUBSTANCES.
 - HAZARDOUS PRODUCTS THE FOLLOWING PRACTICES SHALL BE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS. a. PRODUCTS SHALL BE KEPT IN THEIR ORIGINAL CONTAINERS UNLESS THEY ARE NOT
 - b. ORIGINAL LABELS AND MATERIAL SAFETY DATA SHALL BE RETAINED FOR IMPORTANT
 - PRODUCT INFORMATION;
 SURPLUS PRODUCT THAT MUST BE DISPOSED OF SHALL BE DISCARDED ACCORDING TO THE MANUFACTURER'S RECOMMENDED METHODS OF DISPOSAL PRODUCT SPECIFIC PRACTICES - THE FOLLOWING PRODUCT SPECIFIC PRACTICES SHALL BE FOLLOWED ON SITE:

 - PETROLEUM PRODUCTS: ALL ON SITE VEHICLES SHALL BE MONITORED FOR LEAKS AND RECEIVE REGULAR
 - PETROLEUM PRODUCTS SHALL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT BASED SUBSTANCES USED ON SITE SHALL BE
 - APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS SECURE FUEL STORAGE AREAS AGAINST UNAUTHORIZED ENTRY;
 - iv. INSPECT FUEL STORAGE AREAS WEEKLY:
 - WHEREVER POSSIBLE, KEEP REGULATED CONTAINERS THAT ARE STORED OUTSIDE MORE THAN 50 FEET FROM SURFACE WATER AND STORM DRAINS, 75 FEET FROM PRIVATE WELLS, AND 400 FEET FROM PUBLIC WELLS;
 - COVER REGULATED CONTAINERS IN OUTSIDE STORAGE AREAS: SECONDARY CONTAINMENT IS REQUIRED FOR CONTAINERS CONTAINING REGULATED SUBSTANCES STORED OUTSIDE, EXCEPT FOR ON PREMISE USE HEATING FUEL TANKS, OR ABOVEGROUND OR UNDERGROUND STORAGE TANKS OTHERWISE
 - REGULATED. viii. THE FUEL HANDLING REQUIREMENTS SHALL INCLUDE:
 - (1) EXCEPT WHEN IN USE, KEEP CONTAINERS CONTAINING REGULATED
 - SUBSTANCES CLOSED AND SEALED: (2) PLACE DRIP PANS UNDER SPIGOTS, VALVES, AND PUMPS;
 (3) HAVE SPILL CONTROL AND CONTAINMENT EQUIPMENT READILY AVAILABLE
 - IN ALL WORK AREAS: (4) USE FUNNELS AND DRIP PANS WHEN TRANSFERRING REGULATED
 - SUBSTANCES; (5) PERFORM TRANSFERS OF REGULATED SUBSTANCES OVER AN IMPERVIOUS
 - SURFACE ix. FUELING AND MAINTENANCE OF EXCAVATION, EARTHMOVING AND OTHER CONSTRUCTION RELATED EQUIPMENT SHALL COMPLY WITH THE REGULATIONS OF THE NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES THESE REQUIREMENTS ARE SUMMARIZED IN WD-DWGB-22-6 BEST MANAGEMENT
 PRACTICES FOR FUELING AND MAINTENANCE OF EXCAVATION AND EARTHMOVING
 - FOUIPMENT, OR ITS SUCCESSOR DOCUMENT. FERTILIZERS FERTILIZERS USED SHALL BE APPLIED ONLY IN THE MINIMUM AMOUNTS DIRECTED
 - BY THE SPECIFICATIONS; ONCE APPLIED FERTILIZER SHALL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE
 - TO STORMWATER; STORAGE SHALL BE IN A COVERED SHED OR ENCLOSED TRAILERS. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER SHALL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS.
 - ALL CONTAINERS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR EXCESS PAINT SHALL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM
- EXCESS PAINT SHALL BE DISPOSED OF PROPERLY ACCORDING TO MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS.
- D. SPILL CONTROL PRACTICES IN ADDITION TO GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTION, THE FOLLOWING PRACTICES SHALL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP: MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP SHALL BE CLEARLY POSTED AND SITE PERSONNEL SHALL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES;
- MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP SHALL BE KEPT IN THE MATERIAL STORAGE AREA ON SITE. EQUIPMENT AND MATERIALS SHALL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST AND PLASTIC OR METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE:

- ALL SPILLS SHALL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY;
- THE SPILL AREA SHALL BE KEPT WELL VENTILATED AND PERSONNEL SHALL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A
- HAZARDOUS SUBSTANCE;
 SPILLS OF TOXIC OR HAZARDOUS MATERIAL SHALL BE REPORTED TO THE APPROPRIATE LOCAL, STATE OR FEDERAL AGENCIES AS REQUIRED:
- THE SITE SUPERINTENDENT RESPONSIBLE FOR DAY-TO-DAY SITE OPERATIONS SHALL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR.
- E. VEHICLE FUELING AND MAINTENANCE PRACTICE:
 - CONTRACTOR SHALL MAKE AN EFFORT TO PERFORM EQUIPMENT/VEHICLE FUELING AND MAINTENANCE AT AN OFF-SITE FACILITY; CONTRACTOR SHALL PROVIDE AN ON-SITE FUELING AND MAINTENANCE AREA THAT
- IS CLEAN AND DRY:
- IF POSSIBLE THE CONTRACTOR SHALL KEEP AREA COVERED CONTRACTOR SHALL KEEP A SPILL KIT AT THE FUELING AND MAINTENANCE AREA:
- CONTRACTOR SHALL REGULARLY INSPECT VEHICLES FOR LEAKS AND DAMAGE CONTRACTOR SHALL USE DRIP PANS, DRIP CLOTHS, OR ABSORBENT PADS WHEN REPLACING SPENT FLUID.

- EROSION CONTROL OBSERVATIONS AND MAINTENANCE PRACTICES

 1. THIS PROJECT (DOES NOT) EXCEED(S) ONE (1) ACRE OF DISTURBANCE AND THUS (DOES NOT) REQUIRE(S) A SWPPP. THE SWPPP SHALL BE PREPARED BY THE ENGINEER (CONTRACTOR). THE CONTRACTOR SHALL BE FAMILIAR WITH THE SWPPP AND KEEP AN UPDATED COPY OF THE SWPPP ONSITE AT ALL TIMES.
- THE FOLLOWING REPRESENTS THE GENERAL OBSERVATION AND REPORTING PRACTICES THAT SHALL BE FOLLOWED AS PART OF THIS PROJECT:

 A. OBSERVATIONS OF THE PROJECT FOR COMPLIANCE WITH THE SWPPP SHALL BE MADE BY
- THE ENGINEER (CONTRACTOR) AT LEAST ONCE A WEEK OR WITHIN 24 HOURS OF A STORM 0.25 INCHES OR GREATER
- AN OBSERVATION REPORT SHALL BE MADE AFTER EACH OBSERVATION AND DISTRIBUTED TO THE ENGINEER, THE OWNER, AND THE CONTRACTOR;
- C. A REPRESENTATIVE OF THE SITE CONTRACTOR, SHALL BE RESPONSIBLE FOR
- MAINTENANCE AND REPAIR ACTIVITIES;
 D. IF A REPAIR IS NECESSARY, IT SHALL BE INITIATED WITHIN 24 HOURS OF REPORT.
- BLASTING NOTES:

 1. CONTRACTOR SHALL CONTACT THE NHDES PRIOR TO COMMENCING ANY BLASTING **ACTIVITIES** 2. FOR ANY PROJECT FOR WHICH BLASTING OF BEDROCK IS ANTICIPATED, THE APPLICANT
- SHALL SUBMIT:
 A. A BLASTING PLAN THAT IDENTIFIES:
- WHERE THE BLASTING ACTIVITIES ARE ANTICIPATED TO OCCUR THE ESTIMATED QUANTITY OF BLAST ROCK IN CUBIC YARDS; AND SITE-SPECIFIC BLASTING BEST MANAGEMENT PRACTICES. IF MORE THAN 5000 CUBIC YARDS OF BLAST ROCK WILL BE GENERATED AND THERE ARE ONE
- OR MORE PUBLIC DRINKING WATER WELLS WITHIN 2000 FEET OF THE BLASTING ACTIVITIES, A PLAN TO MONITOR GROUNDWATER TO DETECT ANY CONTAMINATION IN SUFFICIENT TIME TO PROTECT THE WATER SUPPLY WELLS SHALL BE PROVIDED TO THE NHDES. THE GROUNDWATER MONITORING PLAN SHALL INCLUDE:
- MONITORING FOR NITRATE AND NITRITE EITHER IN THE DRINKING WATER SUPPLY WELLS OR IN OTHER WELLS THAT ARE REPRESENTATIVE OF THE DRINKING WATER SUPPLY WELLS IN THE AREA: THE GROUNDWATER SAMPLING PROGRAM MUST BE IMPLEMENTED ONCE APPROVED
- B. THE FOLLOWING BEST MANAGEMENT PROCEDURES FOR BLASTING SHALL BE COMPLIED
- LOADING PRACTICES THE FOLLOWING BLASTHOLE LOADING PRACTICES TO MINIMIZE ENVIRONMENTAL EFFECTS SHALL BE FOLLOWED: DRILLING LOGS SHALL BE MAINTAINED BY THE DRILLER AND COMMUNICATED DIRECTLY TO THE BLASTER. THE LOGS SHALL INDICATE DEPTHS AND LENGTHS OF VOIDS, CAVITIES, AND FAULT ZONES OR OTHER WEAK ZONES ENCOUNTERED AS
- WELL AS GROUNDWATER CONDITIONS: EXPLOSIVE PRODUCTS SHALL BE MANAGED ON-SITE SO THAT THEY ARE FITHER USED IN THE BOREHOLE, RETURNED TO THE DELIVERY VEHICLE, OR PLACED IN SECURE CONTAINERS FOR OFF-SITE DISPOSAL; SPILLAGE AROUND THE BOREHOLE SHALL FITHER BE PLACED IN THE BOREHOLE OR
- CLEANED UP AND RETURNED TO AN APPROPRIATE VEHICLE FOR HANDLING OF PLACEMENT IN SECURED CONTAINERS FOR OFF-SITE DISPOSAL; iv. LOADED EXPLOSIVES SHALL BE DETONATED AS SOON AS POSSIBLE AND SHALL NOT BE LEFT IN THE BLASTHOLES OVERNIGHT, UNLESS WEATHER OR OTHER SAFETY CONCERNS REASONABLY DICTATE THAT DETONATION SHOULD BE POSTPONED;

 V. LOADING EQUIPMENT SHALL BE CLEANED IN AN AREA WHERE WASTEWATER CAN BE
- PROPERLY CONTAINED AND HANDLED IN A MANNER THAT PREVENTS RELEASE O CONTAMINANTS TO THE ENVIRONMENT;

 VI. EXPLOSIVES SHALL BE LOADED TO MAINTAIN GOOD CONTINUITY IN THE COLUMN LOAD TO PROMOTE COMPLETE DETONATION, INDUSTRY ACCEPTED LOADING
- PRACTICES FOR PRIMING, STEMMING, DECKING AND COLUMN RISE NEED TO BE b. EXPLOSIVE SELECTION - THE FOLLOWING BMPS SHALL BE FOLLOWED TO REDUCE
- THE POTENTIAL FOR GROUNDWATER CONTAMINATION WHEN EXPLOSIVES ARE USED: EXPLOSIVE PRODUCTS SHALL BE SELECTED THAT ARE APPROPRIATE FOR SITE CONDITIONS AND SAFE BLAST EXECUTION: II. EXPLOSIVE PRODUCTS SHALL BE SELECTED THAT HAVE THE APPROPRIATE WATER RESISTANCE FOR THE SITE CONDITIONS PRESENT TO MINIMIZE THE POTENTIAL FOR HAZARDOUS EFFECT OF THE PRODUCT UPON GROUNDWATER
- c. PREVENTION OF MISFIRES, APPROPRIATE PRACTICES SHALL BE DEVELOPED AND IMPLEMENTED TO PREVENT MISSIRES MUCK PILES MANAGEMENT - MUCK PILES (THE BLASTED PIECES OF ROCK) AND ROCK PILES SHALL BE MANAGED IN A MANNER TO REDUCE THE POTENTIAL FOR
- CONTAMINATION BY IMPLEMENTING THE FOLLOWING MEASURES: REMOVE THE MUCK PILE FROM THE BLAST AREA AS SOON AS REASONABLY POSSIBLE; MANAGE THE INTERACTION OF BLASTED ROCK PILES AND STORMWATER TO PREVENT

CONTAMINATION OF WATER SUPPLY WELLS OR SURFACE WATER.

SPILL PREVENTION AND SPILL MITIGATION MEASURES SHALL BE IMPLEMENTED TO PREVENT THE RELEASE OF FUEL AND OTHER RELATED SUBSTANCES TO THE ENVIRONMENT DURING BLASTING OPERATIONS. THE MEASURES TO PREVENT SUCH RELEASES SHALL BE DETAILED IN THE GROUNDWATER MONITORING REPORT AND COMPLY WITH THE MEASURES AND BEST MANAGEMENT PRACTICES LISTED ON THIS

Tiahe&Bond





Proposed Ridgeside Development

Farmington Associates, LLC

60 Farmington Road (Route 11) Rochester, NH


В	2/23/2021	Amended Site Plan Review Submission
Α	11/25/2019	Site Plan Review Submission
MARK	DATE	DESCRIPTION
PROJE	CT NO:	W5008-004
DATE:		11/25/2019
FILE:	W5	008-004_DTLS.DWG
DRAWI	N BY:	CML
CHECK	ED:	PMC
ADDDO	VED:	DIM


EROSION CONTROL, NOTES & DETAILS SHEET


SCALE:

C-501

AS SHOWN







IOTES:

ALL LIGHT POLES, LUMINAIRES, AND WIRE TO BE FURNISHED AND INSTALLED BY THE POWER COMPANY. UNLESS OTHERWISE DIRECTED.

ANCHOR BOLTS, GROUND ROD & GROUND WIRE TO BE FURNISHED BY THE POWER COMPANY AND INSTALLED BY THE CONTRACTOR, UNLESS OTHERWISE DIRECTED.

BOLT CIRCLE DIAMETER SHALL BE VERIFIED WITH THE POWER COMPANY.

ALL BASES SHALL BE LOCATED 110-0" (TO CENTRE) RFOM FACE OF CURB OR EDGE OF PAVED SHOULDER, UNLESS OTHERWISE MOTED.

REINFORCEMENT SHALL CONFORM TO SECTION 544 OF THE STANDARD SPECIFICATIONS.

ANY ANCHOR BOLTS DAMAGED DURING INSTALLATION SHALL BE REPRIRED OR REPLACED AS DIRECTED BY THE ENGINEER.

UPON INSTALLATION, ANCHOR BOLT THREADS SHALL BE CLEANED WITH A WIRE BRUSH.

TERRAIN SURROUNDING BASE MUST BE GRADED AS SHOWN IN DETAIL "A" TO PREVENT IMPACTING VEHICLES FORM SNAGGING ON BASE.

-14"x14"x5" CONCRETE PAD

-- 18"x 18" x 5" CONCRETE PAG

-C.T. FRAME & COVER CAMPBELL

APPROVED EQUAL

LIGHT POLE BASE

CLEAN-OUT

NO SCALE

48" BOLT MOUNTED FIBERGLASS VALVE BOX WATER MAIN CRUSHED STONE 6" MIN. (SEE DETAIL) NOTE:

1. HYDRANT INSTALLATION AND OPERATION, MANUFACTURE AND MODEL, AND STANDARD DIMENSIONAL REQUIREMENTS SHALL BE IN ACCORDANCE WITH THE CITY OF ROCHESTER WATER DEPARTMENT AND THE CITY OF ROCHESTER FIRE DEPARTMENT -18" X 18" X 6" CONCRETE FIRE HYDRANT NO SCALE

1/4" GALVANIZED STEEL COVER SMOOTH OR SAFETY TREAD #4 REINF, BARS 2'-0" LONG TOP AND BOTTOM (TV) 4 CORNERS #4X42" REINF. BARS ON 6" CENTERS BENT AS SHOWN PLACED ALL THE WAY AROUND BOX FINISH GRADE

IOTES:
SET CONCRETE BOX PAD ON SUITABLE GRAVEL BASE AND PROVIDE ADEQUATE DRAINAGE AWAY
FROM PAD. REINFORCE AS SHOWN. LOCATION TO BE ACCESSIBLE BY TRUCK AND SUITABLY
PROTECTED FROM PLOW AND TRAFFIC DAMAGE.
"FRONT" DENOTES THE SIDE ON WHICH THE ACCESS DOORS ARE LOCATED. THE PAD MUST BE
INSTALLED SO THAT THE FRONT IS READILY ACCESSIBLE.
PROVIDE 8" X 12" CABLE HOLES- ONE PER WALL OR MORE IF NEEDED. LINE UP WITH TRENCHES.
HOLES MAY EXTEND TO BOTTOM OF WALLS.
PROVIDE REMOVABLE STEEL COVER, SET FLUSH WITH TOP OF CONCRETE- WITH MINIMUM OF 2"
BEARING ON REAR EDGE AND ENDS.
INSTALL GROUND ROD 6" IN FRONT OF LEFT FRONT CORNER OF PAD. TOP OF GROUND ROD TO BE 6"
BELOW FINAL GRADE.
COORDINATE AND VERIFY ALL INFORMATION WITH THE LOCAL ELECTRICAL POWER UTILITY
COMPANY.

SEE TYPICAL CROSS SECTIONS (SHEET

-BASE -SUBBASE

- 1-1/2" STREET LIGHTING CONDUIT -1-1" STREET LIGHTING CONDUIT

-2 - 3" CABLE CONDUITS

KVA	KV	Α	В	С	D	STEEL COVER
750-2500	15	9'-0"	5'-8"	1'-6"	12"	24"X24"X1/4"
150-2500	35	9'-0"	5'-8"	1'-6"	12"	24"X24"X1/4"
75-500	15	7'-0"	4'-0"	1'-6"	0'-8"	16"X24"X1/4"
75-150	35	7'-0"	4'-0"	1'-6"	0'-8"	16"X24"X1/4"

SEE TYPICAL CROSS SECTIONS (SHEET R-4)

AASHTO #67 STONE (#4 to 3/4") SIEVE SIZE % PASSING

-FINISH GRADE

REFER TO PAVEMENT SECTION AND

UTILITY TRENCH DETAILS FOR BACKFILL SPECIFICATIONS

-8" PVC SEWER

INSTALLATION SHALL MEET THE STANDARDS OF THE CITY OF ROCHESTER.

SEWER INSULATION DETAIL

2" RIGID INSULATION

PRECAST CONCRETE TRANSFORMER PAD

GRANULAR FILL

00

00

3" (MIN.) Q Q

6 - 5" ELECTRICAL

CONDUITS

UNDISTURBED SOIL-

0 0

PQ

2" MIN. 3" MIN. SAND BEDDING (SEE NOTE 8)

NOTE:

1. NUMBER, MATERIAL, AND SIZE OF UTILITY CONDUITS TO BE DETERMINED BY LOCAL UTILITY OR AS SHOWN ON ELECTRICAL DRAWINGS.

CONTRACTOR TO PROVIDE ONE SPARE CONDUIT FOR EACH UTILITY TO BUILDING.

2. DIMENSIONS SHOWN REPRESENT OWNERS MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS MAY BE GREATER BASED ON UTILITY COMPANY STANDARDS, BUT SHALL NOT BE LESS THAN THOSE SHOWN.

3. NO CONDUIT RUN SHALL EXCEED 360 DEGREES IN TOTAL BENDS.

4. A SUITABLE PULLING STRING, CAPABLE OF 200 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE UTILITY COMPANY IS NOTIFIED TO INSTALL CABLE. THE STRING SHOULD BE BLOWN INTO THE CONDUIT AFTER THE RUN IS ASSEMBLED TO AVOID BONDING THE STRING TO THE

CONDUIT.

SUBJECT ON A STATE OF THE OPPORTUNITY TO INSPECT THE CONDUIT PRIOR TO BACKFILL. THE CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS SHOULD THE UTILITY COMPANY BE UNABLE TO INSTALL ITS CABLE IN A SUITABLE MANNER.

6. ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND, WHERE APPLICABLE, THE NATIONAL ELECTRIC CODE.

7. ALL 90° SWEEPS WILL BE MADE USING RIGID GALVANIZED STEEL. SWEEPS WITH A 36 TO 48 INCH RADIUS.

8. SAND BEDIONING TO BE REPLACED WITH CONCRETE ENCASEMENT WHERE COVER IS LESS THAN 3 FEET, WHEN LOCATED BELOW PAVEMENT, OR WHERE SHOWN ON THE UTILITIES PLAN.

ELECTRICAL AND COMMUNICATION CONDUIT NO SCALE

Tighe&Bond

Proposed Ridgeside Development

Farmington Associates, LLC

60 Farmington Road (Route 11) Rochester, NH

В	2/23/2021	Amended Site Plan Review Submission
Α	11/25/2019	Site Plan Review Submission
MARK	DATE	DESCRIPTION
PROJE	CT NO:	W5008-004
DATE:		11/25/2019
FILE:	WS	5008-004_DTLS.DWG
DRAW	N BY:	CML
CHECK	ED:	PMC

DETAILS SHEET

SCALE: AS SHOWN

C-505

-RUBBER-LIKE GASKET ROLLS OUT OF RECESS INSIDE FACE OF - APPROVED PREFORMED BITUMASTIC SEALANT (SEE NOTE 3) FILL W/MORTAR PIPE POLYTITE (OR BITUMASTIC O-RIN (OR EQUAL) KOR-N-SEAL JOINT SLEEVE OR EQUAL HORIZONTAL JOINTS PIPE TO MANHOLE JOINTS

NOTES:
1. HORIZONTAL JOINTS BETWEEN THE SECTIONS OF PRECAST CONCRETE BARRELS SHALL BE PER CITY OF

MANHOLE JOINTS

1. HORIZONTAL JOINTS BETWEEN THE SECTIONS OF PRECAST CONCRETE BARRELS SHALL BE PER CITY OF ROCHESTER DPW STANDARD AND SHALL BE SEALED FOR WATERTIGHTNESS USING A DOUBLE ROW LEASTOMERIC OR MASTIC-LIKE GASKET.

2. PIPE TO MANHOLE JOINTS SHALL BE PER CITY OF ROCHESTER STANDARD.


3. FOR BITUMASTIC TYPE JOINTS THE AMOUNT OF SEALANT SHALL BE SUFFICIENT TO FILL AT LEAST 75% OF THE JOINT CAVITY.

4. ALL GASKETS, SEALANTS, MORTAR, ETC. SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' WRITTEN INSTRUCTIONS.

GRANULAR FILL AREA AREA DETAIL -2" MIN. CLOSED CELL PIPE INSULATION WHERE CALLED FOR ON PLANS AASHTO #67 STONE (#4 to 3/4") SIEVE SIZE % PASSING 1" 100 (0) -SPRING LINE BEDDING AND BACKELL 3'-O" MIN OR DA

(WHICHEVER IS GREATER) IOTE: . SAND BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK UP TO 12" ABOVE TOP OF PIPE. ALL UTILITIES SHALL BE INSTALLED PER THE INDIVIDUAL UTILITY COMPANY STANDARDS. COORDINATE ALL INSTALLATIONS WITH INDIVIDUAL UTILITY COMPANIES AND THE CITY OF ROCHESTER.

WATER TRENCH




NOTES: (WHICHEVER IS GREATER)

1. 3/4" CRUSHED STONE BEDDING AND BACKFILL MATERIAL FOR FULL WIDTH OF THE TRENCH FROM MINIMUM 6" BELOW PIPE IN ARRIT AND 12" BELOW PIPE IN ROCK UP TO MINIMUM OF 6" OVER THE TOP OF THE PIPE.

2. SANITARY SEWER SHALL BE INSTALLED PER THE CITY DEPARTMENT OF PUBLIC WORKS STANDARDS. COORDINATE ALL INSTALLATIONS WITH THE CITY OF ROCHESTER.


TYPICAL SEWER TRENCH



1. CRUSHED STONE BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK UP TO 6" ABOVE TOP OF PIPE.

2. ALL UTILITIES SHALL BE INSTALLED PER THE INDIVIDUAL UTILITY COMPANY STANDARDS. COORDINATE ALL INSTALLATIONS WITH INDIVIDUAL UTILITY COMPANIES AND THE CITY OF ROCHESTER.

STORM DRAIN TRENCH



WATER LINE 10'-0" MIN

OTES:

INVERT AND SHELF TO BE PLACED AFTER EACH LEAKAGE TEST.

CARE SHALL BE TAKEN TO INSURE THAT THE BRICK INVERT IS A SMOOTH CONTINUATION OF THE SEWER INVERT.

INVERT BRICKS SHALL BE LAID ON EDGE.

BITLIMINOUS WATERPROF COATING TO BE APPLIED TO ENTIRE EXTERIOR OF MANHOLE.

FRAMES AND COVERS MANHOLE FRAMES AND COVERS SHALL BE OF HEAVY DUTY DESIGN AND PROVIDE A 30-INCH CLEAR OPENING. A 3-INCH (HISHWIH) HEIGHT) WORD "SEWER" SHALL BE PLAINLY CAST INTO THE CENTER OF EACH COVER.

HORIZONTAL JOINTS SHALL BE SEALED FOR WATER TIGHTNESS USING A DOUBLE ROW OF ELASTOMERIC OR MASTIC-LIKE SEALANT.

BARREL AND COME SECTIONS SHALL BE PRECAST REINFORCED CONCRETE DESIGNED FOR H20 LOADING, AND CONFORMING TO ASTM C478-06.

RIP-RAP-


--- MIRAFI FW-700

OTES:
STONE SIZE AND MAT DIMENSIONS DETAILED ON PLANS,
STONE SHALL CONSIST OF SUB-ANGULAR FIELD STONE OR ROUGH UNHEWN QUARRY STONE
OF APPROXIMATELY RECTANGULAR SHAPE. FLAT OR ROUND ROCKS ARE NOT ACCEPTABLE.
THE STONE SHALL BE HADD AND OF SUCH QUALITY THAT IT WILL NOT DISINTEGRATE ON
EXPOSURE TO WATER OR WEATHERING, BE CHEMICALLY STABLE AND IT SHALL BE SUITABLE
IN ALL OTHER RESPECTS FOR THE PURPOSE INTENDED. THE BULK SPECIFIC GRAVITY
(SATURATED SURFACE-DRY BASIS) OF THE INDIVIDUAL STONES SHALL BE AT LEAST 2.5.
THE STONE SHALL BE COMPOSED OF A WELL-GRADED MIXTURE DOWN TO THE ONE-INCH
SIZE PARTICLE SUCH THAT 50 PERCENT OF THE MIXTURE BY WEIGHT SHALL BE LARGER THAN
THE DOS DISCES SPECIFIED. A WELL-GRADED MIXTURE IS DEFINED AS A MIXTURE COMPOSED
PRIMARILY OF THE LARGER STONE SIZE BUT WITH A SUFFICIENT MIXTURE OF OTHER SIZES
TO FILL THE PROGRESSIVELY SMALLER VOIDS BETWEEN THE STONES. THE DIAMETER OF THE
LARGEST STONE SIZE IN SUCH A MIXTURE SHALL BE 1.5 TIMES THE DSO SIZE.

RIP-RAP APRON DETAIL

SEWER MANHOLE NO SCALE

SECTION



NOTES:

1. A 10 FOOT MINIMUM EDGE TO EDGE HORIZONTAL SEPARATION SHALL BE PROVIDED FROM ANY EXISTING OR PROPOSED WATER LINE.

2. AN 18" MINIMUM EDGE TO EDGE VERTICAL SEPARATION SHALL BE PROVIDED, WITH WATER ABOVE SEWER, AT ALL

- AN 16 INITIATION EDGE TO EDGE VERTICAL SEPARATION STALL BE PROVIDED, WITH WATER ABOVE SEWER, IT ALL
 CROSSINGS.

 SEWER PIPE JOINTS SHALL BE LOCATED AT LEAST 6 FEET HORIZONTALLY FROM ANY EXISTING OR PROPOSED WATER MAIN.

 WHERE AN 18" VERTICAL SEPARATION CANNOT BE PROVIDED, SEWER PIPE SHALL BE CONSTRUCTED USING A SDA 26 FVC
 PIPE OR ENCASED CONCRETE FOR A MINIMUM DISTANCE OF 10 FEET ON BOTH SIDES OF THE LINE BEING CROSSED, AS
 SHOWN ABOVE.
- CROSSINGS SHALL CONFORM TO THE CITY OF ROCHESTER STANDARDS AND SPECIFICATIONS.

FOAM GASKET W/ PSA-

ANCHOR W/ BOLT (SEE

1/2 D

GASKET COMPRESSED BETWEEN

HOOD AND STRUCTURE (SEE DETAIL B)

INSTALLATION DETAIL

DETAIL A


WATER & SEWER CROSSING

DETAIL B

WATERTIGHT ACCESS PORT, 6

CONFIGURATION DETAIL


SIDE VIEW



-MOUNTING FLANGE

FRONT VIEW

OIL-WATER-DEBRIS SEPARATOR



NOTES:

1. THE FOUNDATION AREA OF THE WATERWAY SHALL BE CLEARED AND GRUBBED OF ALL TREES, BRUSH, STUMPS, AND OTHER OBJECTIONABLE MATERIAL. MATERIALS REMOVED SHALL BE DISPOSED OF SO THEY WILL NOT INTERFERE WITH THE CONSTRUCTION OR PROPER FUNCTIONING OF THE WATERWAY.

2. THE WATERWAY SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS-SECTION AS REQUIRED TO MEET THE DESIGN CRITERIA. THE WATERWAY SHALL BE FREE OF IRREGULARITIES WHICH WILL IMPEDE NORMAL FLOW.


3. EARTH FILLS REQUIRED TO MEET SUBGRADE REQUIREMENTS BECAUSE OF OVER EXCAVATION OR TOPOGRAPHY SHALL BE COMPACTED TO THE SAME DENSITY AS THE SURROUDING SOIL OF REVENT UNGLAL SETTLEMENT THAT COULD CAUSE DAMAGE TO THE COMPLETED WATERWAY. EARTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE SPREAD OR DISPOSED OF SO IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE WATERWAY.


4. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER AS TO MINIMIZE EROSION AND AIR AND WATER POLLUTION. ALL APPROPRIATE STATE AND LOCAL LAWS AND REGULATIONS SHALL BE COMPLED WITH FOR INSTALLATION.

5. VEGETATION SHALL BE ESTABLISHED IN THE SWALE PRIOR TO ALLOWING STORMWATER RUNOFF TO FLOW THROUGH THE SWALE.

6. MAINTENANCE OF THE VEGETATION IN THE GRASSED WATERWAY IS EXTEMPLEY IMPORTANT IN ORDER TO REVEYEN RULLING, EROSION, AND FALLURE OF THE WATERWAY. MOWING SHOULD BE DONE FREQUENTLY ENDUGLED HOW THE SWALE BY AND WOODLY VEGETATION AND TO KEEP THE GRASSES IN A VIGOROUS CONDITION. THE VEGETATION SHOULD HOT ORDER TO DETERMINE THE FROME STANKES IN THE WATERWAY.

7. THE WATERWAY SHOULD BE DONE PERIODICALLY AND AFTER VEYER WADIOS STORM TO DETERMINE THE CONDITION OF THE WATERWAY. RILLS AND DAMAGED AREAS SHOULD BE PROMETLY REPAIRED AND REVEGETATED AS NECESSARY TO PREVENT FURTHER DETERIORATION.





ALL SECTIONS SHALL BE 4,000 PSI CONCRETE CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQUARE INCHES PER LINEAR FOOT IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL. THE TONGUE AND THE GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12 SQUARE INCHES PER LINEAR FOOT.
THE STRUCTURES SHALL BE DESIGNED FOR H20 LOADING.
CONSTRUCT CRUSHED STONE BEDDING AND BACKFILL UNDER (6" MINIMUM
THICKNESS)
THE TONGUE AND GROOVE JOINT SHALL BE SEALED WITH ONE STRIP OF BUTYL
RUBBER SEALANT.
PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO 7. PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
8. OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3" BEYOND INSIDE WALL OF STRUCTURE.
9. PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4" HIGH AT AN 11s ANGLE CENTERED IN THE WIDTH OF THE WALL AND SHALL BE ASSEMBLED USING AN APPROVED FLEXIBLE SEALANT IN JOINTS.
10. ALL STRUCTURES WITH MULTIPLE PIPES SHALL HAVE A MINIMUM OF 12" OF INSIDE SURFACE BETWEEN HOLES, NO MORE THAN 3"5% OF A HORIZMTAL CROSS SECTION SHALL BE HOLES, AND THERE SHALL BE NO HOLES CLOSER THAN 3" TO JOINTS.

DIAMETER	WALL THICKNESS (MIN.)	FLOOR THICKNESS (MIN.)
4'	5"	6"
5'	6"	8"
6'	7"	8"
8'	9"	10"

	COR	E HOLE SI		
PIPE SIZE	RCP CORE HOLE DIA.		PLASTIC CORE HOLE DIA.	
INCHES	INCHES	FEET	INCHES	FEET
6			7	0.6
12	18	1.5	18	1.5
15	22	1.8	20	1.7
18	26	2.2	24	2.0
24	34	2.8	32	2.7
30	42	3.5	42	3.5
36	48	4.0	48	4.0
42	54	4.5	54	4.5
48	64	5.3	64	5.3
54	72	6.0		
60	78	6.5		

Tighe&Bond

Proposed Ridgeside **Development**


Farmington Associates, LLC

60 Farmington Road (Route 11) Rochester, NH

3	2/23/2021	Amended Site Plan Review Submission	
4	11/25/2019	Site Plan Review Submission	
ARK	DATE	DESCRIPTION	
OJECT NO:		W5008-004	
TE:		11/25/2019	
.E: W5008-004_DTLS.DWG			
AWN BY:		CML	
ECKED:		PMC	
PROVED:		BLM	

DETAILS SHEET SCALE: AS SHOWN

C-506



ate: February 22, 2021 12:07 PM By: CML

