

NONRESIDENTIAL SITE PLAN APPLICATION City of Rochester, New Hampshire



			CONTRACTOR OF THE PROPERTY OF
Date: March 23, 2021			No: <u>×</u> Unclear: oplication as soon as possible.)
Property information			
Tax map #: 205; Lot	#('s): <u>18</u> ;	Zoning district:	Agricultural
Property address/location:			
Name of project (if applicable	le):		
Size of site: 34.53 acres;			
Property owner			
Name (include name of indiv	vidual): Thomas R. & Diann	e C. Aubert	
Mailing address: 5 Gary Drive F	Rochester, NH 03867		
Telephone #: 603-534-5990		_ Email:_Taubert@n	netrocast.net
Applicant/developer (if Name (include name of indiv	vidual): Same as owner		
Mailing address:			
Telephone #:		_ Email:	
Engineer/designer			
Name (include name of indiv	vidual): Kenneth A. Berry		
Mailing address: 335 Second Cro	wn Point Road Barrington, NH (03825	
Telephone #: 603-332-2863			
Email address: k.berry@berrysun	veying.com	Professional	license #: 14243
Proposed activity (check	all that apply)		
New building(s): S	Site development (oth	er structures, pa	rking, utilities, etc.):
Addition(s) onto existing build			
	Page 1 (of 3 p	pages)	

Updated

Describe proposed activity/use: Excavation operation
Describe existing conditions/use (vacant land?): Unvegetated sand pit surrounded by wetlands
Utility information
City water? yes no × ; How far is City water from the site? N/A
City sewer? yes no <u>x</u> ; How far is City sewer from the site? N/A
If City water, what are the estimated total daily needs? N/A gallons per day
If City water, is it proposed for anything other than domestic purposes? yes no _N/A
If City sewer, do you plan to discharge anything other than domestic waste? yes no $\frac{N/A}{A}$
Where will stormwater be discharged? N/A
Building information Type of building(s): N/A
Building height: N/A Finished floor elevation: N/A
Parking spaces: existing: total proposed: N/A; Are there pertinent covenants? N/A

Proposed post-development disposition of site (should total 100%)					
Square footage % overall si					
Building footprint(s) – give for each building	0				
Parking and vehicle circulation	0				
Planted/landscaped areas (excluding drainage)	0				
Natural/undisturbed areas (excluding wetlands)	275,735	18.3			
Wetlands	1,145,733	76.2			
Other – drainage structures, outside storage, etc.	82,500	5.5			

Updated

Page 2 (of 3 pages)

Comments	
Please feel free to add any comments, additional	I information, or requests for waivers here:
Submission of application	
This application must be signed by the property opposite property owner), and/or the agent.	owner, applicant/developer (if different from
I(we) hereby submit this Site Plan application to t	the City of Rochester Planning Board
pursuant to the <u>City of Rochester Site Plan Regu</u>	lations and attest that to the best of my
knowledge all of the information on this application	on form and in the accompanying application
materials and documentation is true and accurate	e. As applicant/developer (if different from
property owner)/as agent, I attest that am duly a	authorized to act in this capacity.
Signature of property owner:	
	Date: 3-23-2
Signature of applicant/developer:	
Signature of agent:	Date:
	Date: 3-23-21
Authorization to enter subject property	
hereby authorize members of the Rochester Plan	nning Board. Zoning Board of Adjustment
conservation Commission, Planning Department,	and other pertinent City departments
oards and agencies to enter my property for the	purpose of evaluating this application
ncluding performing any appropriate inspections of	during the application phase, review phase,
ost-approval phase, construction phase, and occ pecifically to those particular individuals legitimat	cupancy phase. This authorization applies
respecting this specific application/project. It is und	derstood that these individuals must use all
easonable care, courtesy, and diligence when en	tering the property.
ignature of property owner:	
	Date: 3 · 23 - 2
och-fileshare\plan\$\Forms\Applications\Site Plan - Nonresidential.doc 27/2019	Updated



BERRY SURVEYING & ENGINEERING

335 Second Crown Point Road
Barrington, NH 03825
Phone: (603) 332-2863
Fax: (603) 335-4623
www.BerrySurveying.Com
crberry@metrocast.net

March 23, 2021

City of Rochester Planning Board Attention: Chief Planner, Seth Creighton 33 Wakefield Street Rochester, NH 03867

Re

Site Plan/Excavation 36 Cross Road Rochester, NH 03867 Tax Map 205, Lot 18

Mr. Creighton,

On behalf of our clients, Thomas & Dianne Aubert, Berry Surveying & Engineering (BS&E) is submitting for TRG, to discuss a proposed site plan.

Background and General Narrative:

Thomas & Dianne Aubert own the parcel known as 36 Cross Road in Rochester, NH (Tax Map 216, Lot 29). Berry Surveying & Engineering has conducted an on-site survey of the parcel which includes a topographic analysis as well as a wetlands analysis. Wetlands were found along the existing stream and pond. The parcel is vacant with an existing traveled way for access. The subject parcel has been used in previous years as a gravel pit.

The Proposal:

The applicant is proposing to excavate earthen material from the existing gravel pit area. No disturbance is proposed within the wetland buffer. As part of the excavation, proper erosion and sediment control measures will be installed to ensure that all sediment is contained within the construction area.

In addition to site plan approval, the applicant is requesting a special exception to allow for the excavation use within the agricultural zone. A separate application will be submitted to the zoning board of adjustment.

Respectfully submitted,

BERRY SURVEYING & ENGINEERING

Kevin Poulin
Project Engineer

Christopher R. Berry, SIT Principal, President



BERRY SURVEYING & ENGINEERING

335 Second Crown Point Road Barrington, NH 03825 Phone: (603) 332-2863 Fax: (603) 335-4623 www.BerrySurveying.Com

March 23, 2021

City of Rochester Planning & Development Department Attention: Seth Creighton

33 Wakefield Street Rochester, NH 03867

Trip Generation Summary
Thomas & Dianne Aubert
36 Cross Road Rochester, NH 03868
Tax Map 205, Lot 18

Mr. Creighton,

Pursuant to the City of Rochester Land Site Review Regulations, Berry Surveying & Engineering (BS&E), on behalf of Thomas & Dianne Aubert, has prepared a Trip Generation Summary for the excavation operation at 36 Cross Road. This estimate assumes a full operation for the duration of the project, when in reality it will be operated more sporadically. The following assumptions have been made for peak hour traffic generation during the AM peak hour of 7-9AM and PM peak hour of 4PM to 6 PM:

- Two dump trucks will be operating between the excavation operation and 828 Portland Street (Carole Court).
- According to Google Maps, it is approximately 3.3 miles or 9-10 minutes from 36 Cross Road to 828 Portland Street.
- It is assumed that a dump truck will take 5 minutes to load and unload, making a dump truck cycle approximately 20 minutes long. A dump truck will be able to make 3 cycles per hour.
- During the AM and PM peak hour, two dump trucks will make a combined 6 trips per hour, plus the excavator operator arriving in the AM and departing during the PM.
- This results in the excavation operation generating 7 trips during the AM peak hour and 7 trips during the PM peak hour.
- It is recommended that the existing and surrounding infrastructure will be sufficient to handle the minimal temporary increase in vehicle trips and peak hour and all other hours for Cross Road.


Respectfully Submitted,


BERRY SURVEYING & ENGINEERING

Christopher R. Berry, SIT Principal, President


Kenneth A. Berry, PE, LLS, CPSWQ, CPESC, CESSWI


Principal, VP-Technical Operations





SHEET 1 OF 6





PLAN AUBER EXCAVATION GRADING P
LAND OF
HOMAS R. & DANNE C. A
35 CROSS ROAD
ROCHESTER, N.H.
TAX MAP 205, LOT 1





NOTES:

1.) OWNER: THOMAS R. & DIANNE C. AUBERT 5 GARY DRIVE

- 2.) TAX MAP 205, LOT 18
- 3.) EXISTING LOT AREA: 1,503,971 Sq.Ft., 34.53 Ac.
- 4.) S.C.R.D. BOOK 3677, PAGE 404
- 5.) THE INTENT OF THIS PLAN IS TO SHOW THE EROSION & SEDIMENT CONTROL MEASURES FOR THE EXCAVATION OPERATION LOCATED AT TAX MAP 205, LOT 18.
- 6.) UPON FINAL COMPLETION AND 85% STABILIZATION, THE DRAINAGE SYSTEM IS TO BE CLEANED OF ALL DEBRIS. SEDIMENT CONTROL PRACTICES REMOVED AND DISPOSED OF PROPERLY, AND ANNUAL MAINTENANCE PREFORMED ON ALL DRAINAGE PRACTICES.
- 7.) EROSION AND SEDIMENT CONTROL INSPECTIONS TO BE CONDUCTED ONCE PER EVERY SEVEN DAYS AND AT AN INCREASED FREQUENCY INCLUDING WITHIN 24-HOURS OF A 0.25 INCH RAIN EVENT. INSPECTIONS TO BE CONDUCTED BY A "QUALIFIED PERSON" AS DEFINED BY EPA CGP 4.1.1 AND INSPECTION REPORTS SUBMITTED TO THE CITY OF DOVER, NH, ENGINEERING DEPARTMENT WITHIN 24 HOURS IN ACCORDANCE WITH CGP 4.1.7 AND MAINTAINED BY THE OWNER FOR A PERIOD OF THREE YEARS AFTER THE PROJECT IS COMPLETED. SEE ALSO CITY OF ROCHESTER ADDITIONAL INSPECTION REQUIREMENTS BELOW.
- 8.) SILT FENCE MAY BE SUBSTITUTED WITH FILTREXX SILT SOXX OR EROSION CONTROL MIX BERM, SILT FENCE IS NOT A SUBSTITUTE
- 9.) PER EPA CGP Z.1.2.2 (INSTALL PERIMETER CONTROL), "YOU MUST INSTALL SEDIMENT CONTROLS ALONG THOSE PERIMETER AREAS OF YOUR SITE THAT WILL RECEIVE STORMWATER FROM EARTH DISTURBING ACTIVITIES." AS A RESULT OF SWEPP INSPECTIONS, THE CONTRACTOR MAY HAVE TO EXPAND PERIMETER CONTROLS TO MEET THIS REQUIREMENT IN EASE PLAN IS INITIAL QUIDANCE AS TO THE ANTICIPATED REQUIREMENTS AND IT THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT STORMWATER VIOLATION DO NOT
- 10.) CITY OF ROCHESTER: IN ACCORDANCE WITH STORMWATER REGULATIONS THE FOLLOWING STORMWATER MEASURES ARE REQUIRED.
 - A.) ALL PROPOSED BMPs WILL CONFORM TO THE NH STORMWATER MANUAL VOLUME 3.
 - B. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SOIL LAND DISTURBANCE AND MUST BE REVIEWED AND APPROVED BY COMMUNITY SERVICE.

 C.) TEMPORARY STABILIZATION MEASURES SHOULD BE IN PLACE WITHIN SEVEN CALENDAR DAYS FOR EXPOSED SOILS
 - C.) TEMPORARY STABILIZATION MEASURES SHOULD BE IN PLACE WITHIN SEVEN CALENDAR DAYS FOR EXPOSED SOILS
 AREAS THAT ARE WITHIN ONE HUNDRED FEET OF A SUFFACE WATER BODY OR A WETLAND AND MORE THAN 14 CALENDAR
 DAYS FOR ALL OTHER AREAS. PERMANENT STABILIZATION SHOULD BE IN PLACE WITHIN THREE CALENDAR DAYS FOLLOWING
 COMPLETION OF FINAL GRADING OF EXPOSED SOIL AREAS.

 D.) ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED IN FUNCTIONING CONDITION UNTIL
 - FINAL STABILIZATION IS ACCOMPLISHED.
 - DEPARTMENT OF PUBLIC WORKS OR THEIR DESIGNATED AGENT SHALL HAVE ACCESS TO THE SITE TO COMPLETE ROUTINE INSPECTIONS AND SHALL BE NOTIFIED 24—HOURS PRIOR TO INSTALLATION OF A STORWWATER BMP IN ORDER TO SCHEDULE AN INSPECTION, DURING NORMAL WORKING HOURS.
 - SCHEDULE AN INSPECTION, DURING NORMAL WORKING HOURS.

 F) THE PLANNING BOARD OR DPW MAY REQUIRE THE DESIGN ENGINEER AND/OR AN INDEPENDENT, THIRD—PARTY INSPECTION AND OVERSIGHT OF THE CONSTRUCTION OF STORMWATER MANAGEMENT FACILITIES AND EROSION AND SEDIMENT CONTROL AT THEIR DISCRETION. THE OWNER / APPLICANT IS RESPONSIBLE FOR ALL FEES ASSOCIATED WITH INSPECTIONS.

 G.) ALL SWPPP INSPECTIONS MUST BE CONDUCTED BY A QUALIFIED PROFESSIONAL SUCH AS A PROFESSIONAL ENGINEER
 - PE). A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC). A CERTIFIED EROSION SEDIMENT AND STORMWATER INSPECTOR (CESSWI), OR A CERTIFIED PROFESSIONAL IN STORMWATER QUALITY (CPSWQ). INSPECTION REPORTS WILL BE SUBMITTED TO THE DPW ENGINEERING DEPARTMENT.
- 11.) CONTRACTOR IS REQUIRED TO UTILIZE A CONSTRUCTION ENTRANCE.
- 12.) CONTRACTOR IS RESPONSIBLE FOR CLEANING AND MAINTAINING THE PERIMETER PROTECTION ONCE INSTALLED.
- 13.) FUGITIVE DUST IS TO BE CONTROLLED THROUGHOUT THE CONSTRUCTION PROCESS IN ACCORDANCE WITH ENV-A 1DOD.
- 14.) CONTRACTOR IT TO MEET THE REQUIREMENTS SPECIFIED IN RSA 430:51-57 AND AGR 3800, RELATING TO INVASIVE SPECIES.
- 15.) CONTRACTOR IS RESPONSIBLE FOR PROTECTING THE WATER QUALITY FROM ANY RUN OFF DURING THE CONSTRUCTION PROCESS, IN ACCORDANCE WITH ENV-WQ 1507, IN ORDER TO PREVENT VIOLATIONS OF THE STORM WATER QUALITY STANDARDS.


HaB HINKLEY SILT LOAM K = 0.17

SEE WEBSOIL USDA-NRCS ERODIBILITY FACTOR - K, CPESC MANUAL, ENVIROCERT INTERNATIONAL INC., STATE OF NY EROSION & SEDIMENT CONTROL MANUAL, AND ROCKINGHAM COUNTRY SOIL SURVEY, ROCKWEB SOIL ATTRIBUTES.

CONTRACTOR TO BE AWARE OF THE SOIL PROFILES AND ENSURE THAT PROPER EROSION PREVENTION AND SEDIMENT CONTROL MEASURES ARE TAKEN AT ALL TIMES. ANY DEWATERING REQUIREMENTS IN NEW HAMPSHIRE REQUIRE SPECIAL PROVISIONS IN ACCORDANCE WITH THE "CLARIFICATION OF SECTION 9.12. (STATE OF NEW HAMPSHIRE CONDITIONS) AND OTHER NI SPECIFIC INFORMATION FOR THE U.S. EPA 2012 NPDES CONSTRUCTION GENERAL PERMIT (CGP)" DATED MAY 3, 2012 INCLUDED IN THE SWPPP.

COVER MANAGEMENT DURING CONSTRUCTION FOR EXPOSED SOIL WILL INCLUDE HAY / STRAW APPLIED AT A RATE OF 2.0 TONS PER ACRE, TEMPORARY SEEDING OF ANNUAL RYE GRASS, AND PERMANENT SEEDING AT THE EARLIES OPPORTUNITY. SEE ADDITIONAL REQUIREMENT FOR STABILIZATION ON THE EROSION AND SEDIMENT CONTROL DETAIL. SHEETS, E-10 ND E-102.

THE CONSTRUCTION SCHEDULE WILL BE MANAGED SO THAT ALL STORMWATER STRUCTURES WILL BE BUILT AND STABILIZED PRIOR TO RECEIVING SURFACE WATER RUNOFF. CONTRACTOR TO BE RESPONSIBLE FOR ALL DIVERSIONS DURING CONSTRUCTION AND FOR INTERIM SCIMENT AND ERSOING CONTROL MEASURES.




(IN FEET) 1 inch = 40 ft

O OF ROAD ROAD LOT LAND OF MAS R. & DIANNE 36 CROSS R(ROCHESTER, TAX MAP 205, THOMAS

SN SN H 335 BARRING \mathbf{m}

KENNETH CONSID




- AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24 AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8" THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A MAXIMUM 6' APART, AND DRIVEN A MINIMUM OF 16" INTO THE
- WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE
- WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM EY-PASSING, MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF. SEE MAINTENANCE NOTE BELOW, REMOVAL OF SEDIMENT REQUIRED AT A DEPTH OF 6-INCHES. PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE FOR SEDIMENT STORAGE. SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE ADSTORAGED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED. TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, SILT FENCE, PAGE 90.

- SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL, ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE
- IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING
- THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.
 SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH SIX-INCHES IN DEPTH.
 SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND

SILT FENCE DETAIL





STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, O


- STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.

 THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH BERM IS INSTALLED AT THE ENTRANCE OF THE PROJECT STIE.

 THE HICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES.

 THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INCRESS OR CORRESS OCCURS OR 10 FEET, WHICH EVER SHEETER TO PLACING OCTEXILE THE COLOT SHALL BY THE SHALL BY PLACED OVER THE CONSTRUCTION ENTRANCE OF THE SHALL BY PLACED OVER THE CONSTRUCTION ENTRANCE ALMA USE AND SHALL BY PLACED OVER THE PROJECT OF THE PROJECT OF THE SHALL BY PLACED OVER THE SHAL

TO TRAP SEDIMENT, ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC OF-WAY MUST BE REMOVED PROMPTLY. CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY RUCTION EXIT, PAGE 124.



- THE MANAMENT OF THE PLANS.
 CHECK DAMS WILL NOT BE USED IN A FLOWING STREAM.
 TEMPORARY CHECK DAMS WILL BE REMOVED ONCE THE
 SWALE OR DITCH IS DETERMINED STABLE.
 TO BE CONSTRUCTED IAW NH SWM § 3 4-2 SEDIMENT
 CONTROL PRACTICES, TEMPORARY CHECK DAMS, PAGE 114.

FLOW_ STONE GRADE STABILIZATION STRUCTURE

E2 CATCH BASIN OR DET. POND STONE TO ALLOW-Вистонононом 3.0' COMMENDED RIP RAP GRADATION RANGES STABLE OUTLET MEADOW BUFFER 0.5 FEET 6 INCHES SIZE OF STONE (INCHES) % OF WEIGHT SMALLER THAN THE GIVEN d50 SIZE


- 1 CONSTRUCT THE LEVEL SPREADER LIP ON A 0% GRADE TO INSURE UNIFORM SPREADING OF RUNOFF
- 2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON FILL.
- 3. THE ENTIRE LEVEL LIP AREA SHALL BE PROTECTED BY PLACING EXCELSIOR ENFORCER MATTING BENEATH THE STONE. EACH STRIP SHALL OVERLAP BY AT LEAST SIX INCHES.
- 4. THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- 5. MAINTENANCE: THE LEVEL SPREADER SHOULD BE CHECKED PERIODICALLY AND AFTER EVERY MAJOR STORM TO DETERMINE IF THE LIP HAS BEEN DAMAGED AND THE DESIGN CONDITIONS HAVE NOT CHANGED. ANY DETRINENTAL SEDIMENT ACCUMULATION SHOULD BE REMOVED. IF STONE REMOVAL HAS TAKEN PLACE ON THE LIP, THEN THE DAMAGE SHOULD BE REPAIRED.
- 6 REFERENCE IS MADE TO NHDES SWM VOL. 2, 4-6, STONE BERM LEVEL SPREADERS, PAGE 162

EROSION CONTROL MIX

1'-0" MIN.

STONE BERM LEVEL SPREADER

E3



GRASS CONVEYANCE SWALE NOT TO SCALE

TO BE USED IN ALL AREAS WHERE THERE WILL BE NO TRAFFIC.

INSPECT ANNUALLY FOR EROSION, SEDIMENT ACCUMULATIONS, VEGETATION LOSS, & INVASIVE SPECIES. REPAIR AS NECESSARY.

MOW GRASS ANNUALLY TO A DEPTH OF 4".

RUNOFF WATER WITH SEDIMENT

MAINTENANCE

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS MADE AS NECESSARY. SEDIMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDIMENT HAS REACHED A MAXIMUM OF ONE HALF THE DEPTH OF THE TRAP. THE SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURE OR VEGETATIVE MEANS. THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE CONTRIBUTING DRAINAGE AREA TO THE INLET HAS BEEN COMPLETELY

BLOCK & GRAVEL DROP INLET SEDIMENT FILTER

NOT TO SCALE

INSTALL STABILIZATION MATTING DURING CONSTRUCATION

TO BE CONSTRUCTED IAW NH SWM #2 CHAPTER 4, #5 TREATMENT SWALES, PAGE 123.

CONSTRUCTION SAFETY FENCE NOT TO SCALE

LEGEND 48" ORANGE FENCE, 12 FEET O.C 48" ORANGE FENCE, 11 FEET O.C SAF6 48" ORANGE FENCE, 6 FEET O.C. 48" HIGH DENSITY ORANGE POLYETHELENE SAFETY FEN WIRE OR ZIP TIES TO SEI SAFETY FENCE TO POST

. ALL SENSITIVE AREAS SHALL BE PROTECTED AS PER PLAN.

ALL TREES IN THE CONSTRUCTION AREA AND SPECIFICALLY DESIGNATED FOR REMOVAL SHALL BE

SHEEN FRANCHER SHALL HOW YESBURY 3 FEED UTSEE OF THE ORDE UNE OF THE TREE.

SAFETY FENCE SHOULD BE FASTINED SECURELY TO THE T-POSTS.

TO THE FENCE MAST TRANS IN A FACE DURING MAST PAYSES OF CONSTRUCTION; ANY CHANGE OF THE

48" Safety Fence, 72" T-Posts

E8

TEMPORARY EROSION CONTROL MEASURES

1. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME.

EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER.

ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS, DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN ONE POUND OF SEED PER 50 SQUARE YARDS OF AREA. (SEE SEED SPECIFICATIONS THIS SHEED

ALL DISTURBED AREAS WILL BE RESTABILIZED WITHIN 45 DAYS. AT ANY ONE TIME, NO MORE THAN 5 ACRES, (217,800 Sq. $\rm Ft.$) WILL BE DISTURBED.

SILT FENCES AND PERIMETER BARRIERS SHALL BE INSPECTED PERIODICALLY AND AFTER EVERY RAIN DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND LISPOSED OF.

. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VECETATED.

PER THE EPA CGP REQUIREMENTS THERE WILL BE REPORTS OF THE EROSION CONTROL INSPECTIONS IAW SWPPP PREPARED BY BS&E. ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.25° DR GREATER RAIN EVENT.

B. DITCHES, SWALES, AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.

DO NOT TRAFFIC EXPOSED SOIL SURFACES WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION SYSTEM.

O. ROADWAYS, DRIVEWAYS AND CUT AND FILL SLOPES MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINAL GRADE.

11. STABILIZATION MEANS:

LIFTING STRAPS

GRATE

iiiiiiiiii

E11

A MINIMUM OF 85% OF VEGETATIVE COVER HAS BEEN ESTABLISHED.
 A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED, OR
 EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.

12. THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

13. THE NHDES STORMWATER MANUAL, IN THREE VOLUMES, DATED DECEMBER 2008, IS A PART OF THIS PLAN SET AND THE MORE RESTRICTIVE WILL GOVERN. (NH SWM)

DET T CONTROL OF NNE C. AUBE S ROAD ER, N.H. A & SEDIMENT C LAND OF MAS R. & DIANNE 36 CROSS RC ROCHESTER, I TAX MAP 205,

RING ROAD 332-28

-TO BE USED IN ALL AREAS WHERE THERE WILL BE TRAFFIC.

- ARE SUBJECT TO DAMAGE BY SNOW PLOWS, AND MUST BE INSPECTED AFTER ANY SNOW EVENT AND REPLACED AS REQUIRED.

-THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF CORD IS COVERED WITH SEDIMENT, THE SILTSACK SHOULD BE EMPTIED.

TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.

RECOMMENDED MAINTENANCE SCHEDULE

-EACH SILTSACK SHOULD BE INSPECTED AFTER EVERY
MAJOR RAIN EVENT, AND MUST BE MAINTAINED. ND (NH AS N -IF THERE HAVE BEEN NO MAJOR EVENTS, SILTSACK SHOULD BE INSPECTED EVERY 2-3 WEEKS. 335 BARRING m OF NEW HAMA KENNETH

SILTSACK DETAIL

E - 101

JRVEYING ENGINEE SROWN POINT 03825 (603

SHEET 5 OF 6



 \underline{PLAN} not to scale

E6

GRADE

CONSTRUCT AT

ANGLE OF REPOSE

ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
FILTER MEDIA FILL TO MEET APPLICATION REQUIRMENTS.
COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.
SILTSOXX MAY BE USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT
BARRIERS.

NOT TO SCALE 30' 2"X2"X36" WOODEN STAKES PLACED 10' O.C. --- FILTREXX SOXX SILT FENCE-BLOWN /PLACED FILTER MEDIA-AS NOTED) AREA TO BE PROTECTED Marken Ma

35481 Grafton Eastern Rd | Grafton, Oh 44044 440–926–2607 | fax: 440–926–4021 WW.FILTREXX.COM OR APPROVED EQUAL

 $\underline{SECTION}$ NOT TO SCALE

2"X2"X36" WOODEN STAKES PLACED 10' 0.0 (SEE SECTION) E10

EROSION CONTROL MIX BERM

NOT TO SCALE

2'-0" MIN

ION CONTROL MIX BERMS SHALL BE USED ONLY AS FOLLOWS: BERMS SHALL BE USED IN AREAS WHERE EROSION WILL OCCUR ONLY IN THE FORM OF SHEET EROSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY

THE BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSLY AS POSSIBLE.

THE BERMS SHALL BE INSTALLED ON SLOPES LESS THAN 5%.

SUBJECT TO (E), BELOW, THE MIX SHALL HAVE AN ORGANIC PORTION BETWEEN 80 AND 100%, DRY WEIGHT BASIS, AND BE FIBROUS AND BLONGATED SUCH AS FROM SHREDDED BARK, STUMP GRINDINGS, COMPOSED BARK, OR EQUIVALENT MANUFACTURED PRODUCTS.

WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS SHALL NOT BE USED AS ORGANIC MATERIAL.

THE MIX SHALL NOT CONTAIN SILTS, CLAY, OR FINE SANDS.

THE MIX SHALL HAVE A PARTICLE SIZE BY WEIGHT OF 70 TO 85% PASSING A 6-INCH SCREEN.

THE MIX SHALL HAVE A PRETICLE SIZE BY WEIGHT OF 70. TO 85% PASSING A 6-INCH SCREEN AND A MAXIMUM OF 85% PASSING THE 0.75-INCH SCREEN.

THE MIX SHALL BE AT LEAST 12 INCHES HIGH AND AT LEAST 2 FEET WIDE.

TO BE CONSTRUCTED IAW NH SWM §3 4-2 SEDIMENT CONTROL PRACTICES, EROSION CONTROL MIX BERMS, PAGE 106.

ABOVE THE BERM. THE BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSLY AS

BARRIERS.
SILTSOXX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS
NECESSARY TO MEET THE REQUIRMENTS OF THE SPECIFIC APPLICATION.
FILTREXX SOXX IS A REGISTERED TRADEMARK OF FILTREXXIN TERNATIONAL, LLC.
SILT FENCE IS NOT A SUBSTITUTION FOR SILT SOXX AND ANY EQUAL
SUBSTITUTION TO BE APPROVED.
TO BE CONSTRUCTED IAW FILTREXX, SECTION 1:EROSION & SEDIMENT CONTROL
(PAGE 323) — CONSTRUCTION ACTIVITIES, SWPPP CUT SHEET: FILTREXX
SEDIMENT CONTROL

CONTROL

TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.


FILTREXX SEDIMENT


E7

BLOCK AND GRAVEL DROP INLET SEDIMENT FILTER

- GRAVEL FILTER

NOTE: FOR AREAS REQUIRING DOUBLE PERIMETER CONTROL WITHIN 50' OF JURISDICTIONAL WETLANDS AND NOT FOR ALL SILT SOXX APPLICATIONS. THIS DUPLICATION MAY BE SPECIFIED AS 12" SILT SOXX OR ORANGE CONSTRUCTION FENCE AS NOTED.





GODD GOOD FAIR EXCELLENT EXCELLENT FAIR EXCELLENT EXCELLENT FAIR

WITH NO DEFINED CHANNEL

SEEDING GUIDE

SEEDING WELL DRAINED

SEEDING SPECIFICATIONS

LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF

PIPE OUTLET PROTECTION CONSTRUCTION SPECIFICATIONS

. THE SUB GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.

PECIFIED GRADATION. 2. THE ROCK OR GRAVEL USED FOR FILTER OF RIP RAP SHALL CONFORM TO NHDOT

3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.

4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

5. TO BE CONSTRUCTED IAW NH SWM #2 4-6 CONVEYANCE PRACTICES, 6. OUTLET PROTECTION, PAGE 172.

E14

TABLE 7-24	RECOMMEND	ED RIP RAP	GRADA	TION RANGES
d50 SIZE=	0.5	FEET	6	INCHES
% OF WEIGHT SI THAN THE GIVEN		SIZE FROM	OF STOR	NE (INCHES) TO
100%		9		12
85%		8		11
50%		6		9
15%		2		3

CONSTRUCTION SEQUENCE:

E17

.) CUT AND REMOVE TREES IN CONSTRUCTION AREA ONLY AS REQUIRED, RELOCATE ANY PROJECT T.B.M.

4.) CLEAR, CUT AND DISPOSE OF DEBRIS IN APPROVED FACILITY

5.) CONSTRUCT TEMPORARY CULVERTS AS REQUIRED, OR DIRECTED

6.) CONSTRUCT ROADWAYS FOR ACCESS TO DESIRED CONSTRUCTION AREAS. ALL ROADS SHALL BE STABILIZED IMMEDIATELY. SEE BEST MANAGEMENT PRACTICES FOR BLASTING ON SHEET C-102.

7.) START BUILDING CONSTRUCTION.

8.) INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. INSTALL RAIN GARDENS. ALL DISTURBED AREAS SHALL STABILIZED IMMEDIATELY AFTER GRADING.

BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SEEDED OR MULCHED AT REQUIRED, OR DIRECTED. NO AREA IS ALLOWED TO BE DISTURBED FOR A LENCTH OF TIME THAT EXCEEDS 45 DAYS BEFORE BEING STABILIZED. DAILY, OR AS REQUIRED. ALL ROADWAYS AND PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADES. LIMIT THE LENGTH OF EXPOSURE OF UNSTABILIZED SOIL TO 45 DAYS OR LESS.

10.) CONSTRUCT TEMPORARY BERMS, DRAINS DITCHES, SILT FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.

11.) INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION. ALL SWPPP INSPECTIONS MUST BE CONDUCTED BY A QUALIFED PROFESSIONAL SUCH AS A PROFESSIONAL ENGINEER (PE), A CERTIFIED PROFESSIONAL IN EROSION AS MOD SEDIMENT CONTROL (CPESC), A CERTIFIED REPOSION SEDIMENT AND STORM WATER INSPECTOR (CESSWI), OR A CERTIFIED PROFESSIONAL IN STORM WATER QUALITY (CPSWO), INSPECTION REPORTS SHALL BE SUBMITTED TO THE COMMUNITY SERVICES DEPARTMENT. EROSION AND SEDIMENT CONTROL PRACTICES ARE TO BE INSPECTED WEEKLY AND AFTER 0.5" OF RAINFALL.

12.) COMPLETE PERMANENT SEEDING AND LANDSCAPING.

13.) REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE COMPLETE.

14.) SMOOTH AND REVEGETATE ALL DISTURBED AREAS.

16.) LOT DISTURBANCE, OTHER THAN THAT SHOWN ON THE APPROVED PLANS, SHALL NOT COMMENCE UNTIL AFTER THE ROADWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE.

B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE.
METHODS INCLUDE BROADCASTING, BRILLING AND HYDROSEEDING. WHERE BROADCASTING IS
USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.
C. REFER TO TABLE(G-E1 THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-E1 THIS

POUNDS PER 1,000 S.F.

SHEET) FOR RATES OF SEEDING. ALL LEGUMES (GROWNVETCH, BIRDSFOOT TREFOIL, AND TAITED, ALL LEGUMES (GROWNVETCH, BIRDSFOOT TREFOIL, AND TAITED, AND THE RESPONDED THE RESPONDED WITH THEIR SPECIFIC INOCULANT.

D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO BAY 20 OR FROM AUGUST 10 TO SEPTEMBER 19.

EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 19.

NOTE: THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS

THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

TALL FESCUE
CREEPING RED FESCUE
CROWN VETCH
OR
FLAT PEA
TOTAL

TALL FESCUE
CREEPING RED FESCUE
BIRDS FOOT TREFOIL
TOTAL

CONSERVATION MIX

TALL FESCUE (35%)

CREEPING RED FESCUE 1/ 50
KENTUCKY BLUEGRASS 1/ 50
TOTAL

CREEPING RED FESCUE (25%) 15 ANNUAL RYEGRASS (12%) PERENNIAL RYEGRASS (10%)

KENTUCKY BLUEGRASS (10%) 15 WHITE CLOVER (3%)

FLAT PEA TOTAL

F. TALL FESCUE 1

MIXTURE

SEEDING RATES

POUNDS PER PER ACRE 1,000 Sq. FL.

30 0.75 40 OR 55 0.95 OR 1.35

0.35 0.25 0.35

20 20 2

20 30

4. MULCH A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEDING. B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90LBS PER

SLOPE STABILIZATION DETAIL

NOT TO SCALE

A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE

B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL

3. FERRILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERRILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.

2. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, DOCASIONAL MOWNS MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VECETATION. TO BE CONSTRUCTED LAW N SWM

#3 4—1 EROSION CONTROL PRACTICES, PERMANENT VECETATION, PAGE 80.

SEE RAIN GARDEN AND INFILTRATION DETAIL SHEETS FOR SPECIFIC PLANTING INSTRUCTIONS AND SEEDING.

E 18 DEFINITION OF STABLE:

PER ENV-WQ 1500 ALTERATION OF TERRAIN

BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED.
A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED..
A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR
RIP-RAP HAS BEEN INSTALLED.
OR, EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

ADDITION STABILIZATION NOTES:

HAY MULCH OR OTHER APPROVED METHODS SHALL BE USED TO CONTROL EROSION OF NEWLY GRADED AREAS. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS AFTER THEIR CONSTRUCTION. DISTURBED SOIL AREAS SHALL BE EITHER TEMPORARILY OR PERMANENTLY STABILIZED. IN AREAS WHERE FINAL GRADING HAS NOT OCCURRED, TEMPORARY STABILIZATION MEASURES SHOULD BE IN PLACE WITHIN SEVEN (7) CALENDAR DAYS FOR EXPOSED SOIL AREAS THAT ARE WITHIN ONE HUNDRED (100) FEET OF SURFACE WATER BODY OR A WETLAND AND NO MORE THAN 14 CALENDAR DAYS FOR ALL OTHER AREAS, PERMANENT STABILIZATION SHOULD BE IN PLACE WITHIN THREE (3) CALENDAR DAYS FOLLOWING COMPLETION OF FINAL GRADING OF EXPOSED SOIL AREAS.

E21

4" TOPSOIL (MIN.) AND SEED TO ESTABLISH INSTALL ROLLED EROSION CONTROL BLANKET WITH ANCHOR HOOKS AS PER MANUFACTURES REQUIREMENTS. SUBMIT SHOP DRAWINGS FOR RODUCT EXAMPLES) NAG BIONET S 150 BN 3:1 TO 2:1 SLOPE NAG BIONET SC 150 BN 2:1 TO 1:1 SLOPE ANCHOR HOOK PER NAG BIONET SC 125 BN 1:1 AND GREATER MANUFACTURER'S REQUIREMENTS) AEC CURLEX II 1.5H TO 1V TO BE CONSTRUCTED IAW NH SWM #3 4-1 EROSION CONTROL PRACTICES, TEMPORARY EROSION CONTROL BLANKET, PAGE 58. ANCHOR PATTERN AND INSTALLATION INSTRUCTIONS FROM NORTH AMERICAN SEREN (NAG) AND AMERICAN EROSION COMPANY (AEC) WILL BE FOLLOWED FOR EACH APPLICATION AND SLOPE CONDITIONS WILL APPLY, SLOPES MORE GRADUAL THAN 3:1 MAY BE STABILIZED WITH VEGETATION OR HECP (HYDRAULICALLY APPUED EROSION CONTROL MIX) BONDED FIBER MATRIX. HOWEVER THE ENGINEER RESERVES THE RIGHT TO REQUEST INGREASED ROLLED EROSION CONTROL BLANKET (RECB) RECB TO BE INSTALLED ON ANY SLOPE.

E22

WINTER STABILIZATION NOTES

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR TO OCTOBER 15TH SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES ON DETENTION BASINS, SHALL BE LINED WITH BIODEGRADABLE, PHOTODEGRADABLE "JUSTE MATTING" (EXCELSIOR'S CURLEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING ACTIVE AFTER OCTOBER 15TH, ANY SNOW THAT ACCUMULAT THAW ALL AREAS WILL BE STABILIZED, AS DIRECTED ABOVE.

. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPRAP WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED.

PRIOR TO OCT, 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN 3. PRIOR TO CCT. 151H ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS' ELEVATIONS ARE PROPOSED TO REWAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND MLL REPUGE ROADWAY FORSON. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 304.3, BUT SHALL HAVE BETWEEN 15-25% PASSING THE #200 SIEVE AND THE LARGEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT MILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH, ANY NEW OR DISTURBED PLIES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT FENCING.

E - 102

NNE C. ROAD N.H. LAND OF MAS R. & DIANNE 36 CROSS RC ROCHESTER, I TAX MAP 205,

8

SURVEYING-SURVEYING-SURCINEER ND CROWN POINT F NH 03825 (603)3 ECOND (ON, NH AS NO 335 BARRING BE

F NEW KENNETH COTIEST.

SHEET 6 OF 6