



NONRESIDENTIAL SITE PLAN APPLICATION City of Rochester, New Hampshire

Date: March 23, 2021 Is a	conditional use	needed? Yes: x	No:	_ Unclear:
(If so	, we encourage y	ou to submit an ap	plication as s	oon as possible.)
Property information				
Tax map #: 216 ; Lot #('s):	29 ;	Zoning district:	Granite Ridge	Development
Property address/location: 21 Far				
Name of project (if applicable):				and the second s
Size of site: 2.15 acres; overl				
Property owner				
Name (include name of individual): 21 Farmington F	Road LLC		
Mailing address: 549 US Highway 1	BYP, Portsmouth I	NH 03801		
Telephone #: (603) 436-0666		Email: sroberts@)hpgrlaw.com	
Applicant/developer (if differe	nt from property	owner)		and the second s
Name (include name of individual)			LC	
Mailing address: 22 Isaac Lucas Circ	cle Dover NH 0382	0		MATERIA SERVICIA PROPERTI A SERVICIA DE ANTIGO ESTA A PROPERTI A SERVICIA DE ASSESSA A PERSONA DE ASSESSA A PE
Telephone #: 603-502-5200				
Engineer/designer				
Name (include name of individual)	: Kenneth A. Berry	& Christopher R. Ber	ry Berry Surveyi	ing & Engineering
Mailing address: 335 Second Crown p				ACCORDING TO THE PARTY OF THE P
Telephone #: 603-332-2863		Fax #:		
Email address: k.berry@berrysurveying.com	n & crberry@metrocast.r	Professional li	cense #: _14	243
Proposed activity (check all tha	it apply)			
New building(s): X Site de	velopment (othe	er structures, parl	king, utilities.	etc.): X
Addition(s) onto existing building(s): <u>X</u> Der	molition: X	Change o	f use:
	Page 1 (of 3 p			
roch-fileshare\plan\$\Forms\Applications\Site Plan - Non /27/2019	residential.doc			Updated
				- [

Describe proposed activity/use: See attached na	rrative	
Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15; Are there pertinent covenants? Yes Number of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0 ; number of proposed employees total: 4-8 Check any that are proposed: variance N/A; special exception N/A; conditional use X		
Utility information		
Utility information City water? yes X no; How far is City water from the site? On site City water? yes X no; How far is City sewer from the site? On site If City water, what are the estimated total daily needs? 500 gallons per day If City water, what are the estimated total daily needs? 500 gallons per day If City water, is it proposed for anything other than domestic purposes? yes X r If City water, do you plan to discharge anything other than domestic waste? yes n Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15 _; Are there pertinent covenants? Y Number of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0; number of proposed employees total: 4-8 Check any that are proposed: variance N/A _; special exception N/A _; conditional use Wetlands: Is any fill proposed? N/A _; area to be filled: N/A; buffer impact? 50 THIS CHART IS FILLED OUT BASED ON FINISHED LOT 29-1 Proposed post-development disposition of site (should total 100%) Building footprint(s) - give for each building	On site	
	On Site	
Utility information City water? yes X no; How far is City water from the site? On site City sewer? yes X no; How far is City sewer from the site? On Site If City water, what are the estimated total daily needs? 500 gallons per day If City water, is it proposed for anything other than domestic purposes? yes X no If City sewer, do you plan to discharge anything other than domestic waste? yes no Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15; Are there pertinent covenants? Yes Number of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0; number of proposed employees total: 4-8 Check any that are proposed: N/A _; special exception N/A _; conditional use X Wetlands: Is any fill proposed? N/A _; area to be filled: N/A; buffer impact? 600 s THIS CHART IS FILLED OUT BASED ON FINISHED LOT 29-1 Proposed post-development disposition of site (should total 100%) Square footage % overall site Building footprint(s) - give for each building 2264 10.3 Parking and vehicle circulation 16850 75.8 Planted/landscaped areas (excluding drainage) 2851 12.8 Natural/undisturbed areas (excluding wetlands) 0		
Utility information City water? yes X no; How far is City water from the site? On site City sewer? yes X no; How far is City sewer from the site? On site If City water, what are the estimated total daily needs? 500 gallons per day If City water, what are the estimated total daily needs? 500 gallons per day If City water, is it proposed for anything other than domestic purposes? yes X no If City sewer, do you plan to discharge anything other than domestic waste? yes no Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15; Are there pertinent covenants? Yes Number of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0; number of proposed employees total: 4-8 Check any that are proposed: variance N/A; special exception N/A _; conditional use X Wetlands: Is any fill proposed? N/A, area to be filled: N/A; buffer impact? 600 s THIS CHART IS FILLED OUT BASED ON FINISHED LOT 29-1 Proposed post-development disposition of site (should total 100%) Building footprint(s) - give for each building 2264 10.3 Parking and vehicle circulation 16850 75.8 Planted/landscaped areas (excluding drainage) 2851 12.8		
If City sewer, do you plan to discharge anything	other than domestic wa	3ste? vos
Utility information City water? yes X no ; How far is City water from the site? On site City sewer? yes X no ; How far is City sewer from the site? On site If City water, what are the estimated total daily needs? 500 gallons per day If City water, is it proposed for anything other than domestic purposes? yes X If City sewer, do you plan to discharge anything other than domestic waste? yes Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15 ; Are there pertinent covenants? Number of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0 inumber of proposed employees total: 4-8 Check any that are proposed: variance N/A; special exception N/A; conditional use Wetlands: Is any fill proposed? N/A; area to be filled: N/A is buffer impact? 6 THIS CHART IS FILLED OUT BASED ON FINISHED LOT 29- Proposed post-development disposition of site (should total 100%) Building footprint(s) — give for each building 2264 10.3 Parking and vehicle circulation 16850 75.8 Planted/landscaped areas (excluding drainage) 2851 12.8 Natural/undisturbed areas (excluding wetlands) 0	no _	
Utility information City water? yes X no ; How far is City water from the site? On site City sewer? yes X no ; How far is City sewer from the site? On Site If City water, what are the estimated total daily needs? 500 gallons per day If City water, what are the estimated total daily needs? 500 gallons per day If City water, is it proposed for anything other than domestic purposes? yes X no If City sewer, do you plan to discharge anything other than domestic waste? yes no Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15; Are there pertinent covenants? Y.Mumber of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0; number of proposed employees total: 4-8 Check any that are proposed: variance NA; special exception N/A; conditional use 2 Wetlands: Is any fill proposed? NA; area to be filled: N/A; buffer impact? 600 THIS CHART IS FILLED OUT BASED ON FINISHED LOT 29-1 Proposed post-development disposition of site (should total 100%) Building footprint(s) - give for each building		
Utility information City water? yes X no; How far is City water from the site? On site City sewer? yes X no; How far is City sewer from the site? On Site If City water, what are the estimated total daily needs? 500gallons per day If City water, is it proposed for anything other than domestic purposes? yes X no; If City sewer, do you plan to discharge anything other than domestic waste? yes no X Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15; Are there pertinent covenants? Yes Number of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0 number of proposed employees total: 4-8 Check any that are proposed: variance N/A; special exception N/A; conditional use X Wetlands: Is any fill proposed? N/A; area to be filled: N/A; buffer impact? 600 SF THIS CHART IS FILLED OUT BASED ON FINISHED LOT 29-1 Proposed post-development disposition of site (should total 100%) Building footprint(s) - give for each building 2264		
Building height: 15-20' Finished	d floor elevation: 255.4	0'
t parking spaces: existing: 0 total proposed: 1 Number of cubic yards of earth being removed from the complex of existing employees: 0; number of existing em	om the site Fill Only Imber of proposed empecial exception N/A;	ployees total: 4-8 conditional use X
		,
Building footprint(s) – give for each building	2264	% overall site
Building footprint(s) – give for each building Parking and vehicle circulation	2264 16850	% overall site
Describe existing conditions/use (vacant land?): See attached narrative Utility information City water? yes X no; How far is City sewer from the site? On site City sewer? yes X no; How far is City sewer from the site? On Site If City water, what are the estimated total daily needs? 500gallons per or If City water, is it proposed for anything other than domestic purposes? yes If City sewer, do you plan to discharge anything other than domestic waste? yes Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information # parking spaces: existing: 0 total proposed: 15 _; Are there pertinent covena Number of cubic yards of earth being removed from the site Fill Only Number of existing employees: 0; number of proposed employees tot Check any that are proposed: N/A _; special exception N/A _; condition Wetlands: Is any fill proposed? N/A _; area to be filled: N/A; buffer importance in the site of proposed post-development disposition of site (should total 100%) Proposed post-development disposition of site (should total 100%) Building footprint(s) - give for each building 2264 10.3 Parking and vehicle circulation 16850 75.8	% overall site 10.3 75.8	
Building footprint(s) – give for each building Parking and vehicle circulation Planted/landscaped areas (excluding drainage) Natural/undisturbed areas (excluding wetlands)	2264 16850 2851 0	% overall site 10.3 75.8
Building footprint(s) – give for each building Parking and vehicle circulation Planted/landscaped areas (excluding drainage) Natural/undisturbed areas (excluding wetlands) Wetlands	2264 16850 2851 0	% overall site 10.3 75.8

* 7

Describe existing conditions/use (vacant land?): See attached narrative Utility information City water? yes X no ; How far is City water from the site? On site City sewer? yes X no ; How far is City sewer from the site? On Site If City water, what are the estimated total daily needs? 500 gallons per day If City water, is it proposed for anything other than domestic purposes? yes X If City sewer, do you plan to discharge anything other than domestic waste? yes where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40'	rrative		
Describe existing conditions/use (vacant land?)	: See attached narrative		
Jtility information			
	water from the site?	On site	
City sewer? yes X no; How far is City	sewer from the site?	On Site	
City water, what are the estimated total daily n	eeds? 500	llopo non d	
City water, is it proposed for anything other tha	an domestic number of		
/here will stormwater be discharged? Underwood	other than domestic wa	aste? yes no	
	na infiltration system		
If City sewer, do you plan to discharge anything other than domestic waste? yes no Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank			
Where will stormwater be discharged? Underground infiltration system Building information Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40' Other information			
Type of building(s): Bank Building height: 15-20' Finished floor elevation: 255.40'			
	_		
moor or cable yards of earth being removed tre	om the cita Fill Only		
imper of existing employees: 0 : nu	mber of proposed ome	ployees total: 4-8	
sy that are proposed. Variance N/A; sy	pecial exception N/A ;	conditional use X	
etlands: Is any fill proposed? N/A; area to be THIS CHART IS FILLED O	e filled: N/A ;	ouffer impact? 600	
	sition of site (should to	otal 100%)	
Proposed <u>post-development</u> dispos	Torse (criodia te		
Proposed <u>post-development</u> dispos	Square footage	% overall site	
Proposed <u>post-development</u> dispos Building footprint(s) – give for each building	Square footage 2264	% overall site	
Proposed <u>post-development</u> disposed <u>Building footprint(s)</u> – give for each building Parking and vehicle circulation	Square footage 2264 16850		
Proposed post-development disposed Building footprint(s) – give for each building Parking and vehicle circulation Planted/landscaped areas (excluding drainage)	Square footage 2264 16850 2851	10.3	
Proposed post-development disposed Building footprint(s) – give for each building Parking and vehicle circulation Planted/landscaped areas (excluding drainage) Natural/undisturbed areas (excluding wetlands)	Square footage 2264 16850 2851	10.3 75.8	
Proposed post-development disposed Building footprint(s) – give for each building Parking and vehicle circulation Planted/landscaped areas (excluding drainage)	Square footage 2264 16850 2851	10.3 75.8	

DocuSign Envelope ID: 5B47E213-4816-4618-8624-7C8370ECF2CE

Page 2 (of 3 pages)

Comments	
Please feel free to add any comments, additional information, or requests for waive	ers here:
Please feel free to add any comments, additional information, or requests for waivers he see attached narrative Submission of application This application must be signed by the property owner, applicant/developer (if different property owner), and/or the agent. I(we) hereby submit this Site Plan application to the City of Rochester Planning Board pursuant to the City of Rochester Site Plan Regulations and attest that to the best of my knowledge all of the information on this application form and in the accompanying application and additional and documentation is true and accurate. As applicant/developer (if different for property owner)/as agent, I attest that I am duly authorized to act in this capacity. Signature of property owner: Date: 3/16/2021 Signature of agent: Put fussul. Date: 3/16/2021 Authorization to enter subject property I hereby authorize members of the Rochester Planning Board, Zoning Board of Adjustm. Conservation Commission, Planning Department, and other pertinent City departments, boards and agencies to enter my property for the purpose of evaluating this application including performing any appropriate inspections during the application phase, review post-approval phase, construction phase, and occupancy phase. This authorization appropriate inspecting this specific application/project. It is understood that these individuals must use as a property of the property. Date: 3/16/2021 Noctorial and Site Plan - Nomesidential doc Understood that these individuals must use as a property of the property. Date: 3/16/2021	
Submission of application	
	rent from
I(we) hereby submit this Site Plan application to the City of Rochester Planning Box	ard
pursuant to the City of Rochester Site Plan Regulations and attest that to the best of	of my
	ent from
knowledge all of the information on this application form and in the accompanying application and documentation is true and accurate. As applicant/developer (if different property owner)/as agent, I attest that I am duly authorized to act in this capacity. Signature of property owner: Date: 3/16/2021 Signature of applicant/developer: Number 1	
Signature of property owner: Unthony Vilorenzo	
Date: 3/16/2021	
(a)	And the second section of the section of t
booking it of the state of the	
Signature of agent: Peter Russell	
Date.	
Authorization to enter subject property	
specifically to those particular individuals legitimately involved in evaluating, reviewi	ing, or
inspecting this specific application/project. It is understood that these individuals mu	
ZF000C4E0A7 4U9	
Date: 3/10/2021	
\\roch-fileshare\plan\$\Forms\Applications\Site Plan - Nonresidential.doc 3/27/2019	Jpdated

Application for Conditional Use Conditional Uses and Buffer Reductions Section 42.19 - Conservation Overlay District City of Rochester, NH

Date: 3-23-21
Property information
Tax map #: 216 ; Lot #('s): 29 ; Zoning district: Granite Ridge Development
Property address/location: 21 Farmington Road
Name of project (if applicable):
Property owner
Name (include name of individual): 21 Farmington Road LLC
Mailing address: 549 US Highway 1 BYP, Portsmouth NH 03801
Telephone #: 603-436-0666 Fax 603-431-0879
Applicant/developer (if different from property owner)
Name (include name of individual): Miles Cook, NM Cook Development LLC
Mailing address: 22 Isaac Lucas Circle Dover NH 03820
Telephone #: 603-502-5200 Fax #: mcook@metrocast.net
Engineer/designer
Name (include name of individual): Kenneth A. Berry & Christopher R. Berry Berry Surveying & Engineering
Mailing address: 335 Second Crown point Road Barrington NH 03825
Telephone #: 603-332-2863 Fax #:
Email address: k.berry@berrysurveying.com & crberry@metrocast.net Professional license #: 14243
Proposed Project
Please describe the proposed project: Proposed 600 SF of disturbance within the 50' wetland buffer
to fill around a proposed bank, fire lane and storm water treatment area.
Please describe the existing conditions: See attached narrative.
roch-fileshare\plan\$\Forms\Applications\Conditional Use-Wetland.doc 1 evised 4/2/2015]

*[]	
P	ease fill in one of the next two sections – for either <u>Conditional Uses</u> or <u>Buffer Reductions</u> *
	onditional Uses
Fo ac	r Conditional Uses only, justify the proposal in terms of each of the criteria below cordance with subsection 42.19 (i) (1) (A)). All four criteria must be satisfied.
(i)	The proposed construction is essential to the productive use of land not in the COD.
Sec	e attached narrative.
	Design and construction methods will be such as to minimize impact upon lands and will include restoration of the site consistent with the permitted use.
-	valuative.
sec	ction shall limit the applicant from exploring alternatives with abutting property owners
(iii) There is no feasible alternative route on land controlled by the applicant that not cross the CO District nor has less detrimental impact on the wetlands. Nothing in Section shall limit the applicant from exploring alternatives with abutting property owned see attached narrative.	
1	Economic advantage is not the sole reason for the proposed location of work.
1	Economic advantage is not the sole reason for the proposed location of work. attached narrative.
See	
	attached narrative.
See	attached narrative.
Buff	attached narrative.

.

a	or <u>Buffer Reductions</u> only, justify the proposal in terms of each of the criteria below (in coordance with subsection 42.19 (i) (2) (B)). All four criteria must be satisfied.
th	The structure for which the exception is sought cannot feasibly, after consideratio all reasonable alternatives, be constructed on a portion or portions of the lot, which lies the CO district, or the application of the CO district eliminates greater than 50% or buildable area located on the parcel or in the judgment of the Planning Board, the oposed site layout would result in a significantly higher quality design.
(ii) Se not	The proposed structure and use must be consistent with the purpose and intent of ction 42.19 and provisions must be made to ensure that drainage from the structure will adversely impact any wetlands.
(iii) he	There shall be no impervious areas for parking within the reduced buffer for which Conditional Use Approval is sought.
iv) on	The maximum building coverage is limited to 50% of the outer half of the buffer e, as shown in the diagram below.
′) lan	Best management practices must be demonstrated to the satisfaction of the ning Board.

	•
itaria halaw (:-	
riteria below (in ied.	
ieu.	
r consideration	
e lot, which lie	
er than 50% of	
ing Board, the	
-	
and intent of	
e structure will	
ffer for which	
ner for writeri	
of the buffer	
or the bullet	
ction of the	
OI 1/10	

Submission of application

This application must be signed by the property owner, applicant/developer (if different from property owner), and/or the agent.

I(we) hereby submit this Conditional Use application to the City of Rochester Conservation Commission and Planning Board pursuant to the <u>City of Rochester Zoning Ordinance</u> and attest that to the best of my knowledge all of the information on this application form and in the accompanying application materials and documentation is true and accurate. As applicant/developer (if different from property owner)/as agent, I attest that I am duly authorized to act in this capacity, bocusianed by:

Signature of property owner:

Luthory Dilorungo	27656C4E8A714D9	Date: 3/16/2021	
Signature of applicant/developer:	Date: 3-22-2		
Signature of agent:	Puter Russell	B35470E180A0400	Date: 3/16/2021

Authorization to enter subject property

I hereby authorize members of the Rochester Conservation Commission and Planning Board, and other pertinent City departments, boards and agencies to enter my property for the purpose of evaluating this application including performing any appropriate inspections. This authorization applies specifically to those particular individuals legitimately involved in evaluating, reviewing, or inspecting this specific application/project. It is understood that these individuals must use all reasonable care, courtesy, and diligence when entering the property. (It is not necessary to sign this provision if a Planning Board application has been submitted.)

0	Anthony Dilonnzo		
		Date: 3/16/2021	

\\roch-fileshare\plan\\Forms\Applications\Conditional Use-Wetland.doc [revised 4/2/2015]



BERRY SURVEYING & ENGINEERING

335 Second Crown Point Road Barrington, NH 03825 Phone: (603) 332-2863 Fax: (603) 335-4623 www.BerrySurveying.Com crberry@metrocast.net

City of Rochester Planning Board Attention: Chief Planner, Seth Creighton 33 Wakefield Street Rochester, NH 03867

March 23, 2021

Re: Site Plan & Subdivision 21 Farmington Road Rochester, NH 03867 Tax Map 216, Lot 29

Mr. Creighton,

On behalf of our client, NM Cook Development, Berry Surveying & Engineering (BS&E) is submitting for TRG, to discuss a proposed site plan and minor subdivision.

Background and General Narrative:

21 Farmington LLC owns the parcel at 21 Farmington Road in Rochester, NH (Tax Map 216, Lot 29). Berry Surveying & Engineering has conducted an on-site survey of the parcel which includes a topographic analysis as well as a wetlands analysis. This work was conducted under a prior application and has been updated and reviewed in 2021. Wetlands were found along the existing stream to the rear of the parcel. The parcel has 2 existing buildings that sit on the northerly side of the parking lot. The site is mostly paved area with some grass and wooded are towards the rear.

The Proposal:

The proposed project consists of 2 portions. The first is to subdivide the parcel into 2 lots. A portion of the lot will be subdivided off to encompass the proposed site plan (this will be known as Lot 29-1). The remaining land will continue to be Lot 29. Due to the applications being conducted at the same time, the tax map and lot numbers reference the original parcel, 29, however much of the site activity will take place on the newly created lot 29-1. As part of the subdivision the existing buildings will be removed prior to recording because the proposed boundary line runs through one of them. As part of this subdivision, there will be 3 easements. Easement 1 will be for access and stormwater in service of Lot 29-1. Easements 2 & 3 will be access easements in favor of Lot 29. The shape and design of the subdivision is specific to this proposed user as well as the topographic limits of the site. Due to the future ownership of the remainder of Lot 29, it is important for some of the congruent abutting businesses that the lots be congruent in nature. The applicant is very cognizant of the need for future connections of the

Project Narrative, 21 Farmington Road, Rochester, NH

March 23, 2021 Page 2 of 2

parcels moving forward and has left an access easement at the front of the project site, as well as keeping the existing trail system free of the subdivision lines.

The second portion of the application is the proposed site plan. As stated above, the existing buildings and a portion of the existing parking lot will be removed. A proposed bank and relating parking will be constructed in its place on Lot 29-1. The proposed bank will require 7 spaces, however, 15 spaces are provided based on the needs of the end user and their experiences at their other locations. After discussions with the planning department, the applicant is proposing to keep the rear of the site open for future proposed parking. The site plan notes its location and the grading and drainage plan note the design intent and construction style needed for its construction. In addition the applicant will likely enter into a private agreement to allow additional parking on the remainder of the 21 Farmington Road. The proposed bank will have a drive up ATM lane at the rear of the site, two drive through teller lanes and a bypass lane (a turning template is included in the plan set demonstrating a Rochester fire truck can navigate the bypass lane).

As part of the site plan, an intensive drainage design was conducted. Given the existing condition of the site, soil type and proximity to adjacent wetlands, underground infiltration systems were designed. These underground infiltration systems will capture all of the runoff form the proposed bank development as well as some of the parking area on Lot 29. The stormwater will be pretreated and then infiltrated into native soil for full treatment. An overflow device will also be installed to route any runoff towards a level spreader that will be constructed along the 50'buffer. The proposed underground infiltration and level spreader will add a level of stormwater protection to the existing stream and wetlands that was not previously there.

All proper erosion and sediment control measures will be taken to ensure that no runoff is tracked onto Farmington Road or areas outside the proposed construction zone.

The proposed bank will continue to use the same sewer and water service on site.

As part of this application a conditional permit will be required for disturbing area within the 50' buffer. See attached conditional use narrative. Additionally, a permit is being filed with NHDOT for the proposed use. As part of the NHDOT application a traffic analysis was conducted for the proposed use. This analysis demonstrated that a deceleration lane will be required along N.H. Route 11 approaching the site. This deceleration lane was required for the prior application on this project site and replicated in this design. Design plans for the decel lane are included in the plan set.

Respectfully submitted,


BERRY SURVEYING & ENGINEERING


James F. Hayden Project Engineer Christopher R. Berry, SIT Principal, President


BERRY SURVEYING & ENGINEERING


335 Second Crown Pt. Rd., Barrington, NH 03825 (603) 332-2863 / (603) 335-4623 FAX www.BerrySurveying.Com












SHEET 5 OF 24



STANDARD SITE PLAN NOTES:

21 FARMINGTON ROAD LLC 549 US HIGHWAY 1 BYP PORTSMOUTH, NH G3801-4131

APPLICANT: NF COOK DEVELOPMENT, LLC 22 ISAAC LUCAS CIRCLE DOVER, NH 03820

- 2.) TAX MAP 216, LOT 29
- 3.) LOT AREA: 93,832 Sq. Ft., 2.15 Ac.
- 4.) S.C.R.D. BOOK 4248, PAGE 628

4.) S.C.R.D. BOOK 424E, PAGE 628

5.) ZOMING: GRD — GRANITE RIDGE DEVELOPMENT SETBADISS.

SETBADISS.

HISTORY SETBADISS.

HIST


- 6.) ALL ON-SITE UTILITIES SHALL BE INSTALLED UNDERGROUND, EXCEPT ONE REQUIRED DROP POLE.
- 7.) THE SUBJECT PARCEL IS SERVICED BY MUNICIPAL WATER AND MUNICIPAL SEWER,
- B.) ALL EROSION CONTROL NOTES SHALL INCLUDE PROVISIONS FOR CONSTRUCTION SEQUENCING, TEMPORARY TROSION CONTROL MEASURES, AND PERMANENT STANDARDSSOLM AS LOAM SPEPAD RATE FOR DISTUREDED AREAS, RATES OF LIME, TIPE AND RATES FOR FERTILIZER, AND SEED AND MULCH MIXTURE WITH RATES OF APPLICATION.
- 9.) ALL TREATMENT SWALES TO BE CONSTRUCTED SHALL HAVE SOD BOTTOMS.
- 10.) A LETTER OF CREDIT FOR 10% OF THE TOTAL COST OF CONSTRUCTION OF TO BE DISTURBED AREAS ON THE SITE SHALL BE SUBMITTED PRIOR TO ANY EARTH DISTURBENC ACTIVITY COLURS. COOPONIATE WITH THE CITY OF PROCHESTER DEPARTMENT OF PLANNING & DEPARTMENT OF PUBLIC WORKS.
- A PRE-CONSTRUCTION CONFERENCE WITH THE DEVELOPER, THE DESIGN ENGINEER, THE EARTHWORK CONTRACTOR, AND THE TECHNICAL STAFF SHALL OCCUR PRIOR TO ANY EARTH DISTURBING ACTIVITY.
- 12.) BUILDING ADDRESSES SHALL BE ASSIGNED BY THE ASSESSING DEPARTMENT AT THE TIME OF ISSUANCE OF A BUILDING PERMIT.
- 1.5.) ALL CONSTRUCTION SHALL CONFORM TO THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION DATED 2016. CONSTRUCTION SHALL ALSO CONFORM TO THE CITY OF ROCHESTER POLICES AND PRACTICES.
- 14.) CALL DIG SATE PRIOR TO BEGINNING WORK (1-888-344-7233).
- 15.) CONTRACTOR TO CONTACT ROCHESTER DPW A MINIMUM OF TWO WEEKS PRIOR TO ANY CONSTRUCTION TO COORDINATE ALL WORK CONCERNING INSTALLATION OF ANY PROPOSED WATER LINE IMPROVEMENTS AS MAY BE REQUIRED.
- 16.) CONTRACTOR SHALL COORDINATE ALL ELECTRICAL INSTALLATIONS WITH EVERSOUPCE AT (603) 436-7708. ALL ELECTRIC CONDUIT INSTALLATION SHALL BE INSPECTE) BY EVERSOURCE PRIOR TO BACKFILL. A 48-HOUR MINIMUM NOTICE IS REQUIRED.
- 18.) ALL UNPAYED DISTURBED AREAS ARE TO RECEIVE 4" QUALITY LOAM AND SEED.
- 19.) THE SITE WORK HOURS SHALL BE LIMITED TO MONDAY-FRIDAY 7AM-6PM, SATUPDAY 8AM-6PM WITH NO SUNDAY HOURS. HOURS OF CONSTRUCTION SHALL BE DOCUMENTED ON A SITE CONSTRUCTION SIGN ALONG WITH THE CONTACT INFORMATION FOR THE GENERAL CONTRACTOR.
- 20.) FROM GROUND BREAKING THE SITE SHALL REMAIN ACCESSIBLE YEAR ROUND IN ALL WEATHER CONDITIONS.
- 21.) THIS SITE DESIGN HAS BEEN REVIEWED FOR COMPLIANCE WITH THE APPLICABLE ACCESSIBILITY REGULATIONS IN ACCORDANCE WITH NH RSA 11-A:5.
- 22. WRITTEN DIMENSION ON THIS PLAN TAKE PRECEDENCE OVER SCALED DIMENSIONS, THE CONTRACTOR SHALL USE CAUTION WHEN SCALING REPRODUCED PLANS. IN THE EVENT OF A COMPLICTE BETWEN THIS PLAN SET AND ANY OTHER DRAWNICS AND/OR SPECIFICATIONS, THE ENGINEER SHALL BE INTIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CONTRACTOR ITS TO CONFIRM ALL BLEVATIONS, COMPLICTS MILL BE REPORTED TO THE DESIGN ENGINEER PRIOR TO CONSTRUCTION.
- 23.) FOR MORE INFORMATION ABOUT THIS VESTED SITE PLAN PLEASE CONTACT THE CITY OF ROCHESTER PLANNING OFFICE AT 603-335-1338.
- 24.) BACKFLOW PREVENTORS SHALL BE PROVIDED FOR DOMESTIC WATER LINES.
- 25.) THE FOLLOWING FEDERAL AND STATE PERMITS HAVE BEEN ISSUED FOR THE SUBJECT PROPERTY: NHOOT DRIVEWAY PERMIT: PENDING
- 26.) ALL PLANS ARE CONSIDERED TO BE NOT FOR CONSTRUCTION UNTIL ALL REQUIRED PERMITS ARE OBTAINED AND PLANS ARE STAMPED FOR CONSTRUCTION.
- 27.) MECHANICALS ARE TO BE PLACED ON THE ROOF OF THE STRUCTURE.
- 23) AS BUILT PLANS OF SITE SHALL BE SUBMITTED ON PAPER AND IN A DIGITAL FERMAL IN A POP AND AUTOCAD DWG, AUTOCAD DWG OR AN ERS FORMAT TO THE CITY OF ROCHESTER DEPARTMENT OF PUBLIC WORKS UPON COMPLETION OF PROJECT, AS-BUILT PLANS SHALL BE PREPARED, AND CERTIFIED CORRECT BY A LLS. OF P.E. DIGITAL FILES SHALL BE CEO-REFERENCED TO NEW HAMPSHIRE STATE PLANE COORDINATES NAD83 AND SHALL BE EXPRESSED IN FEET.
- FEET.


 29.) IMPERVIOUS COVERAGE LOT 29:
 EXISTING PAVED IMPERVIOUS: 3,021 Sq. Ft. (3,2%)
 EXISTING PAVED IMPERVIOUS: 40,477 Sq. Ft. (40,5%)
 EXISTING TOTAL IMPERVIOUS: 40,469 Sq. Ft. (40,5%)
 PROPOSED BULLIONG IMPERVIOUS: 0 Sq. Ft. (62,8%)
 PROPOSED TOTAL IMPERVIOUS: 36,269 Sq. Ft. (41,2%)
 IMPERVIOUS: COVERAGE LOT 29-1:
 EXISTING PAVED IMPERVIOUS: 0 Sq. Ft. (61,2%)
 EXISTING PAVED IMPERVIOUS: 0 Sq. Ft. (63%)
 PROPOSED BULLIONG IMPERVIOUS: 0 Sq. Ft. (63%)
 PROPOSED BULLIONG IMPERVIOUS: 0 Sq. Ft. (63%)
 PROPOSED BULLIONG IMPERVIOUS: 12,264 Sq. Ft. (63%)
 PROPOSED PAVED IMPERVIOUS: 12,264 Sq. Ft. (63%)
 PROPOSED PAVED IMPERVIOUS: 14,378 Sq. Ft. (63.2%)
- 30.) BACKFLOW PREVENTORS SHALL BE PROVIDED FOR DOMESTIC WATER LINES.
- 31.) THE LIMITS OF CONSTRUCTION DISTURBANCE AND TREE CLEARING LIMITS ARE TO BE MARKED OUT AND APPROVED BY THE CITY PRIOR TO WORK.
- ALL PLANS ARE CONSIDERED TO BE NOT FOR CONSTRUCTION UNTIL ALL REQUIRED PERMITS ARE OBTAINED AND PLANS ARE STAMPED FOR CONSTRUCTION.
- 33.) THE INTENT OF THIS PLAN IS TO SHOW THE OVERNEW SITE PLAN IN RELATION TO THE ABUTTING LOTS.

LC OVERVIEW SITE PLAN
OPE: 21 FARMINGTON ROAD L
RAMINGTON ROAD
ROCHESTER, N.H.
TAX MAP 216, LOT 29 -AND FOR:

SURV SURV 335 SECOND CROWI BARRINGTON, NH 0382 SCALE : 1 ''








3.) LOT AREA: 93,832 Sq. Ft., 2.15 Ac.

4.) S.C.R.D. BOOK 424B, PAGE 628

- 5.) I HEREBY CERTIFY THAT, TO THE BEST OF MY KNOWLEDGE & BELIEF, THIS PARCEL DOES NOT FALL WITHIN THE FLODO PLAIN FLUOD HAZARD RET: FEMA COMMUNITY# -330150, MAP# -3301700184D, DATED: MAY 17, 2005 & FEMA COMMUNITY# -330150, MAP# 33017020230. DATED: MAY 17, 2005
- 6.) VERTICAL DATUM BASED ON USGS NAVDB8 ELEVATIONS. HOMIZONTAL COORDINATES BASED ON NH GRID. (CITY OF ROCHESTER NH CONTROL POINTS 240 & 241)
- SDIL: HINCKLEY LOAMY SAND, 3-8% SLOPE THROUGHOUT SOURCE: USDA-NRCS WEBSOIL
- 8.) PLAN INTENT: TO DEMONSTRATE THE PROPOSED GRADING AND DRAINAGE INFRASTRUCTURE.
- 10.) TWO ON SITE BENCHMARKS ARE PROVIDED. BS&E IS TO PROVIDE ADDITIONAL BENCHMARKS PRIOR TO CONSTRUCTION.
- EXISTING AND PROPOSED CONTOURS ARE PROVIDED AT 1' INTERVALS WITH DRAINAGE FEATURES AT MORE PRECISE INTERVALS.
- SEE UTILITY PLANS FOR DETAILS ON THE PROPOSED SEWER, WATER, AND UNDERGROUND ELECTRIC LINES SHOWN.
- EXISTING CONDITIONS INFORMATION IS BASED ON A SURVEY PERFORMED BY BERRY SURVEYING & ENGINEERING AND IS ENCLOSED IN THIS PACKAGE.
- 15.) THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERHIED BY THE OWNER OR ITS REPRESENTATIVE THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE OWNER WHICH THE OCCASIONED BY THE CONTRACTOR'S FAILURE OF ALL DAMAGES WHICH MICH TEL OCCASIONED BY THE CONTRACTOR'S FAILURE OF CATE EACH AND TO PRESENCE ANY AND ALL UNDERGROUND UTILITIES CALL. "UNC-SAFE" 1—888-DIGSAFE (344-7233) AT LEAST 72 HOURS BEFORE COMMENDING CONSTRUCTION.")
- 15.) WHERE AN EXISTING UNDERGROUND UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL BE ACCUPATELY DETERMINED WITHOUT DLK-MY BY THE CONTINATION, AND THE INFORMATION FURNISHED TO THE ENGINEER FOR RESOLUTION OF THE CONFLICT.
- 18.) THE CONTRACTOR SHALL MAKE ALL ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENT OF GAS, ELECTRIC, TELEPHONE AND ANY OTHER PRIVATE UTILITIES BY THE UTILITY COMPANIES.
- 17.) AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE. DISTURBANCE OUTSIDE AREAS SHOWN TO BE APPROVED BY DESIGN ENGINEER.
- 18.) THE TERM "PROPOSED" (PROP.) MEANS WORK TO BE CONSTRUCTED USING NEW MATERIALS, OR, WHERE APPLICABLE, RE-USING EXISTING MATERIALS IDENTIFIED AS "REMOVE & RESET" (R & R)
- 20.) ALL ELEVATIONS TO BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE DESIGN ENGINEER IS TO BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCY. TEMPORARY BENCHMARKS (T.B.M.) ARE TO BE PROVIDED BY THE DESIGN ENGINEER.
- 21.) UPON FINAL COMPLETION AND 85% STABILIZATION THE DRAINAGE SYSTEM IS TO BE CLEANED OF ALL DEBRIS TO INCLUDE THE PUMPING OF THE BASIN SUMPS.
- 22.) ALL CATCH BASINS AND DRAIN MANHOLES ARE TO HAVE BOOTS INSTALLED ON ALL INLETS AND OUTLETS. CATCH BASINS ARE TO HAVE NHDOT TYPE "B" CRATES AND DRAIN MAIHOLES ARE TO HAVE NH STANDARD COVERS.
- 23.) SEE DETAILS CONCERNING SITE LAYOUT, UTILITY, AND SEDIMENT AND EROSION CONTROLS.
- 24.) ALL DRAINAGE PIPE IS TO BE HDPE N=12. INDIMIDUAL PIPE SIZES ARE SPECIFIED. RECYCLED PIPE IS APPROVED FOR PROJECT SITE. RECYCLED HDPE PIPE "GREEN PIPE" IS ACCEPTABLE FOR THIS PROJECT SITE.
- 25) ALL CATCH BASINS SHALL BE PRE-CAST H-20 LOADING AND SHALL BE EQUIPPED WITH DEEP SUMPS (4" MINE) AND HOODS (SEE DITALES) HOODS ARE TO BE "THE ELMINATOR" BY KLEAKSTEAM. PINS ARE TO BE INNOTIT THE "B" STALE AND SHALL BE SET FLUSH WITH FINISH GRADE, UNLESS OTHERWISE INSTRUCTED DURING CONSTRUCTION BY ROCHESTER DRW. RIMS ABOVE FRISH RAPLE WILL BE NOT BE ACCEPTED. ALL RIMS, GRATES AND COVERS ARE TO BE U.S.A MADE HOUSE ARE TO BE INSTRUCTED IMMEDIATELY AFTER BASIN CONSTRUCTION.
- 26.) THIS SITE PLAN PROPOSES 38,000 Sq.Ft. OF DISTURBANCE.
- 27.) ROOF DRAINS TO TIE INTO DMH #15 OR #16.
- 28.) FUTURE PARKING LOCATION PROVIDED ON THE SITE PLAN. IF FUTURE PARKING IS TO BE CONSTRUCTED, FILL AND A RETAINING WALL WILL BE REQUIRED. PARKING AREA SHALL BE CONSTRUCTED SO THAT RUMORF FLOWS TOWARDS THE BANK AND INTO THE PROPOSED CATCH BASINS AS IS THE DESIGN INTENT.



GRAPHIC SCALE (IN FEET) 1 inch = 20 ft.

LCC ADING & DRAINAGE PLAN
OF: 21 FARMINGTON ROAD L
: NM COOK DEVELOPMENT LL
FARMINGTON ROAD
ROCHESTER, N.H.
TAX MAP 216, LOT 29


RRY SURVEYING & ENGINEERING SS SECOND CROWN POINT ROAD SINGTON, NH 03825 (603)332-2863 335 Si BARRING SCAL $_{\Omega}$

NM NM


LAND FOR:



SHEET 8 OF 24



SHEET 9 OF 24



HINKLEY LOAMY SAND K = 0.17

SEE SITE SPECIFIC SOILS MAP (SSSM)
SEE WEBSOIL USDA-ANCS
ERODIBLITY FACTOR - K, CPESC MANUAL, ENVIROCERT INTERNATIONAL INC. &
ROCKINGHAM COUNTRY SOIL SURVEY, ROCKWEB SOIL ATTRIBUTES.

CONTRACTOR TO BE AWARE OF THE SOIL PROFILES AND ENSURE THAT PROPER EROSION PREVENTION AND SEDIMENT CONTROL MEASURES ARE TAKEN AT ALL TIMES. ANY DEWATERING REQUIREMENTS IN NEW HAMPSHIRE REQUIRE SPECIAL PROVISIONS IN ACCORDANCE WITH THE "CLARFICATION OF SECTION 9.1.2 (STATE OF NEW HAMPSHIRE CONDITIONS) AND OTHER HIS SPECIFIC INFORMATION FOR THE U.S. EPA 2012 NPOES CONSTRUCTION GENERAL PERMIT (CGP)" DATED MAY 3, 2012 INCLUDED IN THE SWPPP.

COVER MANAGEMENT DURING CONSTRUCTION FOR EXPOSED SOIL WILL INCLUDE HAY / STRAW APPLIED AT A RATE OF 2.0 TONS PER ACRE, TEMPORARY SEEDING OF ANNUAL RYE GRASS, AND PERMANENT SEEDING AT THE EARLIES OPPORTUNITY. SEE ADDITIONA REQUIREMENT FOR STABILIZATION ON THE EROSION AND SEDIMENT CONTROL DETAIL SHEETS, E-101 AND E-102.

THE CONSTRUCTION SCHEDULE WILL BE MANAGED SO THAT ALL STORMWATER STRUCTURES WILL BE BULLT AND STABILIZED PRIOR TO RECEIVING SURFACE WATER RUNOFF. CONTRACTOR TO BE RESPONSIBLE FOR ALL DIVERSIONS DURING CONSTRUCTION AND FOR INTERIM SEDIMENT AND EROSION CONTROL MEASURES.

NM COOK DEVELOPMENT, LLC 22 ISAAC LUCAS CIRCLE ROCHESTER, NH 03820 APPLICANT:

3.) LOT AREA: 93,832 Sq. Ft., 2.15 Ac.

4.) S.C.R.D. BOOK 4248, PAGE 628

5.) VERTICAL DATUM BASED ON USGS NAVD88 ELEVATIONS.
HORIZONTAL COORDINATES BASED ON NH GRID. (CITY OF ROCHESTER NH - CONTROL POINTS 240 & 241)

6.) SOIL: HINCKLEY LOAMY SAND, 3-8% SLOPE THROUGHOUT SOURCE: USDA-NRCS WEBSOIL

7.) IMPERVIOUS COVER: 50,008 Sq. Ft., 1.15 Ac., 53.3%

8.) THE PURPOSE OF THIS PLAN IS TO SHOW THE EROSION AND SEDIMENT CONTROL PLAN FOR THE PROPOSED SITE PLAN.

9.) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVE AND BELOW GROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. ANY UTILITY CONFLICTS SHOULD BE REPORTED IMMEDIATELY TO THE DESIGN ENGINEER.

10.) THE CONTRACTOR SHALL CALL AND COORDINATE WITH DIGSAFE AT 1-888-344-7233 AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.

11.) ALL DRAINAGE PIPE IS TO BE HDPE N-12. INDIVIDUAL PIPE SIZES ARE SPECIFIED ON GRADING AND DETAIL PLAN SHEETS, GREEN PIPE.

12.) ALL ELEVATIONS TO BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE DESIGN ENGINEER IS TO BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCY. TEMPORARY BENCHMARKS (T.B.M.) ARE TO BE PROVIDED BY THE DESIGN ENGINEER.

13.) UPON FINAL COMPLETION AND 85% STABILIZATION, THE DRAINAGE SYSTEM IS TO BE CLEANED OF ALL DEBRIS. SEDIMENT CONTROL PRACTICES REMOVED AND DISPOSED OF PROPERLY, AND ANNUAL MAINTENANCE PREFORMED ON ALL DRAINAGE PRACTICES.

14.) EROSION AND SEDIMENT CONTROL INSPECTIONS TO BE CONDUCTED ONCE PER EVERY SEVEN DAYS AND AT AN INCREASED FREQUENCY INCLIDING WITHIN 24-HOURS OF A 0.25 INCH RAIN EVENT. INSPECTIONS TO BE CONDUCTED BY A "QUALIFIED PERSON" AS DEFINED BY FEAR COP 4.1.1 AND INSPECTION REPORTS SUBMITTED TO THE CITY OF ROCHESTER, NH, ENGINEERING DEPRARTMENT WHITH 24 HOURS IN ACCORDANCE WITH COP 4.1.7 AND MAINTAINED BY THE OWNER FOR A PERIOD OF THREE YEARS AFTER THE PROJECT IS COMPLETED. SEE ALSO CITY OF ROCHESTER ADDITIONAL INSPECTION REQUIREMENTS BELOW.

15.) PERIMETER CONTROL MAY BE EROSION CONTROL MIX BERM, SILT FENCE, OR FILTREXX SILT SOXX (OR APPROVED EQUAL.) BIOMEDIA PROTECTION IS TO BE INSTALLED WITH FILTREXX SILT SOXX OR OTHER APPROVED MULCH FILLED TUBE PROTECTION. SEE EROSION AND SEDIMENT CONTROL DETAILS FOR INSTALLATION INSTRUCTION.

16.) PER EPA COP Z.1.2.2 (INSTALL PERIMETER CONTROL), "YOU MUST INSTALL SEDIMENT CONTROLS ALONG THOSE PERIMETER AREAS OF YOUR SITE THAT WILL RECEIVE STORMWATER FROM EARTH DISTURBING ACTIVITIES." AS A RESULT OF SWPPP INSPECTIONS, THE CONTROLTOR MAY HAVE TO EXPAND PERIMETER CONTROLS TO MEET THIS REQUIREMENT. THE EASE PLAN IS INITIAL GUIDANCE AS TO THE ANTICIPATED REQUIREMENTS AND IT THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT STORMWATER VIOLATION DO NOT OCCUR.

17.) CITY OF ROCHESTER: IN ACCORDANCE WITH STORMWATER REGULATIONS THE FOLLOWING STORMWATER MEASURES ARE REQUIRED.

A.) ALL PROPOSED BMP» WILL CONFORM TO THE NH STORMWATER MANUAL VOLUME 3.

B.) EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SOIL LAND DISTURBANCE AND MUST BE REVIEWED AND APPROVED BY COMMUNITY SERVICE.

C.) TEMPORARY STABILIZATION MEASURES SHOULD BE IN PLACE WITHIN SEVEN CALENDAR DAYS FOR EXPOSED SOILS AREAS THAT ARE WITHIN ONE HUNDRED FEST OF A SURFACE WATER BODY OF A WETLAND AND NO MORE THAN 14 CALENDAR DAYS FOR ALL OTHER AREAS, PERMANENT STABILIZATION SHOULD BE IN PLACE WITHIN THREE CALENDAR DAYS FOLLOWING COMPLETION OF FINAL GRADING OF EXPOSED SOIL AREAS.

D. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED IN FUNCTIONING CONDITION UNTIL FINAL STABILIZATION IS ACCOMPLISHED.

ACCOMPLISHED.

E) DEPARTMENT OF PUBLIC WORKS OR THEIR DESIGNATED ACENT SHALL HAVE ACCESS TO THE SITE TO COMPLETE ROUTINE INSPECTIONS AND SHALL BE NOTIFIED 24—HOURS PRIOR TO INSTALLATION OF A STORMWATER BMP IN ORDER TO SCHEDULE AN INSPECTION, DURING NORMAL WORKING HOURS.
F) THE PLANNING BOARD OR DPW MAY REQUIRE THE DESIGN ENDINEER AND/OR AN INDEPENDENT, THIRD-PARTY INSPECTION AND OVERSIGHT OF THE CONSTRUCTION OF STORMWATER MANAGEMENT FACILITIES AND EROSION AND SEDIMENT CONTROL AT THEIR DISCRETION. THE OWNER / APPLICANT IS RESPONSIBLE FOR ALL FEES ASSOCIATED WITH INSPECTIONS.
G.) ALL SWPPP INSPECTIONS MUST BE CONDUCTED BY A QUALIFIED PROFESSIONAL SUCH AS A PROFESSIONAL ENGINEER (PC), A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (PCSS), A CERTIFIED EROSION SEDIMENT AND STORMWATER INSPECTOR (CESSWI), OR A CERTIFIED PROFESSIONAL IN STORMWATER QUALITY (CPSWQ). INSPECTION REPORTS WILL BE SUBMITTED TO THE DPW ENGINEERING DEPARTMENT.

CONTRACTOR IS RESPONSIBLE FOR SWEEPING THE PARKING LOT, SIDEWALKS AND ANYTHING DISTURBED, TO ENSURE THAT NO SEDIMENT IS BEING TRACKED ONTO N.H. ROUTE 11.


CONTRACTOR IS RESPONSIBLE FOR CLEANING AND MAINTAINING THE INLET PROTECTION ONCE INSTALLED

FUGITIVE DUST IS TO BE CONTROLLED THROUGHOUT THE CONSTRUCTION PROCESS IN ACCORDANCE WITH ENV-A 1000.

CONTRACTOR IT TO MEET THE REQUIREMENTS SPECIFIED IN RSA 430:51-57 AND AGR 3800, RELATING TO INVASIVE SPECIES.

CONTRACTOR IS RESPONSIBLE FOR PROTECTING THE WATER QUALITY FROM ANY RUN OFF DURING THE CONSTRUCTION PROCESS, IN ACCORDANCE WITH ENV-WQ 1507, IN ORDER TO PREVENT VIOLATIONS OF THE STORM WATER QUALITY STANDARDS.

CATCH BASIN HOODS WILL BE INSTALLED AS SOON AS THE BASIN IS PUT ON LINE. RIM IS TO BE RAISED WITH FINAL GRADE SO THAT STORMWATER RUNOFF CAN DRAIN PROPERLY THROUGHOUT CONSTRUCTION.



LEGEND

RAIN CARDEN BIO-MEDIA
PROTECTION
PERIMETER CONTROL
RESIDENTIAL (ROADWAY CONSTRUCTION
IRON PIPE (FND)
IRON BOUND (FND)
REBAR (FND)
UTILITY POLE
GUY WIRE

P —— SS —— SS —— SS ——

PLA LLC LLC T CONTROL STON ROAD ELOPMENT L ROAD N.H. OF: AND FOR:

8 335 RRIN



BA SC DA

 $_{\Omega}$

SHEET 10 OF 24

NOTES CONTINUED: NOTES CONTINUED: NOTES: 9.) IF THE EARTHWORK IS PERFORMED DURING FREEZING WEATHER (NOT ALLOWED IN CITY R.O.W.), EXPOSED SUBGRADES ARE SUSCEPTIBLE TO FROST, NO FILL OF UTILITIES SHALL BE PLACED ON FROZEN GROUND. THIS WILL LIKELY REQUIRE REMOVAL OF A FROZEN SOIL CRUST AT THE COMMENCEMENT OF EACH DAY'S OPERATION, THE FINAL SUBGRADE ELEVATION WOULD ALSO REQUIRE AN APPROPRIATE DEGREE OF INSULATION WOULD ALSO REQUIRE AN APPROPRIATE DEGREE OF INSULATION AGAINST FREEZING. 16.) CONTRACTOR SHALL COORDINATE ALL CABLE INSTALLATIONS WITH COMCAST. 1.) OWNER: 17.) CONTRACTOR SHALL COORDINATE ALL GAS INSTALLATIONS WITH UNITIL. NM COOK DEVELOPMENT, LLC 18.) ALL WATER SERVICES ARE TO BE WITNESSED WITH A 2"X4" PAINTED BLUE. ALL SEWER SERVICES ARE TO BE WITNESSED WITH A 2"X4" PAINTED YELLOW, IS STUBBED PRIOR TO BUILDING CONSTRUCTION. APPLICANT: 22 ISAAC LUCAS CIRCLE DOVER, NH D3820 10.) PLACEMENT OF BORROW MATERIALS SHALL BE PERFORMED IN A MANNER THAT PREVENTS LONG TERM DIGFERENTIAL SETTLEMENT EXCESSIVELY WET MATERIALS SHALL BE STOCKHLED AND ALLOWED TO DRAIN BEFORE PLACEMENT FROZEN MATERIAL SHALL NOT BE USED FOR CONSTRUCTION. VOIDS BETWEEN STONES AND CLUMPS OF MATERIAL SHALL BE FILLED WITH FINE MATERIALS. 2.) TAX MAP 216, LOT 29 3.) LOT AREA: 93,832 Sq. Ft., 2.15 Ac. 20.) SEE EVISTING CONDTIONS PLAN FOR DATUM, VERTICAL DATUM BASED ON NAVDBB ELEVATIONS, HORIZONTAL DATUS BASED ON NADBS STATE PLANE COORDINATES GATHERED USING TOPCON HIPER SR SURVEY GRADE OFS. 4.) S.C.R.D. BOOK 4248, PAGE 628 11.) FINAL UTILITY LOCATIONS TO BE COCRDINATED BETWEEN THE CONTRACTOR, ALL APPROPRIATE UTILITY COMPANIES AND THE ROCHESTER DPW. 5.) THE INTENT OF THIS PLAN IS TO SHOW THE PROPOSED UTILITY DESIGN. 6.) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERHIFLED. LOCATING AND PROTECTING ANY ABOVE AND BELOW GROUND UTILITIES IS THE SOLE RESPONSIBILIT OF THE CONTRACTOR. ANY UTILITY CONTICITS SHOULD BE REPORTED IMMEDIATELY TO THE DESIGN ENGINEER. 21.) ALL SEWER INSTALLATIONS SHALL CONFORM TO THE REQUIREMENTS OF NINDES & ROCHESTER OPW SEWER DIVISION STANDARDS. ALL PVC SEWER PIPE IS TO CONFORM WITH ENV-WO 704.05 (c)-(e) FOR 5DR 35 GRAVITY SEWER PIPE, CONFORM WITH ENV-WO 704.08 FOR 5DR 21 / 11 / 9 FORCE MAIN PRESSURE PIPE, AND CONFORM WITH ASTM D3034, PVC JOINT SEALS SHALL CONFORM WITH ASTM D3121. THE FORCE MAIN SHALL BE TESTED IN ACCORDANCE WITH ENV-WO 704.09. 12.) CONTRACTOR TO CONTACT ROCHESTER DPW A MINIMUM OF TWO WEEKS PRIOR TO ANY CONSTRUCTION TO COORDINATE ALL WORK CONCERNING INSTALLATION OF ANY PROPOSED WATER LINE IMPROVEMENTS. 7.) THE CONTRACTOR SHALL CALL AND COORDINATE WITH DIGSAFE 1-BB8-344-7233 AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY. 13.) ALL WATER MAIN AND SERVICE INSTALLATIONS SHALL CONFORM TO CITY OF ROCHESTER STANDARDS. ALL HIGHWAY CONSTRUCTION WILL MEET THE CITY OF ROCHESTER STANDARDS. EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.


8.) PROTECTION OF SUBGRADE: THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN STABLE, DEWATERED SUBGRADES, TRENCHES, AND OTHER APEAS DURING CONSTRUCTION, SUBGRADE INSTUBBANCE MAY BE INFLUENCED BY EXCAVATION METHODS, MOISTURE, PRECIPITATION, CROUNDWATER CONTROL, AND CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL TAKE PRECAUTIONS TO PREVENT SUBGRADE DISTURBANCE, SUCH PRECAUTIONS MAY INCLUDE DIVERTING STORMWATER RINOGE AWAY FROM CONSTRUCTION AREAS, REDUCING TRACFIC IN SENSITIVE AREAS, AND MAINTAINING AN EOFECITE DEWATERING PROGRAM, SOILS EXHIBITING HEAVING OF INSTABILITY SHALL BE OVER EXCAVATED TO MORE COMPETENT BEARING SOIL AND PEPLAGED WITH FREE DRAINING STRUCTURAL FILL MEETING THE ENGINEERS SPECIFIC RECOMMENDED CRITERIA. 22.) VERTICAL DATUM BASED ON NAVDBB ELEVATIONS HORIZONTAL COORDINATES BASED ON NADB3. COORDINATES GATHERED USING TOPCON HIPER SR SURVEY GRADE GPS RECEIVERS. 14.) CONTRACTOR SHALL COORDINATE ALL ELECTRICAL INSTALLATIONS WITH EVERSOURCE AT (800) 662-7764. ALL ELECTRIC CONDUIT INSTALLATION SHALL BE INSPECTED BY EVERSOURCE PRIOR TO BACKFILL A 48-HOUR MINIMUM NOTICE IS REQUIRED. 23.) CONTRACTOR TO TRANSFER TEMPORARY BENCHMARK TO A SUITABLE BENCHMARK TO CONTROL CONSTRUCTION. ANY ELEVATION DISORCEANCIES ARE TO BE REPORTED TO THE THE DESIGN ENGINEER IMMEDIATELY. 15.) CONTRACTOR SHALL CODRDINATE ALL TELECOMMUNICATIONS INSTALLATIONS WITH FAIRPOINT COMMUNICATIONS AT (603) 427-5525 CGS BOUND ~FND~ FLUSH CGS BOUN EDGE OF POORLY DRAINED EX. STREAM LLC UTILITY PLAN

21 FARMINGTON ROAD I.

M COOK DEVELOPMENT LL.
FARMINGTON ROAD
ROCHESTER, N.H.

X MAP 216, LOT 29 ...N N N PROPOSED BANK FF = 255.40-AND FOR: SURVEYING
ENGINEERING
CROWN POINT ROAD
IH 03825 (603)332-2863 1-PROP. CATCH BASIN #3 TIE INTO EXISTING SEWER STUB PROP. DRAIN MANHOLE 815 - EXIST. EDGE OF PAVEMENT EX. CURB EX. WATER LINE HYDRANT. 8 & ST SECOND C. 335 SECOND C. SCALE : CONTRACTOR NH (CONTRACTOR) EWL -EWL -PROPOSED EDGE OF 10' SHOULDER OF ME BERRY CONTRACTOR TO COORDINATE AND INVESTIGATE EX. SIZE OF LINES COORDINATE WITH ARCHITECT IF A FIRE LINE IS REQUIRED - EX. 8" SEWER LINE L=133.30', S= 0.0093'/. - FX 8" SEWER LINE L=280.21', 5= 0.02'/ N.H. ROUTE 11/ FARMINGTON ROAD NEW HAMA EXISTING SMH
RIM = 254,06
INV. IN = 244,26
INV. OUT = 244,10 KENNETH A. BERRY No. 14748 GRAPHIC SCALE LICENSED (IN FEET)

1 inch = 20 ft.



NOTES

- CALL DIG SAFE PRIOR TO BEGINNING WORK. (1-888-344-7233). THE LANDSCAPE CONTRACTOR IS ADVISED OF THE PRESENCE OF UNDERGROUND UTILITIES AND SHALL VERIFY THE EXISTENCE AND LOCATION OF THE SAME BEFORE COMMENCING AND DIGGING OPERATIONS. THE LANDSCAPE CONTRACTOR SHALL REPLACE OR REPAIR UTILITIES, PAVING, WALKS, CURRING, ETC DAMAGED IN PEFFORMANCE OF THIS JOB AT NO ADDITIONAL COST TO THE OWNER OR GENERAL CONTRACTOR.
- CONTRACTOR SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH ALL SITE CONDITIONS PRIOR TO CONSTRUCTION BIDDING.
- THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTINGS SHOWN ON THE DRAWINGS. VARIATIONS IN QUANTITIES ARE TO BE APPROVED BY THE DESIGN ENGINEER.
- PROVIDED SMOOTH TRANSITION WHERE NEW WORK MEETS EXISTING CONDITIONS.
- ALL PLANT MATERIAL INSTALLED SHALL MEET THE SPECIFICATIONS OF "AMERICAN STANDARD FOR NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN
- ALL PLANT MATERIALS SHALL BE FREE FROM INSECTS AND DISEASE.
- ALL PLANTINGS SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING STAKING OR GUYING, WARPIPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNTIL ACCEPTANCE FROM OWNER.
- ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF EXISTING AND NEWLY PLANTED TREES AND SHRUBS DURING THE CONSTRUCTION PROCESS. WHERE REDUIRED, THE CONTRACTOR SHALL INSTALL TEMPORARY FENCING (SNOW OR EQUAL) AROUND EXISTING TREES AND SHRUBS THAT COULD BE IMPACTED BY THE CONSTRUCTION PROCESS. STORAGE OF CONSTRUCTION EQUIPMENT, CONSTRUCTION MATERIALS, SNOW STORAGE AND OR VEHICLE PARKING SHALL NOT BE PERMITTED WITHIN THE DRIP LINE OF TREES OR TWENTY FEET WHICH EVER IS GREATER.
- NEW PLANTINGS SHALL BE INSTALLED PER PROJECT DRAWINGS AND SPECIFICATION THAT INCLUDE FERTILIZATION AND MULCHING AS REQUIRED.
- TREES ALONG THE RIGHT OF WAY ARE TO BE REGULARLY PRUNED SO THAT THERE ARE NO BRANCHES BELOW 8', TO NOT IMPEDE SIGHT DISTANCE.

- 12. WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR GROUND COVER AND PERENNIAL BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL TWO PARTS SPHACNUM PEAT MOSS, AND ONE PART HORTICULTURAL PERLITE BY VOLUME. PEAT MOSS MAY BE SUBSTITUD WITH WELL—ROTTED OR DEHYDRATED MANURE OR COMPOST, ROTOTILL BEDS TO A DEPTH OF BENIFICE.
- 13. MAINTENANCE OF NEW PLANTINGS AND LAWNS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR AND OR LANDSCAPE SUBCONTRACTOR UNTIL ACCEPTANCE BY THE OWNER. RESPONSIBILITIES SHALL INCLUDE WATERING WEEDING AND MOWING AS NECESSARY. ALL PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE, REPLACEMENT MATERIAL SHALL BE GUARANTEED FOR AND ADDITIONAL YEAR FROM TIME OF INSTALLATION.
- 14. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY EROSION CONTROL MEASURES DURING THE CONSTRUCTION PHASE AND UNTIL ALL AREAS HAVE BEEN STABILIZED AND ACCEPTED BY THE OWNER. THE GENERAL CONTRACTOR SHALL PROVIDE WEEKLY INSPECTIONS OF EROSION MEASURE AND IMMEDIATELY AFTER STORM EVENTS AND REPAIR AS NECESSARY.
- 15. THE GENERAL CONTRACTOR AND OR THE LANDSCAPE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL THIREE GUYING MATERIAL ONCE PLANT MATERIAL HAS BEEN ESTABLISHED. (MIMIMUM OF ONE GROWING SEASON). ALL TEMPORARY EROSION CONTROL MEASURE SHALL BE REMOVED ONCE STABILIZATION OF DISTURBANCE HAS BEEN ACCEPTED BY OWNER.
- 16. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM OF TWO MOWINGS FOR ALL TURF AREAS OR UNTIL ACCEPTANCE BY THE OWNER. A MINIMUM UNIFORM 75% CATCH OF TURF IS REQUIRED FOR ACCEPTANCE.
- ALL PLANTINGS SHALL BE WATERED REGULARLY DURING THEIR FIRST YEAR AND MAINTAINED PERMANENTLY IN GOOD GROWING CONDITION AS AN EFFECTIVE VISUAL SCREEN.
- 18. SHRUBS OR TREES WHICH DIE SHALL BE REPLACED WITHIN ONE GROWING SEASON WITH NEW SHRUBS OR TREES TO ENSURE CONTINUED COMPLIANCE WITH APPLICABLE LANDSCAPING
- ALL REQUIRED LANDSCAPING SHALL BE INSTALLED BEFORE OCCUPANCY, OR WITHIN SIX MONTHS IF OCCUPANCY OCCURS DURING WINTER CONDITIONS.
- 20. ALL PLANT STOCK SHALL CONFORM TO ANSI Z260.1 NURSERY STOCK, LATEST EDITIONS (AMERICAN ASSOCIATION OF NURSERYMEN, INC.)

- PLANT-PIT BACK-FILL SHALL BE MIXED AT A RATE OF 7 PARTS OF TOPSOIL TO 2 PARTS OF DEHYDRATED COW MANURE. SLOW RELEASE FERTILIZER SHALL BE APPLIED AS PER MANUFACTURERS RECOMMENDATIONS. USE EXISTING ON—SITE TOPSOIL AS PART OF BACK FILL WHEN AVAILABLE.
- ALL LANDSCAPED AREAS NOT PLANTED WITH TREES, SHRUBS OR GROUNDCOVER SHALL BE RESTORED WITH SEED OR SOD AS INDICATED ON PLANS.
- 23. TOPSOIL WILL BE TESTED FOR FERTILIZATION REQUIREMENTS, AND SLOW RELEASE ENVIRONMENTALLY FRIENDLY FERTILIZER WILL BE APPLIED AT THE RECOMMENDED RATES.
- 24. ALL DISTURBED WETLAND BUFFER AREAS, EXCEPT FOR AREAS THAT ARE PART OF THE DRAINAGE SYSTEM, ARE TO BE RESEEDED WITH A CONSERVATION SEED MIX AND ONLY MOWED TWICE PER YEAR.
- 25. ALL PLANT SUBSTITUTIONS MUST BE APPROVED BY THE ENGINEER.
- 26. PLANTS FURNISHED IN CONTAINERS SHALL HAVE THE ROOTS WELL ESTABLISHED IN THE SOIL MASS AND SHALL HAVE AT LEAST ONE (1) GROWING SEASON. ROOT-BOUND PLANTS OR INADEQUATELY SIZED CONTAINERS TO SUPPORT THE PLANT MAY BE DEEMED UNACCEPTABLE.
- 27. ALL PLANTS SHALL BE GUARANTEED BY THE CONTRACTOR FOR NO LESS THAN ONE FULL YEAR FROM THE TIME OF INSTALLATION. DURING THIS TIME, THE OWNER SHALL MAINTAIN ALL PLANT MATERIALS IN THE ABOVE MANNER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT THE PLANTS TO ENSURE PROPER CARE. IF THE CONTRACTOR IS DISSATISFED WITH THE CARE GIVEN, HE SHALL IMMEDIATELY, AND IN SUFFICIENT TIME TO PERMIT THE CONDITION TO BE RECTIFIED, NOTIFY THE OWNER IN WRITING OR OTHERWISE FORFEIT HIS
- 28. BY THE END OF THE GUARANTEE PERIOD, THE CONTRACTOR SHALL HAVE REPLACED ANY PLANT MATERIAL THAT IS MISSING, NOT TRUE TO SIZE AS SPECIFIED, THAT HAS DIED, THAT HAS DIED, THAT HAS DIED THAT HAS DIE
- 29. THE CONTRACTOR IS TO USE TEMPORARY MEASURES FOR WATERING PLANTS DURING THE ESTABLISHMENT PERIOD. INCLUDING CONNECTING TEMPORARY HOSES TO THE STRUCTURE WATER SUPPLY LINE AND UTILIZING SPRINKLERS UNTIL 85% GROWTH OCCURS.
- 30. A MULCH BED IS TO BE INSTALLED IN A 6' RADIUS AROUND THE PROPOSED TREE. THE REMAINING AREA IS TO BE LOAMED AND SEEDED.
- 31. TREES ARE TO BE 6' TALL AT PLANTING.
- 32. ALL UNPAVED AREAS SHALL BE LOAMED AND SEEDED.

I. CONTRACTOR SHALL OBTAIN APPROVAL FROM LA. PRIOR TO PURCHASHIG &/OR INSTALLING SUGSTITUTE PLANT MATERIAL FROM TO PURCHASE OF ANN SUBSTITUTE MATERIALS.

2. CONSTRUCTION ACCESS WILL BE AS EMPECTED BY LA. CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF ACCESS ROUTE AND ALL AREAS DISTURBED BY PLANING OPERATIONS UPON COMPLETION OF CONSTRUCTION CEPERATIONS, AT NO ADDITIONAL COST TO THE OWNER.

S. LAYOUT OF ALL PLANTING BEDS AND LOCATION OF PLANTS TO BE APPROVED BY LA ON SITE PRIOR TO CONSTRUCTION AND INSTALLATION.

I CONTRACTOR IS RESPONSIBLE FOR MAKING SURE ALL PLANT MATERIAL HAS AGECUATE WATER DURING THE ESTABLISHMENT PERIOD.

2. THE USE OF GATOR BACS, SOAKER HOSE, HAND WATERING AND OTHER TECHNICIES SHOULD BE USED TO ASSURE PROPER HYDRATION OF THE PLANTINGS IS MAINTAINED.

PLANTING SCHEDULE 21 Farmington Road Botanical Name / Common Name

Trees	Size	Qty	Labe
Plantanus acerifolia/London Planeiree	3" Cal.	2	PA
Acer Rubrum / Red maple	3" Cal.	6	AR
Quercus rubra / Red Oak	3" Cal.	5	QR
Shrubs			
Syringa pubescens / Miss Kim Lilac	#3 3-4"	2	MK
Cornus sanguina 'Winter Flame' / Winter Flame Dogwood	2-318&8	2	CS
Perennials			
Hemerocallis 'Big Time Happy' / Big Time Happy Daylily	#1	22	HD
Hememorallis "Pandon Me" / Pandon Me Daviily	M4	22	PM



General Plant Maintenance Guide

General Plant Bed Malnumance:

All plant matriterance should be performed by a qualified incrtaulturalist or literates entorist. Cleaning the clear are personant inches, and was provident by a submitted for the shading up around the plants and in more cases indirected ovide the personal pode in the "fill helps takep) litter from shading up around the plants and in more cases failing the plants. Washing the file they are identify all yearleds will said grat the plants established, Mulching overy year hard necessary. Shading the def washind and suring its own of all that is needed, him executary only install onto lated of world and do not place the walch doesn'then 3" to the rounks or same of woodly plants.

The first year wetering during any periods will be not peace.

If notice of review retrieved in the must indust be seen a society from the trains.

If notice of review retrieved in the must indust be seen a society from the trains.

For the first period of the first peace of the first peace have stropped their sense for the year.

Furthering the other peace year.

Depending on the smooth of extrapection the bed and a recover, deep root densities many be needed.

Grasses only specific isocilipsed back at the end of the growing scason and all the clippings removed from the gras. On one over resids. Too reach resids will prohibit, the grass from developing Ima a strong clump.

- 311 kast hit mud keptimen nh 33229


EYING SINEERING I POINT ROAD I (603)332–2863 ALS 20 FT. SECOND SECOND IGTON, N BER


PLAN TON ROAD LOPMENT L ROAD N.H.


LANDSCAF
OF: 21 FARN
NM COOK I
FARMING
ROCHES
TAX MAP


-AND FOR:














AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8" THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A MAXIMUM 6' APART, AND DRIVEN A MINIMUM OF 16" INTO THE

RROUND.

WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY-PASSING. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF, SEE MAINTENANCE NOTE BELOW, REMOVAL OF SEDIMENT REQUIRED AT A DEPTH OF 6-INCHES.

PLACE THE ENDS OF THE SILT FENCE UP CONTOURT TO PROVIDE FOR SEDIMENT STORAGE. SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER.

THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED.

TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, SILT FENCE, PAGE 90.


SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL, ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE

F THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING

THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.
SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH SIX-INCHES IN DEPTH.
SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND

SILT FENCE DETAIL


E5 STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE



PLAN VIEW

NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY

STONE CHECK DAM



CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH.

UNILLIED TO THE SWALE OR DRAINAGE DITCH.

THE MAXIMUM CONTRIBUTION DRAINAGE AREA TO THE DAM SHOULD BE LESS THEN ONE ACRE.

THE MAXIMUM HEIGHT OF THE DAM SHOULD BE TWO FEET.

THE CENTER OF THE DAM SHOULD BE AT LEAST SIX INCHES LOWER THAN THE OUTER EDGES.

THE MAXIMUM SPADING IS AS SHOWN ON THE PROJECT SITE PLANS.

PLANS.
CHECK DAMS WILL NOT BE USED IN A FLOWING STREAM.
TEMPORARY CHECK DAMS WILL BE REMOVED ONCE THE
SWALE OR DITCH IS DETERMINED STABLE.
TO BE CONSTRUCTED IAW NH SMM #3 4-2 SEDIMENT
CONTROL PRACTICES, TEMPORARY CHECK DAMS, PAGE 114.

2"-3"
ANGULAR STONE 5
FLOW 24

STONE GRADE STABILIZATION STRUCTURE

E2 CATCH BASIN OK STONE TO ALLOW-DAYLIGHT DRAINAGE OUTLET PIPE 2.0 Maranananan TABLE 7-24-RECOMMENDED RIP RAP GRADATION RANGES FEET SIZE OF STONE (INCHES) % OF WEIGHT SMALLER THAN THE GIVEN d50 SIZE 50%

1. CONSTRUCT THE LEVEL SPREADER LIP ON A 0% GRADE TO INSURE UNIFORM SPREADING OF RUNOFF.

2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON FILL.

3. THE ENTIRE LEVEL LIP AREA SHALL BE PROTECTED BY PLACING EXCELSIOR ENFORCER MATTING BENEATH THE STONE. EACH STRIP SHALL OVERLAP BY AT LEAST SIX INCHES. 4. THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.

5. MAINTENANCE: THE LEVEL SPREADER SHOULD BE CHECKED PERIODICALLY AND AFTER EVERY MAJOR STORM TO DETERMINE IF THE LIP HAS BEEN DAMAGED AND THE DESIGN CONDITIONS HAVE NOT CHANGED. ANY DETRIMENTAL SEDIMENT ACCUMULATION SHOULD BE REMOVED, IF STONE REMOVAL HAS TAKEN PLACE ON THE LIP, THEN THE DAMAGE SHOULD BE REPAIRED.

E7

STABILIZED.

FILTREXX SEDIMENT

BLOCK AND GRAVEL DROF

6 REFERENCE IS MADE TO NHDES SWM VOL. 2, 4-6, STONE BERM LEVEL SPREADERS, PAGE 162

STONE BERM LEVEL SPREADER NOT TO SCALE

-FROSION CONTROL MIX

1'-0" MIN.

EROSION CONTROL MIX BERM

'-0" MIN

ION CONTROL MIX BERMS SHALL BE USED ONLY AS FOLLOWS: BERMS SHALL BE USED IN AREAS WHERE EROSION WILL OCCUR ONLY IN THE FORM OF SHEET REDSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY

THE BERMS SHALL BE INSTALLED FOLLOWING INC COMMON OF THE LAND BY ARROLD FOR POSSIBLE.

THE BERMS SHALL BE INSTALLED ON SLOPES LESS THAN 5%.
SUBJECT TO (E), BELOW, THE MIX SHALL HAVE AN OPGANIC PORTION BETWEEN 80 AND 100%, DRY WEIGHT BASIS, AND BE FIBROUS AND ELONGATED SUCH AS FROM SHEEDDED BARK, STEWAY GENDRINGS, COMPOSED BARK, OF EQUIVALENT MANUFACTURED PROPULCTS.
WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS SHALL NOT BE USED AS ORGANIC MATERIAL.
THE MIX SHALL HOT CONTAIN SILTS, CLAY, OR FINE SANDS.
THE MIX SHALL HAVE A PARTICLE SIZE BY WEIGHT OF 70 TO 85% PASSING A 6—INCH SCREEN AND A MAXIMUM OF 85% PASSING THE 0.75—INCH SCREEN.
THE MIX SHALL HAVE A ENTWEEN 50 AND 8.0

THE BERM SHALL BE AT LEAST 12 INCHES HIGH AND AT LEAST 2 FEET WIDE.
TO BE CONSTRUCTED IAW NH SWM #3 4—2 SEDIMENT CONTROL PRACTICES, EROSION CONTROL MIX BERMS, PAGE 106.

BOVE THE BERM. HE BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSLY AS

CONSTRUCT AT

ANGLE OF REPOSE

EXISTING GRADE

NOT TO SCALE

GRASS TREATMENT SWALE NOT TO SCALE

INSPECT ANNUALLY FOR EROSION, SEDIMENT ACCUMULATIONS, VEGETATIÓN LOSS, & INVASIVE SPECIES. REPAIR AS NECESSARY.

MOW GRASS ANNUALLY TO A DEPTH OF 4".

MAINTENANCE

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS MADE AS NECESSARY. SEDIMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDIMENT HAS REACHED A MAXIMUM OF ONE HALF THE DEPTH OF THE TRAP. THE SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM EROSION BY EITHER STRUCTURE OR VEGETATIVE MEANS. THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE CONTRIBUTING DRAINAGE AREA TO THE INLET HAS BEEN COMPLETELY


BLOCK & GRAVEL DROP


INLET SEDIMENT FILTER

NOT TO SCALE

E3

TO BE CONSTRUCTED IAW NH SWM #2 CHAPTER 4, #5 TREATMENT SWALES, PAGE 123.





CONSTRUCTION SAFETY FENCE

ALL SENSITIVE AREAS SHALL BE PROTECTED AS PER PLAN.
 ALL TREES IN THE CONSTRUCTON AREA NOT SPECIFICALLY DESIGNATED FOR REMOVAL SHALL BE PRESERPED AND PROTECTED WITH HOM SMBILLY STEEL OUTSIDE OF THE DRIP LINE OF THE THEE.
 WHEN PRACTICABLE, MOSTALL HOW, MSBILLY STEEL OUTSIDE OF THE DRIP LINE OF THE THEE.
 THE TREENOR MUST REMAIN IN PLACE DIRENCE ALL PHASES OF CONSTRUCTION; ANY CHANGE OF THE SHOTTCTUFF FENCING MUST BE APPROVED.

E8

. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME.

ERCSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER.

ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4° OF LOAM AND SEEDED WITH NOT LESS THAN ONE POUND OF SEED PER SO SQUARE YAPOS OF AREA. (SEE SEED SPECIFICATIONS THIS SHEED

ALL DISTURBED AREAS WILL BE RESTABILIZED WITHIN 45 DAYS. AT ANY ONE TIME, NO MORE THAN 5 ACRES, (217,800 Sq. ft.) WILL BE DISTURBED.

SILT FENCES AND PERIMETER BARRIERS SHALL BE INSPECTED PERIODICALLY AND AFTER EVERY RAIN DURING THE LIFE OF THE PROJECT, ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF.

AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED. THE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VECTATED.

DD NOT TRAFFIC EXPOSED SOIL SURFACES WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED CUTSIDE THE LIMITS OF THE INFILTRATION SYSTEM.

O. DRIVEWAYS AND CUT AND FILL SPLOPES MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINAL GRADE.

12. THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

3. THE NHDES STORMWATER MANUAL, IN THREE VOLUMES, DATED DECEMBER 2008, IS A PART OF THIS PLAN SET AND THE MORE RESTRICTIVE WILL GOVERN, (NH SWM)

TEMPORARY EROSION CONTROL MEASURES

PER THE EPA CCP REQUIREMENTS THERE WILL BE REPORTS OF THE EPOSION CONTROL INSPECTIONS NAW SAMPP PREPARED BY BS&C. ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.25° OR GREATER PAIN EVENT.


DITCHES, SWALES, AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.

11 STABILIZATION MEANS:

11.1. A MINIMUM OF 85% OF VEGETATIVE COVER HAS BEEN ESTABLISHED.
11.2. A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED, OR
11.3. EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.

E11

TO BE USED IN ALL AREAS WHERE THERE WILL BE NO TRAFFIC.



RECOMMENDED MAINTENANCE SCHEDULE
-EACH SILTSACK SHOULD BE INSPECTED AFTER EVERY MAJOR RAIN EVENT, AND MUST BE MAINTAINED.

-IF THERE HAVE BEEN NO MAJOR EVENTS, SILTSACK SHOULD BE INSPECTED EVERY 2-3 WEEKS.

-TO BE USED IN ALL AREAS WHERE THERE WILL BE

TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.

SILTSACK DETAIL


RIN ROA)332-URVEYING-ENGINEER CROWN POINT 8 335 RRIN($_{\Omega}$ BA NEW HAY KENNETH

DETAILS LLC LLC

SEDIMENT C 21 FARMINGTI I COOK DEVEL FARMINGTON R ROCHESTER, I

OSION AND FOR:

A. BERRY No. 14743



2"X2"X36" WOODEN STAKES PLACED 10' D.C. (SEE SECTION) FILTREXX SOXX (12" TYPICAL) AREA TO BE PROTECTED

S LIL MATERIAL TO MEET FILTREXX SPECIFICATIONS. ILLER MEDIA FILL TO MEET APPLICATION REQUIRMENTS. SOMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER. SILTSOXX MAY BE USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT

BARRIERS.
SILTSOXX COMPOST/SOIL/RODX/SEED FILL MATERIAL SHALL BE ADJUSTED AS
NECESSARY TO MEET THE REQUIRMENTS OF THE SPECIFIC APPLICATION.
FILTEXXX SOXX IS A REGISTREED TRADMARK OF FILTEXXX INTERNATIONAL, LLC.
SILT FENCE IS NOT A SUBSTITUTION FOR SILT SOXX AND ANY EDUAL
SUBSTITUTION TO BE APPROVED.
TO BE CONSTRUCTED IAW FILTREXX, SECTION 1:EROSION & SEDIMENT CONTROL
(PAGE 323) — CONSTRUCTION ACTIVITIES, SWPPP CUT SHEET. FILTREXX
SEDIMENT CONTROL.

NOT TO SCALE 3.0" 2"X2"X36" WOODEN STAKES PLACED 10' O.C. HARDWOOD - FILTREXX SOXX SILT FENCE-BLOWN/PLACED FILTER MEDIA-AS NOTED) AREA TO BE PROTECTE MANAMANAMANAMANAMA

Filtrexx International, LLC 35481 Grofton Eastern Rd | Grofton, Oh 44044 440–926–2607 | fax: 440–926–4021 WW.FLTREXX.COM OR APPROVED EQUAL

TO BE CONSTRUCTED IAW NH SWM #3 4-2 SEDIMENT CONTROL PRACTICES, TEMPORARY STORM DRAIN INLET PROTECTION, PAGE 118.

NOTE: FOR AREAS REQUIRING DOUBLE PERIMETER CONTROL WITHIN 50' OF JURISDICTIONAL WETLAND AND NOT FOR ALL SILT SOXX APPLICATIONS. THIS DUPLICATION MAY BE SPECIFIED AS 12" SILT SOXX OR ORANGE CONSTRUCTION FENCE AS NOTED.

 $\underline{SECTION}$ NOT TO SCALE


LIFTING STRAPS

-THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF CORD IS COVERED WITH SEDIMENT, THE SILTSACK SHOULD BE EMPTIED.

- ARE SUBJECT TO DAMAGE BY SNOW PLOWS, AND MUST BE INSPECTED AFTER ANY SNOW EVENT AND REPLACED AS REQUIRED.

E - 101

SHEET 17 OF 24



ELEVATION

OVERLAP EDGES

REQUIRED TO SHOW DETAIL, BUT DO NOT OMEND USE OF HAY BALES FOR EROSION

E13 PIPE OUTLET PROTECTION NOT TO SCALE DTE : GEOTEXTILE FABRIC DR FILTER MATERIAL TO BE PLACED BETWEEN RIP RAP AND SOIL. Lo --La-

222 SECTION A-A SECTION A-A PIPE OUTLET TO FLAT AREA WITH NO DEFINED CHANNEL

PIPE OUTLET TO WELL-DEFINED CHANNEL

NOTE: THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES. SEEDING RATES

A. TALL FESCUE CREEPING RED FESCUE RED YOP TOTAL

TALL FESCUE
CREEPING RED FESCUE
CROWN VETCH
OR
FLAT PEA
TOTAL

C. TALL FESCUE
CREEPING RED FESCUE
BIRDS FOOT TREFOIL
TOTAL

CREEPING RED FESCUE 1/ 50
KENTUCKY BLUEGRASS 1/ 50
100

D. TALL FESCUE FLAT PEA

NOTE: Temporary seed mix for stabilization of turf shall be winter rye or oats at a rate of 2.5 lbs. per 1000 s.f. and shall be placed prior to OCT. 15, if permanent seeding not yet complete. SEEDING GUIDE SEEDING WELL MIXTURE 1/ DROUGHTY DRAINED FAIR EXCELLENT EXCELLENT 2/ FAIR EXCELLENT EXCELLENT 2/ GRAVEL PIT, SEE NH-PM-24 IN APPENDIX FOR RECO

1/ REFER TO SEEDING MINTURES AND RATES IN TABLE 7-38.
Z/ POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREA AND ATHLETIC FIELDS.

GRADING AND SHAPING SLOPES SHALL NOT BE STEEPER THAN 2:1;3:1 SLOPES OR FLATTER ARE

A SLOPES SHALL NOT BE STEEPER THAN 2:13:71 SLOPES OR FLATTER ARE
PREFERRED.
WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED.
SECEDBED PREPARATION
A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM
THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.
B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE PEMOVED BECAUSE
THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA. WHERE
FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO
PREPARE A SEED BED AND MIX FERTILIZER AND LIME INTO THE SOIL. THE SEEDBED
SHOULD BE LEFT IN REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE
OPERATION SHOULD BE PEFFORMED ACROSS THE SLOPE WHEREVER PRACTICAL
ESTABLISHING A STAND
A LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF

LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF

THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED:
AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR LODIES. PER 1,000 SO.FT. NITROGEN(N), 50LBS, PER ACRE OR 1.1LBS, PER 1.000 SQ.FT.

PHOSPHATE(P205), 100LBS. PER ACRE OR 2.2LBS. PER 1,000 SQ.FT. POTASH(KZO), 100LBS, PER ACRE OR 2.2LBS, PER 1,000 SQ.FT.

OR 1,000LBS. PER ACRE OF 5-10-10.)

NAG BIONET SC 150 BN 2:1 TO 1:1 SLOPE

TO BE CONSTRUCTED IAW NH SWM #3 4-1 EROSION CONTROL PRACTICES, TEMPORARY EROSION CONTROL BLANKET, PAGE 56.
ANCHOR PATTERN AND INSTALLATION INSTRUCTIONS FROM NORTH AMERICAN GREEN (NAG) AND AMERICAN EROSION COMPANY (AEC) WILL BE FOLLOWED FOR EACH APPLICATION AND SLOPE CONDITIONS WILL APPLY.

SEEDING AND INCORPORATED INTO THE SOIL KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS, WHEN A SOIL TEST IS NOT

(NOTE: THIS IS THE EQUIVALENT OF SDOLBS, PER ACRE OF 10-20-20 FERTILIZER

SEEDING SPECIFICATIONS

CONSERVATION MIX POUNDS PER ACRE TALL FESCUE (35%) CREEPING RED FESCUE (25%) 15 ANNUAL RYEGRASS (12%) 5 PERENNIAL RYEGRASS (10%) 5 KENTUCKY BLUEGRASS (10%) 15

POUNDS POUNDS PER PER ACRE 1,000 Sq. Ft.

40 OR 55 0.95 OR 1.35

20 30

0.45 0.45 0.05

0.45 0.75 1.20

B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE.

METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING, WHERE BROADCASTING IS

USED, COVER SEED WITH .25 INCH OF SOIL OR LESS. BY OLLTIPACKING OR RAKING.

G. REFER TO TABLE(G-E THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-EI THIS

SHEET) FOR RATES OF SEEDING. ALL LEGUIDES (CROWNNETCH, BIRDSFOOT TREFOIL, AND

FLATTEA) MUST BE INOCULATED WITH THEIR SPECIFIC INDOCULANT.

D. WHEN SEEDED AREAS ARE MULCHED. PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY

COTOBER. WHEN SEEDED AREAS ARE NOT MULCHED. PLANTINGS SHOULD BE MADE FROM

EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.

4. MULCH . A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER

SECURD.

SECURD:

B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 901BS PER MAINTENANCE TO ESTABLISH A STAND

A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE

WEED GROWTH.

B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.

C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL HOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

TO BE CONSTRUCTED IAW NH SWAM #3 4-1 EROSION CONTROL PRACTICES, PERMANENT VEGETATION, PAGE 60.

INSTALL ROLLED EROSION CONTROL BLANKET WITH ANCHOR HOOKS AS PER MANUFACTURES REQUIREMENTS. SUBMIT SHOP DRAWINGS FOR

ANCHOR HOOK PER

MANUFACTURER'S REQUIREMENTS

4" TOPSOIL (MIN.) AND SEED TO ESTABLISH GROWTH

APPROVAL.

ROLLED EROSION CONTROL BLANKET (RECB) SLOPE STABILIZATION DETAIL

NOT TO SCALE

PIPE OUTLET PROTECTION CONSTRUCTION SPECIFICATIONS

- . THE SUB GRADE FOR THE FILTER MATERIAL, GECTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS. SPECIFIED GRADATION.
- 2. THE ROCK OR GRAVEL USED FOR FILTER OF RIP RAP SHALL CONFORM TO NHDOT
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- 4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN DIVE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.
- 5. TO BE CONSTRUCTED IAW NH SWM #2 4-6 CONVEYANCE PRACTICES, 6. OUTLET PROTECTION, PAGE 172.

E14

d50 SIZE=	0.5	FEET	6	INCHES
% OF WEIGHT !		SIZE OF	STONE	(INCHES)
100%		9		12
85%		8		11
50%		6		9
15%		2		3

E17 CONSTRUCTION SEQUENCE:

- 1.) CUT AND REMOVE TREES IN CONSTRUCTION AREA ONLY AS REQUIRED, RELOCATE ANY PROJECT T.B.M.
- 2.) CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SEDIMEN" EROSIGN AND DETENTION CONTROL FACILITIES AS SPECIFIED, EROSIGN AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY SOIL LAND DISTURBANCE AND MUST BE REMEMBED AND APPROVED BY THE COMMUNITY SERVICES EXPERIMENT.
- EROSION, SEDIMENT AND DETENTION CONTROL FACILITY SHALL BE INSTALLED & STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.TEMPORARY DIVERSIONS MAY BE PROJIECE. POST CONSTRUCTION STORM WATER MANAGEMENT PRACTICES MUST BE INITIATED AND STABILIZED EARLY IN THE PROCESS.
- 4.) CLEAR, CUT AND DISPOSE OF DEBRIS IN APPROVED FACILITY
- 5.) CONSTRUCT TEMPORARY CULVERTS AS REQUIRED, OR DIRECTED
- 6.) CONSTRUCT FOADWAYS FOR ACCESS TO DESIRED CONSTRUCTION AREAS, ALL ROADS SHALL BE STABILIZED IMMEDIATELY
- 7) START BUILDING CONSTRUCTION
- B.) INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. INSTALL RAIN GARDENS. ALL DISTURBED AREAS SHALL STABILIZED IMMEDIATELY AFTER GRADING.
- 9.) BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING, ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SE MULCHED AS REQUIRED, OR DIRECTED. NO AREA IS ALLOWED TO BE DISTURRED FOR A LENGTH OF TIME THAT EXCEDS 80 D BEING STRBUZED, DAILY, OR AS REQUIRED. ALL RODAWAYS AND PARKING AREAS SHALL BE STRBUZED WITHIN 72 HOURS OF FINISHED GRADES.

 GRADES.
- 10.) CONSTRUCT TEMPORARY BERMS, DRAINS DITCHES, SILT FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.
- 11.) INSPECT AND MAINTAIN ALL EROSION AND SEDMENT CONTROL MEASURES DURING CONSTRUCTION. ALL SWEPP INSPECTIONS MUST BE CONDUCTED BY A QUALIFIED PROFESSIONAL SUCH AS A PROFESSIONAL ENGINEER (PE), A CERTIFIED PROFESSIONAL IN EROSION AND SEDMENT ONNTROL CONTROL (CPESS). A CERTIFIED PROFESSIONAL IN SECTION SEDMENT AND STORM WATER (MASSEM), OR A CERTIFIED PROFESSIONAL IN STORM WATER QUALITY (CPESMO), INSPECTION REPORTS SHALL BE SUBMITTED TO THE COMMUNITY SERVICES DEPARTMENT.
- 12.) COMPLETE PERMANENT SEEDING AND LANDSCAPING
- 13.) REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE COMPLETE.
- 14.) SMOOTH AND REVEGETATE ALL DISTURBED AREAS.
- 15.) FINISH PAVING ALL ROADWAYS.

E 18 DEFINITION OF STABLE:

PER ENV-WO 1500 ALTERATION OF TERRAIN

- BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED.
 A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED..
 A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP—RAP HAS BEEN INSTALLED.

ADDITION STABILIZATION NOTES:

- HAY MULCH OR OTHER APPROVED METHODS SHALL BE USED TO CONTROL EROSION OF NEWLY GRADED AREAS. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS AFTER THEIR CONSTRUCTION, DISTURBED SOIL AREAS SHALL BE EITHER TEMPORARILY OR PERMANENTLY STABILIZED. IN AREAS WHERE FINAL GRADING HAS NOT OCCURRED, TEMPORARY STABILIZATION MEASURES SHOULD BE IN PLACE WITHIN SEVEN (7) CALENDAR DAYS FOR EXPOSED SOIL AREAS THAT ARE WITHIN ONE HUNDRED (100) FEET OF A SURFACE WATER BODY OR A WETLAND AND NO MORE THAN 14 CALENDAR DAYS FOR ALL OTHER AREAS, PERMANENT STABILIZATION SHOULD BE IN PLACE WITHIN THEE (3) CALENDAR DAYS FOLLOWING COMPLETION OF FINAL GRADING OF EXPOSED SOIL AREAS.

E22

WINTER STABILIZATION NOTES

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VECETATIVE COVERAGE PRIOR TO OCTOBER 15TH SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT APE NOT DIRECTED TO SWALES OR DETENTION BASINS, SHALL BE LINED WITH BIODEGRADABLE, PHOTODEGRADABLE "JUTE MATTING" (EXCELSIOR'S CURLEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL APEAS WILL BE STABILIZED, AS DIRECTED ABOVE.

ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPOPARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPPRAF WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SCON AS THEY ARE PROPERTY GRADED AND SHAPED.

3. PRIOR TO OCT. 15TH ALL POADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS' ELEVATIONS ARE PROPOSED TO REMAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE POUGHTY CROWNED AND A 3" LAYER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND WILL REQUOE ROADWAY EROSION. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 304.3, BUT SHALL HAVE BETWEEN 15—25% PASSING THE #200 SIEVE AND THE LARGEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER OCTOBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERACE GPOWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT WILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH. ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT FENCING.

S H $_{\Omega}$ BA




E - 102


SHEET 18 OF 24


ROAD MENT 1 TON I 21 FAR COOK ARMING ROCHES AND FOR:

200

NEW HAW







6" CRUSHED GRAVEL

SLOPED GRANITE CURB

FINISHED GRADE

10

11


12

BANK RUN GRAVEL


NHDOT ITEM NO. 304.2

COMPACTED SUBGRADE

SLOPE GRANITE CURB DETAIL L



C11 LAMP "A" MOUNTED 10' ON BUILDING




CONSTRUCTION DETAILS
LAND OF: 21 FARMINGTON ROAD LLC
FOR: NM COOK DEVELOPMENT LLC
FARMINGTON ROAD
FARMINGTON ROAD
ROCHESTER, N.H.



C - 102

SHEET 20 OF 24



NOT TO SCALE


4.) SIZE OF DE-WATERING AREA TO BE 10' X 10', ADJUST SIZE DEPENDING ON VOLUME AND USE.


5.) ADDITIONAL BALES MAY BE USED TO INCREASE RETENTION AND FILTERING.

DE-WATERING BASIN

D-101

SHEET 21 OF 24





UNDISTURBED GROUND

PERENNIAL PLANTING DETAIL

TYPICAL POST & RAIL FENCE DETAIL

NOTES:

1. SCARIFY ROOT MASS OF CONTAINERIZED PLANT MATERIAL.

2. INSTALL CONTAINERIZED PLANTS AT FINSHED GRADE

3. TAMP PLANTING MIX FIRMLY AS PIT IS FILLED AROUND EACH PLANT BALL

4. OMIT COLLAR AROUND EACH SHRUB WHEN IRRIGATION SYSTEM IS PRESENT.

5. SOAK EACH PLANT BALL AND PIT IMMEDIATELY AFTER INSTALLATION.

CROWN HEIGHT IN INCHES ECOLAS MEDIAN WITH IN INCHES ECOLAS MEDIAN WITH IN FEET TO 12" MAX.

TO 12" MAX.

FINAL GRADE

TYPICAL PLANTING BED DETAIL

TYPICAL PLANTING BED PLAN

SHRUB & HEDGE PLANTING

L6

VOTES:

- .) CALL DIG SAFE PRIOR TO BEGINNING WORK. (1-888-344-7233). THE LANDSCAPE CONTRACTOR IS ADVISED OF THE PRESENCE OF UNDERGROUND UTILITES AND SHALL WERFY THE EXISTENCE AND LOCATION OF THE SAME BEFORE COMMENCING AND DIGGING OPERATIONS. THE LANDSCAPE CONTRACTOR SHALL REPLACE OR REPAIR UTILITIES, PAVING, WALKS, CURBING, ETC DAMAGED IN PERFORMANCE OF THIS JOB AT NO ADDITIONAL COST TO THE OWNER OR GENERAL CONTRACTOR.
- 2.) CONTRACTOR SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH ALL SITE CONDITIONS PRIOR TO CONSTRUCTION BIDDING. SEE NOTE XXX ON OVERALL SITE PLAN.
- 3.) PROVIDED SMOOTH TRANSITION WHERE NEW WORK MEETS EXISTING CONDITIONS.
- 4.) ALL PLANT MATERIAL INSTALLED SHALL MEET THE SPECIFICATIONS OF "AMERICAN STANDARD FOR NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
- 5.) ALL PLANT MATERIALS SHALL BE FREE FROM INSECTS AND DISEASE.
- 6.) ALL PLANTINGS SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING STAKING OR GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNTIL ACCEPTANCE FROM OWNER.
- 7.) ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING.
- 8.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF EXISTING AND NEWLY PLANTED TREES AND SHRUBS DURING THE CONSTRUCTION PROCESS. WHERE REQUIRED, THE CONTRACTOR SHALL INSTALL TEMPORARY FENCING (SNOW OR EQUAL) AROUND EXISTING TREES AND SHRUBS THAT COULD BE IMPACTED BY THE CONSTRUCTION PROCESS. STORAGE OF CONSTRUCTION EQUIPMENT, CONSTRUCTION MATERIALS, SNOW STORAGE AND OR VEHICLE PARKING SHALL NOT BE PERMITTED WITHIN THE DRIP LINE OF TREES OR TWENTY FEET WHICH EVER IS GREATER.
- 9.) NEW PLANTINGS SHALL BE INSTALLED PER PROJECT DRAWINGS AND SPECIFICATION THAT INCLUDE FERTILIZATION AND MULCHING AS REQUIRED.
- 10.) ALL SHRUB BEDS AND TREE PITS SHALL BE MULCHED WITH 3" CLEAN SHREDDED BLACK MULC
- 11.) WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR GROUND COVER AND PERENNIAL BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL, TWO PARTS SPHAGNUM PEAT MOSS, AND ONE PART HORTICULTURAL PERLITE BY VOLUME. PEAT MOSS MAY BE SUBSTITUTED WITH WELL-ROTTED OR DEHYDRATED MANURE OR COMPOST. ROTOTILL BEDS TO A DEPTH OF 8 INCHES.
- 12.) MAINTENANCE OF NEW PLANTINGS AND LAWNS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR AND OR LANDSCAPE SUBCONTRACTOR UNTIL ACCEPTANCE BY THE OWNER. RESPONSIBILITIES SHALL INCLUDE WATERING WEEDING AND MOWING AS NECESSARY. ALL PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE, REPLACEMENT MATERIAL SHALL BE GUARANTEED FOR AND ADDITIONAL YEAR FROM TIME OF INSTALLATION.
- 13.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY EROSION CONTROL MEASURES DURING THE CONSTRUCTION PHASE AND UNTIL ALL AREAS HAVE BEEN STABILIZED AND ACCEPTED BY THE OWNER. THE GENERAL CONTRACTOR SHALL PROVIDE WEEKLY INSPECTIONS OF EROSION MEASURE AND IMMEDIATELY AFTER STORM EVENTS AND REPAIR AS NECESSARY.
- 14.) THE GENERAL CONTRACTOR AND OR THE LANDSCAPE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL THREE GUYNN MATERIAL ONCE PLANT MATERIAL HAS BEEN ESTABLISHED. (MINIMUM OF ONE GROWING SEASON). ALL TEMPORARY EROSION CONTROL MEASURE SHALL BE REMOVED ONCE STABILIZATION OF DISTURBANCE HAS BEEN ACCEPTED BY OWNER.
- 15.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM OF TWO MOWINGS FOR ALL TURF AREAS OR UNTIL ACCEPTANCE BY THE OWNER. A MINIMUM UNIFORM 75% CATCH OF TURF IS REQUIRED FOR ACCEPTANCE.
- 16.) ALL PLANTINGS SHALL BE WATERED REGULARLY DURING THEIR FIRST YEAR AND MAINTAINED PERMANENTLY IN GOOD GROWING CONDITION AS AN EFFECTIVE VISUAL SCREEN.
- 7.) SHRUBS OR TREES WHICH DIE SHALL BE REPLACED WITHIN ONE GROWING SEASON WITH NEW SHRUBS OR TREES TO ENSURE CONTINUED COMPLIANCE WITH APPLICABLE LANDSCAPING REQUIREMENTS.
- 18.) ALL REQUIRED LANDSCAPING SHALL BE INSTALLED BEFORE OCCUPANCY, OR WITHIN SIX MONTHS IF OCCUPANCY OCCURS DURING WINTER CONDITIONS.
- 19.) TREES ARE TO BE 3" CALIPER 6" OFF THE ROOT BALL
- 20.) ALL PLANT STOCK SHALL CONFORM TO ANSI Z260.1 NURSERY STOCK, LATEST EDITIONS (AMERICAN ASSOCIATION OF NURSERYMEN, INC.)
- 21.) 4" AGED PINEBARK MULCH AND A WEED BARRIER (TY-PAR FABRIC OR APPROVED EQUAL) SHALL BE APPLIED TO ALL SHRUB AND GROUND COVER BEDS. INSTALL WEED BARRIER AS PER MANUFACTURERS RECOMMENDATIONS.
- 22.) PLANT-PIT BACK-FILL SHALL BE MIXED AT A RATE OF 7 PARTS OF TOPSOIL TO 2 PARTS OF DEHYDRATED COW MANURE. SLOW RELEASE FERTILIZER SHALL BE APPLIED AS PER MANUFACTURERS RECOMMENDATIONS. USE EXISTING ON—SITE TOPSOIL AS PART OF BACK FILL WHEN AVAILABLE.
- 23.) ALL LANDSCAPED AREAS NOT PLANTED WITH TREES, SHRUBS OR GROUNDCOVER SHALL BE RESTORED WITH SEED OR SOD AS INDICATED ON PLANS.

LAND OF: 21 FARMINGTON ROAD LLC FOR: NM COOK DEVELOPMENT LLC FARMINGTON ROAD ROCHESTER, N.H. TAX MAP 216, LOT 29

BERRY SURVEYING


335 SECOND CROWN POINT ROAD
BARRINGTON, NH 03825 (603)332–2863
AS NOTED


DATE: MARCH 23, 2021





L-101


SHEET 23 OF 24














SHEET 24 OF 24

