OWNERS

MAP 221 LOT 159 10 FARMINGTON ROAD, LLC 549 ROUTE 1 BY-PASS PORTSMOUTH, NH 03801

MAP 221 LOT 158 RENE G. & LUANNE E. CARDINAL ROCHESTER, NH 03866-0316

APPLICANT/PREPARED FOR

MAP 221 LOT 159 10 FARMINGTON ROAD, LLC 549 ROUTE 1 BY-PASS PORTSMOUTH, NH 03801

RESOURCE LIST

PLANNING/ ZONING DEPARTMENT 31 WAKEFIELD STREET ROCHESTER, NH 03867 (603) 335-1338 MARK SULLIVAN, PLANNING AND ZONING CITY MANAGER DESIGNEE

BUILDING DEPARTMENT 33 WAKEFIELD STREET ROCHESTER, NH 03867 (603) 332-3508 JIM GRANT, DIRECTOR

PUBLIC WORKS 45 OLD DOVER ROAD ROCHESTER, NH 03867 (603) 332-4096 PETER NOURSE, P.E., DIRECTOR

POLICE DEPARTMENT 23 WAKEFIELD STREET ROCHESTER, NH 03867 PAUL TOUSSAINT, CHIEF

FIRE DEPARTMENT 37 WAKEFIELD STREET ROCHESTER, NH 03867 (603) 335-7545 MARK KLOSE, CHIEF

ASSOCIATED PROFESSIONALS

ARCHITECT TW DESIGNS, LLC 254 DRAKE HILL ROAD STRAFFORD, NH 03884 (603) 664-2181

SOIL SCIENTIST TES ENVIRONMENTAL CONSULTANTS. LLC 1494 ROUTE 3A, UNIT 1 BOW, NH, 03304 (603) 856-8925 THOMAS E. SOKOLOSKI, CERTIFIED SOIL SCIENTIST

TRAFFIC ENGINEER TEMORAN, INC. 48 CONSTITUTION DRIVE BEDFORD, NH 03110 (603) 472-4488 JENNIFER PORTER, PE

SURVEYOR 170 COMMERCE WAY PORTSMOUTH, NH 03801 (603) 431-2222


WETLANDS SCIENCE TEMORAN, INC. 48 CONSTITUTION DRIVE BEDFORD, NH, 03110 (603) 472-4488 CHRIS DANFORTH, CERTIFIED WETLAND

LIGHTING CHARRON, INC. P.O. BOX 4550 MANCHESTER, NH, 03108 (603) 624-4827 KEN SWEENEY

ROCHESTER COLLISION **ADDITION**

10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE

APRIL 27, 2021 (LAST REVISED AUGUST 24, 2021)



INDEX OF SHEETS

| SHEET | SHEET TITLE |
|-----------------|--|
| C-00 | COVER |
| S-01 | EXISTING CONDITIONS PLAN |
| C-02 | NOTES & LEGEND |
| C-03 | SITE PREPARATION & EROSION CONTROL PLAN |
| C-04 | SITE LAYOUT PLAN |
| C-05 | GRADING & DRAINAGE PLAN |
| C-06 | LANDSCAPE PLAN |
| C-07 | LANDSCAPE DETAILS |
| C-08 | TRUCK MOVEMENT PLAN |
| C-09 | EROSION CONTROL NOTES |
| C-10 - 13 | DETAILS |
| C-14 | LIGHTING PLAN |
| | |
| REFERENCE PLANS | BY ASSOCIATED PROFESSIONALS |
| _ | ARCHITECTURAL ELEVATION PLANS (BY TW DESIGNS, LLC) |

| PERMI | TS/APF | PROVALS | 3 | |
|---|---------|----------|---------|--|
| | NUMBER | APPROVED | EXPIRES | |
| CITY PLANNING BOARD SITE PLAN REVIEW | - | PENDING | - | |
| CITY ZONING BOARD VARIANCE | Z-21-02 | 2/3/21 | - | |
| NHDES ALTERATION OF TERRAIN | - | - | - | |
| FPA CCP ENDL & SWPPP | _ | _ | | |

LOT MERGER



VARIANCE APPROVAL

AT THE FEBRUARY 3, 2021 PLANNING BOARD OF ADJUSTMENT MEETING, A VARIANCE WAS APPROVED FOR TABLES 12.3 AND 12.8 OF THE ZONING ORDINANCE TO PERMIT ALTERATION OF LAND WITHIN THE WETLAND BUFFER TO ALLOW FOR PARKING AND SITE IMPROVEMENTS.

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

July 12, 2021

BOARD LUBER Shannes Saundus, Planning Div AND 15-14-51

SITE DEVELOPMENT PLANS

TAX MAP 221, LOTS 158 & 159

COVER

10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

APRIL 27, 2021



Structural Engineers Traffic Engineers
Land Surveyors

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910

47424.00 DR DKE FB

47424-00 - COVER

C-00

This plan is not effective unless signed by a duly authorized officer of




THESE PLANS ARE PERMIT DRAWINGS ONLY AND HAVE NOT BEEN DETAILED FOR CONSTRUCTION OR BIDDING.

3 6/25/2021 2 6/18/2021 1 5/27/2021

REVISED NHDES ACT NOTES
REVISED PER CITY TRG COMMENTS

REVISED PER CITY TRG COMMENTS



PJT BMK

DR CK

REV. DATE

DESCRIPTION

47424-00


S-1

LICENSED LAND SURVEYOR

2021-08-24

DATE

This plan is not effective unless signed by a duly outhorized officer Thomas F. Moran, Inc.



| | | | GENERAL |
|-------|------------------|-------|----------------------|
| ABAN | ABANDON | EXIST | EXISTING |
| AC | ACRES | FFE | FINISHED FLOOR ELEVA |
| ADJ | ADJUST | FND | FOUNDATION |
| PPROX | APPROXIMATE | HP | HIGH POINT |
| BC | BOTTOM OF CURB | INV | INVERT ELEVATION |
| BIT | BITUMINOUS | 1T | INFILTRATION TEST |
| BK/PG | BOOK & PAGE | L | LENGTH |
| BLDG | BUILDING | LF. | LINEAR FEET |
| BS | BOTTOM OF SLOPE | LSA | LANDSCAPE AREA |
| BW | BOTTOM OF WALL | MAX | MAXIMUM |
| CONC | CONCRETE | MIN | MINIMUM |
| COORD | COORDINATE | N/F | NOW OR FORMERLY |
| DIA | DIAMETER | NTS | NOT TO SCALE |
| ELEV | ELEVATION | OC | ON CENTER |
| CD | EDGE OF DAVEMENT | DAVE | DAVEMENT |

Copyright 2021 @Thomas F. Moran, Inc. 170 Commerce Way, Suite 102, Portsmouth, N.H. 03801

All rights reserved. These plans and materials may not be capied, duplicated, replicated or otherwise reproduced in any form whatsaever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.

CONTACT OF CONTROL OF

PERFORATED
PROPP PROPOSED
R RADIUS
R&D REMOVE AND DISPOSE
R&R REMOVE AND RESET
REM REMOVE
REM REMOVE
RICH TOF WAY
S SOPE
SF SOULARE FEET
SOULARE FEET
SOULARE FEET
SOULARE FEET
TO PF CURB
THE TOP FOURB
THE TOP FOURB
THE TOP FOURB
THE TOP TOP
WALL
TYP
TYPICAL
UG UNDERGROUND
WCR ACCESSIBLE WHEELCHAIR RAMP

CB CATCH BASIN CAST IRON PIPE
CCO CLEANOUT
CONDUT
DCB DOUBLE-GRATE CATCH BASIN
DI DUCTILE IRON
DMH DRAIN MANHOLE
F&C FRAME AND COVER
F&G FRAME AND GRATE
FES FLARED END SECTION
FP FLUSHING PORT
HOPE HIGH DENSITY POLYETHYLENE PIPE
HW HEADWALL
HYD HYD RANT
INSI INSULATED
LUF LUGHT POLE
COS OUTLET CONTROL STRUCTURE
RCP REINFORCED CONCRETE PIPE
RO ROOF DRAIN
SMH SEWER MANHOLE
SOS SEDIMENT OIL SEPARATOR
ISV TAPPING SLEEVE, VALVE, AND BOX
UNDERGRAIN
UP

GENERAL NOTES

- THESE PLANS ARE PERMIT DRAWINGS ONLY AND HAVE NOT BEEN DETAILED FOR CONSTRUCTION OR BIDDING.
- THESE PLANS WERE PREPARED UNDER THE SUPERVISION OF A LICENSED PROFESSIONAL ENGINEER. TEMORAN, INC. ASSUMES NO LIABILITY AS A RESULT OF ANY CHANGES OR NON-CONFORMANCE WITH THESE PLANS EXCEPT UPON THE WRITTEN APPROVAL OF THE ENGINEER OF RECORD.
- 3. THE SITE PLAN SHALL BE RECORDED IN THE STRAFFORD COUNTY REGISTRY OF DEEDS.
- ALL IMPROVEMENTS SHOWN ON THE SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE CITY PLANNING BOARD.
- 5. ALL WORK SHALL CONFORM TO THE APPLICABLE REGULATIONS AND STANDARDS OF THE CITY OF ROCHESTER, AND SHALL BE BUILT IN A WORKMANLIKE MANNER IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. ALL WORK TO CONFORM TO CITY OR FOCHESTER DEPARTMENT OF PUBLIC WORKS STANDARD SPECIFICATIONS. ALL WORK WITHIN THE RIGHT—OF—WAY OF THE CITY AND/OR STATE SHALL COMPLY WITH APPLICABLE STANDARDS. COORDINATE ALL WORK WITHIN THE RIGHT—OF—WAY WITH APPROPRIATE CITY, COUNTY, AND YOR STATE SHALL COMPLY WITH APPROPRIATE CITY, COUNTY,
- 6. THE SITE CONTRACTOR SHALL ENSURE THAT ALL WORK IS PERFORMED IN ACCORDANCE WITH APPLICABLE SECTIONS OF ENV-WQ 1500. THE SITE CONTRACTOR SHALL NOTIFY THE ENGINEER IN ADVANCE OF CONSTRUCTION OF EACH STORMWATER FACILITY TO COORDINATE REQUIRED INSPECTIONS. THE CONTRACTOR SHALL TAKE PROCRESS PHOTOS DURING CONSTRUCTION OF ALL STORMWATER DRAINAGE COMPONENTS AND SEND TO THE ENGINEER.
- 7. SEE EXISTING CONDITIONS PLAN FOR THE HORIZONTAL AND VERTICAL DATUM.
- 8. SEE EXISTING CONDITIONS PLAN FOR BENCHMARK INFORMATION, VERIFY TBM ELEVATIONS PRIOR TO CONSTRUCTION.
- 9. CONTACT EASEMENT OWNERS PRIOR TO COMMENCING ANY WORK WITHIN THE EASEMENTS.
- 10. PRIOR TO COMMENCING ANY SITE WORK, ALL LIMITS OF WORK SHALL BE CLEARLY MARKED IN THE FIELD.
- 11. SITE WORK SHALL BE CONSTRUCTED FROM A COMPLETE SET OF PLANS, NOT ALL FEATURES ARE DETAILED ON EVERY PLAN. THE ENGINEER IS TO BE NOTIFIED OF ANY CONFLICT WITHIN THIS PLAN SET.
- TEMORAN, INC. ASSUMES NO LIABILITY FOR WORK PERFORMED WITHOUT AN ACCEPTABLE PROGRAM OF TESTING AND INSPECTION AS APPROVED BY THE ENGINEER OF RECORD.
- TEMPORARY FENCING SHALL BE PROVIDED AND COVERED WITH A FABRIC MATERIAL TO CONTROL DUST MITIGATION.
- 14. ALL DEMOLITION SHALL INSURE MINIMUM INTERFERENCE WITH ROADS, STREETS, WALKWAYS, AND ANY OTHER ADJACENT OPERATING FACILITIES, PRIOR WRITTEN PERMISSION FROM THE OWNER/DEVELOPER AND LOCAL PERMITTING AUTHORITY IS REQUIRED IF CLOSURE/OBSTRUCTIONS TO ROADS, STREET, WALKWAYS, AND OTHERS IS DEEMED NECESSARY. CONTRACTOR TO PROVIDE ALTERNATE ROUTES AROUND CLOSURES/OBSTRUCTIONS PER LOCAL/STATE/FEDERAL REGULATIONS.
- 15. REFER TO ARCHITECTURAL PLANS FOR LAYOUT OF BUILDING FOUNDATIONS AND CONCRETE ELEMENTS WHICH ABUT THE BUILDING SUCH AS STAIRS, SIDEWALKS, LOADING DOCK RAMPI PADS, AND COMPACTOR PADS. DO NOT USE SITE PLANS FOR LAYOUT OF FOUNDATIONS.
- 16. IN THE EVENT OF A CONFLICT BETWEEN PLANS, SPECIFICATIONS, AND DETAILS, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR CLARIFICATION.
- 17. IF CONDITIONS AT THE SITE ARE DIFFERENT THAN SHOWN ON THE PLANS, THE ENGINEER SHALL BE NOTIFIED PRIOR TO PROCEEDING WITH THE AFFECTED WORK.
- 18. CONTRACTOR'S GENERAL RESPONSIBILITIES:
- A. BID AND PERFORM THE WORK IN ACCORDANCE WITH ALL LOCAL, STATE, AND NATIONAL CODES, SPECIFICATIONS, REGULATIONS, AND STANDARDS.
- B. NOTIFY ENGINEER IN WRITING OF ANY DISCREPANCIES OF PROPOSED LAYOUT AND/OR EXISTING FEATURES.
- C. EMPLOY A LICENSED SURVEYOR TO DETERMINE ALL LINES AND GRADES AND LAYOUT OF SITE ELEMENTS AND BUILDINGS.
- D. THE CONTRACTOR SHALL BE RESPONSIBLE TO BECOME FAMILIAR WITH THE SITE AND ALL SURROUNDING CONDITIONS. THE CONTRACTOR SHALL ADVASE THE APPROPRIATE AUTHORITY OF INTENTIONS AT LEAST 48 HOURS IN ADVANCE.
- E. TAKE APPROPRIATE MEASURES TO REDUCE, TO THE FULLEST EXTENT POSSIBLE, NOISE, DUST AND UNSIGHTLY DEBINS. CONSTRUCTION ACTIVITIES SHALL BE CARRIED OUT BETWEEN THE HOURS OF 7 AM AND 6 PM, MONDAY THROUGH FRIOAY AND 8 AM AND 6 PM ON SATURDCAY IN ACCORDANCE WITH "STANDARD OF INFRASTRUCTURE DESIGN, ROCHESTER NEW MAMPSHIPF"
- F. MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY WORK AT ALL TIMES.
- G. IN ACCORDANCE WITH RSA 430:53 AND AGR 3800, THE CONTRACTOR SHALL NOT TRANSPORT INVASIVE SPECIES OFF THE PROPERTY, AND SHALL DISPOSE OF INVASIVE SPECIES ON-SITE IN A LEGAL MANUFACTOR.
- H. COORDINATE WITH ALL UTILITY COMPANIES AND CONTACT DISSAFE (811 OR 888-344-7233) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION.
- PROTECT NEW AND EXISTING BURIED UTILITIES DURING INSTALLATION OF ALL SITE ELEMENTS. DAMAGED UTILITIES SHALL BE REPAIRED OR REPLACED AT NO ADDITIONAL COST TO THE OWNER.
- J. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MEANS AND METHODS OF CONSTRUCTION AND FOR CONDITIONS AT THE SITE. THESE PLANS, PREPARED BY TEMPRAN, INC., DO NOT EXTEND TO OR INCLUDE SYSTEMS PERTAINING TO THE SAFETY OF THE CONSTRUCTION CONTRACTOR OR THEIR EMPLOYEES, AGENTS, OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE SEAL OF THE SURVEYOR OR ENGINEER HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEMS THAT MAY NOW OR HEREAFTER BE INCORPORATED INTO THESE PLANS. THE CONSTRUCTION CONTRACTOR SHALL PREPARE OR OBTAIN THE APPROPRIATE SAFETY SYSTEMS WHICH MAY BE REQUIRED BY THE US OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) AND/OR LOCAL REGULATIONS.
- K. WRITTEN DIMENSIONS HAVE PRECEDENCE OVER SCALED DIMENSIONS. THE CONTRACTOR SHALL USE CAUTION WHEN SCALING REPRODUCED PLANS. IN CASE OF CONFLICT BETWEEN THIS PLAN SET AND ANY OTHER DRAWING AND/OR SPECIFICATION, THE ENGINEER SHALL BE NOTHED IMMEDIATELY FOR CLARRICATIONS.
- L. VERIFY LAYOUT OF PROPOSED BUILDING FOUNDATIONS WITH ARCHITECT AND THAT PROPOSED FOUNDATION MEETS PROPERTY LINE SETBACKS PRIOR TO COMMENCING ANY FOUNDATION CONSTRUCTION.
- PROVIDE AN AS—BUILT PLAN AT THE COMPLETION OF THE PROJECT TO THE PLANNING DIRECTOR AND PER CITY REGULATIONS.
- N. IF ANY DEMATIONS FROM THE APPROVED PLANS AND SPECIFICATIONS HAVE BEEN MADE. THE SITE CONTRACTOR SHALL PROVIDE AS-BUILT DRAWNES STAMPED BY A LOCKINGE STRYETOR OF OULLIFIED ENGINEER ALLOW WITH A LETTER STAMPED BY A QUA
- O. AT COMPLETION OF CONSTRUCTION, THE SITE CONTRACTOR SHALL PROVIDE A LETTER CERTIFYING THAT THE PROJECT WAS COMPLETED IN ACCIDEDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS, AND A LETTER STAMPED BY A QUALIFIED ENGINEER THAT THEY HAVE OBSERVED ALL UNDERGROUND DETENTION SYSTEMS, INFILTRATION SYSTEMS OR FILTERING SYSTEMS PRIOR TO BACKFILL AND THAT SUCH SYSTEMS CONFORM TO THE APPROVED PLANS AND SPECIFICATIONS.

GRADING NOTES

- THE CONTRACTOR SHALL ENSURE THAT ALL WORK IS PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF NHOES ENV-WQ 1500 AS APPLICABLE.
- THE CONTRACTOR SHALL PREPARE, MAINTAIN, AND EXECUTE A S.W.P.P.P. IN ACCORDANCE WITH EPA REGULATIONS AND THE CONSTRUCTION GENERAL PERMIT.
- J. THE CONTRACTOR SHALL COORDINATE WITH THE OWNER TO SUBMIT AN eNO! AT LEAST 14 DAYS IN ADVANCE OF ANY EARTHWORK ACTIVITIES AT THE SITE.
- 4. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CHECK THE ACCURACY OF THE TOPOGRAPHY AND REPORT ANY DISCREPANCES TO THE ENGINEER PRIOR TO ANY EARTHWORK BEING PERFORMED ON THE SITE. NO CLAIM FOR EXTRA WORK WILL BE CONSIDERED FOR PAYMENT AFTER EARTHWORK HAS COMMENCED.
- THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR INFORMATION ABOUT SOIL AND GROUNDWATER CONDITIONS. THE CONTRACTOR SHALL FOLLOW THE GEOTECHNICAL ENGINEER'S RECOMMENDED METHODS TO ADDRESS ANY SOIL AND GROUNDWATER ISSUES THAT ARE FOUND ON SITE.
- COORDINATE WITH GEOTECHNICAL/STRUCTURAL PLANS FOR SITE PREPARATION AND OTHER BUILDING INFORMATION.
- COORDINATE WITH ARCHITECTURAL PLANS FOR DETAILED CRADING AT BUILDING, AND SIZE AND LOCATION OF ALL BUILDING SERVICES.
- 8. COORDINATE WITH MECHANICAL AND PLUMBING PLANS FOR ROOF DRAIN INFORMATION.
- LIMITS OF WORK ARE SHOWN AS APPROXIMATE. THE CONTRACTOR SHALL COORDINATE ALL WORK TO PROVIDE SMOOTH TRANSITIONS. THIS INCLUDES GRADING, PAVEMENT, CURBING, SIDEWALKS, AND ALIGNMENTS.
- 10. THE CONTRACTOR SHALL PROVIDE A FINISH PAVEMENT SURFACE FREE OF LOW SPOTS AND PONDING AREAS. CRITICAL AREAS INCLUDE BUILDING ENTRANCE, RAMPS, AND LOADING AREAS.
- 11. THE SITE SHALL BE GRADED SO ALL FINISHED PAVEMENT HAS POSITIVE DRAINAGE AND SHALL NOT POND WATER DEEPER THAN 1/4" FOR A PERIOD OF MORE THAN 15 MINUTES AFTER FLOCODING.
- AT IER FLOUDING.

 2. ALL ELEVATIONS SHOWN AT CURB ARE TO THE BOTTOM OF CURB UNLESS OTHERWISE NOTED.

 NOTED. CURBS HAVE A 6" REVEAL UNLESS OTHERWISE NOTED.
- 13. ALL SIDEWALK AND OTHER CURB REVEALS SHALL BE 6" WITH A TOLERANCE OF PIUS OR MINUS 3/8". WHERE SIDEWALK IS TO BE FLUSH, THE PAVEMENT REVEAL SHALL BE 1/4" MITH A TOLERANCE OF 1/8".
- 14. THE FINISHED GRADE AT BOTTOM OF ALL ACCESSIBLE RAMPS SHALL BE FLUSH WITH PAYEMENT WITH A TOLERANCE OF PLUS OR MINUS 1/4".
- ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE PRIOR TO INSTALLATION OF FINISHED PAVEMENT.
- 16. ROAD AND DRAINAGE CONSTRUCTION SHALL CONFORM TO THE TYPICAL SECTIONS AND DETAILS SHOWN ON THE PLANS AND SHALL MEET LOCAL STANDARDS AND THE REQUIREMENTS OF THE LATEST NHOOT STANDARD SPECIFICATIONS FOR ROADS AND BRIDGE CONSTRUCTION AND THE NHOOT STANDARD STRUCTURE DRAWINGS UNLESS OTHERWISE NOTED.
- 17. STORMWATER DRAINAGE SYSTEM SHALL BE CONSTRUCTED TO LINE AND GRADE AS SHOWN ON THE PLANS. CONSTRUCTION METHODS SHALL CONFORM TO NI-DOT STANDARD SPECIFICATIONS, SECTION 503. CATCH BASINS AND DRAIN AMANDES SHALL CONFORM TO SECTION 504. ALL CATCH BASIN GRATES SHALL BE TYPE B AND CONFORM TO NI-DOT STANDARDS AND SPECIFICATIONS UNLESS OTHERWISE NOTED.
- 18. NO FILL SHALL BE PLACED IN ANY WETLAND AREA.
- 19. ALL EXCAVATIONS SHALL BE THOROUGHLY SECURED ON A DAILY BASIS BY THE CONTRACTOR AT THE COMPLETION OF CONSTRUCTION OPERATIONS IN THE IMMEDIATE AREA.
- ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED, FERTILIZER, AND MULCH.
- 1. DENSITY REQUIREMENTS:

MINIMUM DENSITY* LOCATION

95% BELOW PAVED OR CONCRETE AREAS

95% TRENCH BEDDING MATERIAL AND SAND BLANKET BACKFILL
90% BELOW LOAM AND SEED AREAS

90% BELOW LOAM AND SEED AREAS
**ALL PERCENTAGES OF COMPACTION SHALL BE OF THE MAXIMUM DRY DENSITY AT THE
OPTIMUM MOISTURE CONTENT AS DETERMINED AND CONTROLLED IN ACCORDANCE WITH
ASTM D-1557, BEHOD C. FIELD DENSITY TESTS SHALL BE MADE IN ACCORDANCE WITH
ASTM D-1556 OR ASTM D-6938.

UTILITY NOTES

ALL UTILITY SERVICES TO BUILDING ADDITION TO BE PROVIDED INTERNALLY FROM EXISTING BUILDING.



SITE DEVELOPMENT PLANS


TAX MAP 221, LOTS 158 & 159

NOTES & LEGEND
10 FARMINGTON ROAD
ROCHESTER, NEW HAMPSHIRE
COUNTY OF STRAFFORD
PREPARED FOR

10 FARMINGTON ROAD, LLC

SCALE: NTS

APRIL 27, 2021




| | T 1 |
|------------|----------|
| L | IV. |
| Part Comme | (And)res |

CWI Engineers
Structural Engineers
Traffic Engineers
Land Surveyors
Landscape Architects
Scientists
Www.ifmpran.com

Scientists | www.t/moron.com

47424.00 OR DKE FB - CK CRR CADFILE 47424-00 - NOTES & LEGEND

C-02



(VARIABLE WIDTH PUBLIC RIGHT OF WAY)

Copyright 2021 ©Thomas F. Moran, Inc. 170 Commerce Way, Suite 102, Portsmouth, N.H. 03801

26

All rights reserved. These plans and materials may not be a duplicated, replicated or otherwise reproduced in any form wh without the prior written permission of Thomas F. Moran, Inc.

his plan is not effective unless signed by a duly authorized officer



MAP 221 LOT 165 SECKENDORF REAL ESTATE HOLDINGS, LLC MAP 221 LOT 164 N/F NM COOK 17 FARMINGTON ROAD LLC 22 ISAAC LUCAS CIRCLE DOVER, NH 08820-4910 SCRD BK.#4766 PG.#0234

CONSTRUCTION SEQUENCE NOTES (FOR ALTERATION OF TERRAIN)

- DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO THE SUBSURFACE DETENTION BASIN DURING ANY STAGE OF CONSTRUCTION.
- 2. DO NOT PLACE THE SUBSURFACE DETENTION SYSTEM INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.

ROCK BLASTING AND WATER QUALITY NOTES

- IDENTIFY DRINKING WATER WELLS LOCATED WITHIN 2000 FEET OF THE PROPOSED BLASTING ACTIVITIES. DEVELOP A GROUNDWATER GUALITY SAMPLING PROCRAM TO MONITOR FOR NITHATE AND NITHITE EITHER IN THE DRINKING WATER SUPPLY WELLS OR IN OTHER WELLS THAT ARE REPRESENTATIVE OF THE DRINKING WATER SUPPLY WELLS IN THE AREA. THE PLAN MUST INCLUDE PRE AND POST BLAST WATER GUALITY MONITORING AND BE APPROVED BY NHIDES PRIOR TO INITIATING BLASTING. THE GROUNDWATER SAMPLING PROGRAM MUST BE IMPLEMENTED ONCE APPROVED BY HIDES.
- ALL ACTIVITIES RELATED TO BLASTING SHALL FOLLOW BEST MANAGEMENT PRACTICES (BMPS) TO PREVENT CONTAMINATION OF GROUNDWATER INCLUDING PREPARING, REVIEWING, AND FOLLOWING AN APPROVED BLASTING PLAN, PROPER OF BLLING, EMPLOSIVE HANDING AND LOADING PROCEDURES; OBSERVING THE ENTITE BLASTING PROCEDURES; EVALUATING BLASTING PERFORMANCE, AND HANDLING AND STORAGE OF BLASTER ROCK.

 A LOADING PRACTICES, THE FOLLOWING BLASTHOLE LOADING PRACTICES TO MINIMIZE ENVIRONMENTAL EFFECTS SHALL BE FOLLOWED:

- EFFECTS SHALL BE FOLLOWED:

 (1) DRILLING LOGS SHALL BE MAINTAINED BY THE DRILLER AND COMMUNICATED DIRECTLY TO THE BLASTER. THE LOGS SHALL BE MAINTAINED BY THE DRILLER AND COMMUNICATED DIRECTLY TO THE BLASTER. THE LOGS SHALL INDICATE DEPTHS AND LENGTHS OF VOIDS, CANTIES, AND FAULT CONES ON OTHER WEAK ZONES ENCOUNTERED AS WELL AS ORQUINOMATER CONDITIONS.

 (2) EMPLOSIVE PRODUCTS SHALL BE MANAGED ON-SITE SO THAT THEY ARE EITHER USED IN THE BENEFIT OF THE DELIVERY VEHICLE, OR PLACED IN SECURE CONTAINERS FOR
- CFF-SITE DISPOSAL.

 (3) SPILLAGE ARQUIND THE BOREHOLE SHALL EITHER BE PLACED IN THE BOREHOLE OR CLEANED UP AND RETURNED TO AN APPROPRIATE VEHICLE FOR HANDLING OR PLACEMENT IN SECURED CONTAINERS FOR OFF-SITE DISPOSAL.

 (4) LOADED EMPLOSIVES SHALL BE DETONATED AS SOON AS POSSIBLE AND SHALL NOT BE LEFT IN THE BLASTHOLES DEVERINGHT, LUNESS WEATHER OR OTHER SAFETY CONCERNS REASONABLY DICTATE THAT DETONATION SHOULD BE POSTPONED.

 (5) LOADING COURPMENT SHALL BE CLEANED IN AN AREA WHERE WASTEWATER CAN BE PROPERLY CONTAINED AND HANDLED IN A MANNER THAT PREVENTS RELEASE OF CONTAINANTS TO THE ENVIRONMENT.

- CONTAMINANTS TO THE ENVIRONMENT.

 (6) EXPLOSIVES SHALL BE LOADED TO MAINTAIN COOD CONTINUITY IN THE COLUMN LOAD TO PROMOTE COMPLETE DETONATION. INDUSTRY ACCEPTED LOADING PRACTICES FOR PRIMING, STEMMING, AND COLUMN RISE NEED TO BE ATTENDED TO.

 B. EXPLOSIVE SELECTION. THE FOLLOWING BMPS SHALL BE FOLLOWED TO REDUCE THE POTENTIAL FOR CROUNDWATER CONTAMINATION WHEN EXPLOSIVES ARE USED.
- (1) EXPLOSIVE PRODUCTS SHALL BE SELECTED THAT ARE APPROPRIATE FOR SITE CONDITIONS AND SAFE BLAST EXECUTION.
- AND SAFE BLAST EXECUTION.

 (2) EXPLOSIVE PRODUCTS SHALL BE SELECTED THAT HAVE THE APPROPRIATE WATER RESISTANCE FOR THE SITE CONDITIONS PRESENT TO MINIMIZE THE POTENTIAL FOR HAZARDOUS EFFECT OF THE PRODUCT UPON GROUNDWARD.

 C. PREVENTION OF MISFIRES. APPROPRIATE PRACTICES SHALL BE DEVELOPED AND IMPLEMENTED TO DEPOSE THE MISSINGERS.

- C. PREVENTION OF MISPIRES. APPROPRIATE PRACTICES SHALE BE DEVELOPED AND IMPLEMENTED TO PREVENT MISPIRES.

 D. MUCK PILE MANAGEMENT. MUCK PILES (THE BLASTED PIECES OF ROCK) AND ROCK PILES SHALL BE MANAGED IN A MANNER TO REDUCE THE POTENTIAL FOR CONTAMINATION BY IMPLEMENTING THE FOLLOWING MEASURES:

 (1) REMOVE THE MUCK PILE FROM THE BLAST AREA AS SOON AS REASONABLY POSSIBLE.

 (2) MANAGE THE INTERACTION OF BLASTED ROCK PILES AND STORMAWATER TO PREVENT CONTAMINATION OF WATER SUPPLY WELLS OR SUFFACE WATER.

 (3) MANAGE THE INTERACTION OF BLASTED ROCK PILES AND STORMAWATER TO PREVENT ON MEASURES AND SPILL MITIGATION MEASURES SHALL INCLUDE AT A MINIMUM.

 (1) THE FIFE STORAGE REQUIFIEMENTS SHALL INCLUDE:

 STORAGE OF REGULATED SUBSTANCES ON AN IMPERVOUS SURFACE.

 SECURE STORAGE AREAS AGAINST UNAUTHORIZED ENTRY.

 LABEL REGULATED CONTAINERS CLEARLY AND VISIBLY.

 INSPECT STORAGE AREAS WERLLY.

 COVER REGULATED CONTAINERS IN OUTSIDE STORAGE AREAS.

 - INSPECT STORAGE AREAS WEEKLY.

 COVER REGULATED CONTAINERS IN OUTSIDE STORAGE AREAS.

 WHEREVER POSSIBLE, KEEP REGULATED CONTAINERS THAT ARE STORED OUTSIDE MORE THAN SO FEET FROM SURFACE WATER AND STORM DRAINS, 75 FEET FROM PRIVATE WELLS. AND 400 FEET FROM PUBLIC WELLS.

 SECONDARY CONTAINMENT IS REQUIRED FOR CONTAINERS CONTAINING REGULATED SUBSTANCES STORED OUTSIDE, EXCEPT FOR ON PREMISE USE HEATING FUEL TANKS, OR ABOVECROUND OR UNDERGROUND STORAGE TANKS OTHERWISE REGULATED.

 THE FUEL HANDLING REQUIREMENTS SHALL INCLIDE:

 EXCEPT WHEN IN USE, KEEP CONTAINERS CONTAINING REGULATED SUBSTANCES CLOSED AND SEALED.
- EXCEPT WHEN IN USE, KEEP CONTAINERS CONTAINING REQULATED SUBSTANCES CLOSED AND SEALED.
 PLACE DRIP PANS UNDER SPIGOTS, VALVES, AND PUMPS.
 HAVE SPILL CONTROL AND CONTAINMENT EQUIPMENT READILY AVAILABLE IN ALL WORK AREAS.
 HER SPILL CONTROL AND CONTAINMENT EQUIPMENT READILY AVAILABLE IN ALL WORK AREAS.
 FERFORM TRANSFERS OF REQULATED SUBSTANCES OVER AN IMPERMOUS SURFACE.

 (3) THE RAINING OF ONSITE EMPLOYEES AND THE ON-SITE POSTING OF RELEASE RESPONSE INCORPANCES OF THE ONLY OF THE OWNER OF THE OWNER OF THE OWNER OF THE OWNER OWNER.

 SUBSTANCES OF THE OWNER OF THE SYNAMATION FERTHMANING AND OTHER CONSTRUCTION.

 STREET AND MAINTENANCE OF EXPLANATION FERTHMANING AND OTHER CONSTRUCTION.
- FUELING AND MAINTENANCE OF EXCAVATION, EARTHMOVING, AND OTHER CONSTRUCTION FOREING AND MAINTENANCE OF EXCAVATION, AND SHE NAVIOUS OF MODES (NOTE THESE REQUIREMENT WILL COMPLY WITH THE REGULATIONS OF INDES (NOTE THESE REQUIREMENTS ARE SUMMARIZED IN WO-DWGB-222-6: SEST MANAGEMENT PRACTICES FOR FULLING AND MAINTENANCE OF EXCAVATION AND EARTHMOVING EQUIPMENT OF ITS SUCCESSOR DOCUMENT).

NOTES

- 1. SEE NOTES ON SHEET C-02 AND C-09.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING AND DETERMINING THE LOCATIONS, SIZE, AND ELEVATIONS OF ALL EXISTING UTILITIES, SHOWN OR NOT SHOWN ON THESE PLANS PRIOR TO THE START OF ANY DEMOLITION. THE LOCATIONS SHOWN ON THESE PLANS ARE NOT GUARANTEED BY THE OWNER OR THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES INTERFERRING WITH THE PROPOSED DEMOLITION TO DETERMINE APPROPRIATE ACTION TO BE TAKEN BEFORE PROCEEDING WITH THE WORK. IT IS ALSO THE CONTRACTOR'S RESPONSIBILITY TO ANTICIPATE CONFLICTS AND REPAIR EXISTING UTILITIES AS NECESSARY TO COMPLETE THE WORK AT NO ADDITIONAL COST TO THE OWNER.
- 3. THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY WORK AT ALL THESE
- THE CONTRACTOR SHALL VERIFY ALL SURVEY INFORMATION IN THE FIELD AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO THE START OF CONSTRUCTION.
- CONSTRUCTION DEBRIS AND INVASIVE SPECIES SHALL BE REMOVED FROM SITE AND DISPOSED OF IN A LEGAL MANNER.
- 5. PRIOR TO THE START OF WORK, THE CONTRACTOR SHALL PLACE ORANGE CONSTRUCTION FENCING AROUND EACH TREE TO BE RETAINED THROUGHOUT CONSTRUCTION. NO STOCKPILES OF MATERIAL ARE PERMITTED WITHIN THE DRIP LINE OF THE TREES TO BE SAVED.
- CONTACT THE LANDSCAPE ARCHITECT IMMEDIATELY IF ANY TREES ARE DAMAGED DURING CONSTRUCTION.

CONSTRUCTION SEQUENCE NOTES

TO MINIMIZE EROSION AND SEDIMENTATION DUE TO CONSTRUCTION, CONSTRUCTION SHALL FOLLOW THIS GENERAL CONSTRUCTION SEQUENCE.

MODIFICATIONS TO THE SEQUENCE NECESSARY DUE TO THE CONTRACTOR'S SCHEDULE SHALL INCLUDE APPROPRIATE TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL MEASURES.

THE CONTRACTOR SHALL SCHEDULE WORK SUCH THAT ANY CONSTRUCTION AREA IS STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE EXCEPT AS MOTED BELOW. NO MORE THAN 5 ACRES OF DISTURBED LAND SHALL BE UNSTABILIZED AT ANY ONE THAN

THE PROJECT SHALL BE MANAGED SO THAT IT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER ARG 3800 RELATIVE TO INVASIVE SPECIES.

DO NOT DISCHARGE SEDMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNGEF, WATER FROM EXCAVATIONS) TO THE INFILTRATION SYSTEM. STORMWATER RUNGEF MUST BE DIRECTED TO TEMPORARY PRACTICES UNTIL STORMWATER BMP'S ARE STABILIZED.

DO NOT PLACE INFILTRATION SYSTEMS INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.

AFTER THE INFILTRATION SYSIEM IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE THE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING DRAG.

- NOTIFY LASEMENT OWNERS PRIOR TO COMMENCEMENT OF WORK.
 INSTALL ALL PERIMETER EROSION PROTECTION MEASURES AS INDICATED ON THE PLANS PRIOR TO THE
- INSTALL ALL PERMILER EROSSINE PROTECTION MEASURES AS INSTALLED AT LIMITS OF DISTURBANCE.

 ORANGE CONSTRUCTION FENCING IS TO BE INSTALLED AT LIMITS OF DISTURBANCE.

 DURING CONSTRUCTION FEVEY FEFORT SHALL BE MADE TO MANAGE SURFACE RUNOFF QUALITY.

 DALLY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DAINS, DITCHES, SILT BARRIERS, SEDIMENT TRAPS, ELT, MULCH AND SEED AS REQUIRED, (TEMPORARY SEED MIXTURE OF WINTER RYE APPLIED AT

- 5. DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINS, DITCHES, SILT BARRIERS, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED, ("REMPORARY SEED MIXTURE OF WINTER RYE APPLIED AT A RATE OF 2.5 LBS/100D ST SHALL BE USED).

 CONDUCT MAJOR EARTHWORK, INCLUDING CLEARING AND GRUBBING, WITHIN THE LIMITS OF WORK. ALL CUT AND FILL SLOPES SHALL BE SEEDED WITHIN 72 HOURS AFTER GRADING.

 ALL STRIPPED TOPSOL AND OTHER EARTH MATERIAL SHALL BE STOCKPLED OUTSIDE THE IMMEDIATE WORK AND WELLAND AREAS. A SILT BARRIER SHALL BE STOCKPLED AROUND THESE PILES IN A MANNER TO PROVIDE ACCESS AND AVIOS SEDIMENT OUTSIDE OF THE WORK AREA.

 B. BECIN PERMANENT AND TEMPORARY INSTALLATION OF SEED AND MULCH.
 10. PERFORM EARTHWORK NECESSARY TO ESTABLISH ROUGH GRADING AROUND PARKING FIELDS AND ACCESS DRIVES. MANAGE EXPOSED SOIL SURFACES TO AVOID TRANSPORTING SEDIMENTS INTO WELLANDS. PARKING IOTS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.


 10. CONSTRUCTION UNDERGROUND STORMTECH SYSTEM.
 11. CONSTRUCT BUILDING PAD AND COMMENCE NEW BUILDING CONSTRUCTION.

 12. CONSTRUCT BUILDING PAD AND COMMENCE NEW BUILDING CONSTRUCTION.
 13. CONSTRUCT BUILDING PAD AND COMMENCE NEW BUILDING CONSTRUCTION.

 14. COMPLETE SEEDING. AND MULCHING. SEED TO BE APPLIED WITH BROADCAST SPREADER OR BY HYDRO-SEDING. THEN ROLLED, RAKYO, OR BRACAUCHS AFTER SEEDED AREAS HAVE BECOME FIRMLY SURFACES TO ASSURE SEED/SOIL CONTACT.

 16. REMOVE TEMPORARY ERGISION COMMENCENER THE SEEDED AREAS HAVE BECOME FIRMLY SURFACES THE RESULT OF THE WORK, AND UPON COMPLETION, THE CONTRACTOR SHALL REMOVE ALL SEDIMENT DEPOSITS, EITHER ON OF 1FF SITE, INCLUDING CATCH BASINS, AND SUMPS, DRAIN PIPES AND DITCHES, CURB LINES, ALONG JET SITE, INCLUDING CATCH BASINS, AND SUMPS, DRAIN PIPES AND DITCHES, CURB LINES, ALONG JET SITE, INCLUDING CATCH BASINS, AND SUMPS, DRAIN PIPES AND DITCHES, CURB LINES, ALONG JET SITE, INCLUDING CATCH BASINS, AND SUMPS, DRAIN PIPES AND DITCHES, CURB LINES, ALONG JET SITE, INCLUDING CATCH BASINS, AND SUMPS, DRAIN PIPES AND DITCHES, CURB LINES, ALONG JET SITE
- OPERATIONS.

 18. SEE WINTER CONSTRUCTION SEQUENCE FOR WORK CONDUCTED AFTER OCTOBER 15TH.



TAX MAP 221, LOTS 158 & 159

SITE PREPARATION & EROSION CONTROL PLAN 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE

COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

1"80' (11"X17") SCALE: 1"40' (22'X34")

APRIL 27, 2021



Meetin

Civil Engineers Structural Engineers Traffic Engineers Land Surveyors indscape Architect


170 Commerce Way, Suite 102 Portsmouth, NH 03801 hone (603) 431-2222 Fax (603) 431-0910

47424.00 DR DKE FB - CK CRR CADFILE 47424-00 - SITE PREPARATION

C - 03

HORIZONTAL SCALE 1"=40"

8/24/202 REVISED PER NHDES ACT RFM HEG CRE 6/25/2021 REVISED NHDES ACT NOTES 6/18/202 HEG CRR DKE CRR REV. DATE DESCRIPTION



SIGN LEGEND SIZE (INCHES) (COLORING, TEXT SIZE, NO OF ID SIGN SPACING SHAPE WIDTH HEIGHT RETROFLECTIVITY, ETC.) (STOP) R1-1 R5-1 ONE WAY R7-81 NO PARKING FIRE LANE AS PREFERRED BY CLIENT CAUTION LOW SALT AREA AS PREFERRED BY CLIENT PER CITY OF ROCHESTER "DEAD END" PER CITY OF ROCHESTER PLACARD /SIGN

HANDICAP PARKING SIGNS SHALL BE IN ACCORDANCE WITH TOWN OF TILTON STANDARDS AND ADARCE IN ATIONS

THE PURPOSE OF THIS PLAN IS TO SHOW THE 8,000 SF BUILDING ADDITION AND PARKING EXPANSION TO THE EXISTING ROCHESTER COLLISION BUILDING.

OWNERS OF RECORD: MAP 221 LOT 158: RENE G. & LUANNE E. CARDINAL PO BOX 316 ROCHESTER, NH 03866-0316 SCRD BK.#1566 PG.#605

PARCEL AREA: MAP 221 LOT 158: 50,704 S.F. (1.1640 ACRES)

MAP 221 LOT 159; 106,706 S.F. (2.4496 ACRES)

4. THE PROPOSED OPERATING HOURS ARE 8AM TO 5PM.

5. THE PARCELS ARE LOCATED IN THE GRANITE RIDGE DEVELOPMENT ZONE (GRD).

6. THE PARCELS ARE SHOWN ON THE CITY OF ROCHESTER ASSESSOR'S MAP 221 AS LOTS 158 & 159.

THE PARCELS ARE LOCATED IN FLOOD ZONE X AS SHOWN ON FLOOD INSURANCE RATE MAPS, STRAFFORD COUNTY, NEW HAMPSHIRE, PANELS 184 & 203 OF 405, MAP NUMBERS 33017C01840 & 33017C02030, EFFECTIVE 20 ARE: MAY 17, 2005.

| DIMENSIONAL REQUIREMENTS: | REQUIRED: | PROVIDED: |
|---|--|----------------|
| LOTS: MINIMUM LOT AREA: MINIMUM FRONTAGE: MINIMUM LOT AREA PER DWELLING UNIT: MAXIMUM LOT COVERAGE: | NO REQUIREMENT 50 FT NO REQUIREMENT NO REQUIREMENT | 380 FT N/A |
| SETBACKS: MINIMUM FRONT: MAXIMUM FRONT: MINIMUM SUDE: MINIMUM REAR: | NO REQUIREMENT NO REQUIREMENT NO REQUIREMENT NO REQUIREMENT | N/A 86.2 FT |
| STANDARDS: MAXIMUM NUMBER OF STORIES: MINIMUM NUMBER OF STORIES: MAXIMUM HEIGHT: MINIMUM HEIGHT: | NO REQUIREMENT NO REQUIREMENT NO REQUIREMENT NO REQUIREMENT | N/A |

9. PARKING REQUIREMENTS:

137 SPACES 6 SPACES 9 FT X 18 FT 24 FT PARKING SPACES (SEE CALCULATION)
ACCESSIBLE SPACES
PARKING SPACE SIZE
AISLE WIDTH 64.3 SPACES

PARKING CALCULATIONS:

1.5 SPACES PER 1,000 S.F. GRC%S FLOOR AREA 1.5/1.000 X 21,534 SF =

32.3 SPACES

1 SPACE PER 15 EXTERIOR SALE/RENTAL DISPLAY SPACES 1/15 X 0 DISPLAY SPACES = D SPACES

32 SPACES 64.3 SPACES

4 SPACES PER SERVICE BAY
4/SERVICE BAY X 8 SERVICE BAYS = WETLANDS SHOWN ON THIS PLATFWERE DELINEATED IN NOVEMBER 2020 BY CHRISTOPHER K. DANFORTH CWS #077 OF TEMORAN, INC. TE WETLANDS WERE DELINEATED ACCORDING TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL (1987) AND THE REGIONAL SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL: NORTHCENTRAL AND NORTHEAST REGION, VERSION 2, JANUARY 2012.

10. ALL DIMENSIONS ARE TO THE FACE OF CURB UNLESS NOTED OTHERWISE.

LIGHTING, SIGNAGE, LANDSCAPING, AND SCREENING SHALL MEET THE REQUIREMENTS OF THE CITY OF ROCHESTER ZONING ORDINANCE AND SITE PLAN REGULATIONS.

12. SNOW SHALL NOT BE STOCKPILED IN STORMMATER BMP'S, WETLAND BUFFERS, OR WETLANDS. SEE SNOW STORAGE LOCATIONS. IN THE EVENT THAT THE SNOW STORAGE AREAS PROVIDED ON THE SITE ARE COMPLETELY UTILIZED, EXCESS SNOW STALL DE TRANSPORTED OF SITE FOR DISPOSAL, IN ACCORDANCE WITH NIDES REGULATION. IF SNOW IS STORED WITHIN PARKING AREA, KEEP CATCH BASINS CLEAR, A RED WRITER FLAG SHALL DE ATTACHED TO EACH NEW HYDRANT IS GRORE THAT THE HYDRANT CAN DE READLY LOCATED WHYEN SNOW IS ON THE GROUND.

13. SNOW STORAGE CALCULATION:

REQUIRED: 1 SF OF SNOW STORAGE AREA FOR EVERY 5 TO 10 SF OF PARKING AREA TO BE CLEARED

61,225 SF OF PARKING AREA TO BE CLEARED X (1 SF OF SNOW STORAGE AREA/10 SF OF PARKING AREA TO BE CLEARED)

= 6,123 SF OF SNOW STORAGE AREA

15. SEE ADDITIONAL NOTES ON SHEET C-02 AND C-09.

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD BOARD MEMBER

SITE DEVELOPMENT PLANS

TAX MAP 221, LOTS 158 & 159

SITE LAYOUT PLAN 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD

10 FARMINGTON ROAD, LLC

1'=80' (11'X17') SCALE: 1'=40' (22'X34')

APRIL 27, 2021

Copyright 2021 @Thomas F. Moran, Inc. 170 Commerce Way, Suite 102, Partsmouth, N.H. 03801

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



MAP 221 LOT 165 N/F N/F
SECKENDORF REAL ESTATE HOLDINGS, LLC
11 FARMINGTON ROAD
ROCHESTER, NH 03867
SCRD BK.#3192 PG.#0036

MAP 221 LOT 164 N/F N/F NM COOK 17 FARMINGTON ROAD LLC 22 ISAAC LUCAS CIRCLE DOVER, NH 03820-4910 SCRD BK.#4766 PG.#0234

HORIZONTAL SCALE 1"=40"

| | | | - | |
|------|-----------|-------------------------------|-----|-----|
| 4 | 8/24/2021 | REVISED PER NHDES AOT REMI | HEG | CRR |
| 3 | 6/25/2021 | REVISED NHDES AOT NOTES | HEG | CRR |
| 2 | 6/18/2021 | REVISED PER CITY TRG COMMENTS | HEG | CRR |
| 1 | 5/27/2021 | REVISED PER CITY TRG COMMENTS | DKE | CRR |
| REV. | DATE | DESCRIPTION | DR | or |




tructural Engineers raffic Engineers and Surveyors

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fox (603) 431-0910

47424.00 DR DKE FB CK CRR CADFILE 47424-00 - SITE LAYOUT

C - 04



EXISTING DRAINAGE

INV.12"HPPE OUT=264.62

INV.12"HPPE IN=264.05(DMH-6)

REVISED NHDES AOT NOTES
REVISED PER CITY TRG COMMENTS
REVISED PER CITY TRG COMMENTS

DESCRIPTION

PROPOSED DRAINAGE STRUCTURE TABLE

> DMH-1 RIM=268.6± INV=264.60 (IN) INV=264.50 (OUT) RD-8C INV=265.70

DMH-2 (DROP STRUCTURE) RIM=269.0± INV=262.55 (EXIST-CBB) INV=264.14 (DMH-1) INV=262.55 (OUT)

CB-3 RIM=269.45±

DMH-4 RIM=270.0± INV=265.70 (IN) INV=265.60 (OUT)

DMH-5 RIM=270.0± INV=265.51 (IN) INV=265.41 (OUT)

INV=264.20 (OUT) CB-7 RIM=268.80± INV=265.70 (OUT) SUMP=261.70

DMH-9 RIM=268.9± INV=265.65 (RD-8) INV=265.65 (CB-7) INV=265.55 (OUT)

DMH-15 RIM=267.8± INV=264.55 (IN) INV=264.55 (OUT)

DCB-16 RIM=267.60± INV=264.60 (OUT) SUMP=260.60 DMH-17 RIM=267.6±

INV=264.55 (IN) INV=264.55 (OUT)

(SEE DETAIL)
RIM=257.9±
INV=261.05 (IN)
INV=261.05 (OUT) HW-19 INV=264.1

DMH-11 RIM=268.9± INV=264.90 (IN) INV=264.77 (OUT) DMH-20 RIM=267.9± INV=261.05 (OCS-13) INV=263.30 (HW-20) INV=260.95 (OUT)

OCS-13 (SEE DETAIL) RIM=270.3± INV=261.27 (IN) INV=261.27 (OUT)

CB-14 RIM±267.70± INV=264.70 (OUT) SUMP=260.70

HW-22 INV=260.75 (IN) INV=260.72 (OUT)

HW-23 INV=260.55

DMH-21 RIM=263.65 INV=260.89 (IN) INV=260.85 (OUT)

| | SITE SPECIF | C SOIL | MAP UNIT KEY | | Lieboniir |
|--------|------------------------|---------|-----------------|----------------|-----------|
| SYMBOL | MAP UNIT | SLOPE,% | DRAINAGE CLASS | HISS SYMBOL | SOIL |
| 688 | SUTTON FINE SANDY LOAM | 8-0 | MODERATELY WELL | 321BH | В |
| 68C | SUTTON FINE SANDY LOAM | 8-15 | MODERATELY WELL | 321CH | В |
| 86B | HOLLIS FINE SANDY LOAM | 8-0 | WELL | 224BH | D |
| 500B/ | UDORTHENTS, LOAMY | 8-0 | WELL | 2619H | В |
| 500C/ | UDORTHENTS, LOAMY | 8-15 | WELL | 261CH | В |
| 500D/ | UDORTHENTS, LOAMY | 15-25 | WELL | 261DH | 6 |
| 500B/ | UDORTHENTS, LOAMY | 0-8 | MODERATELY WELL | 361BH | В |
| 500C/ | UDORTHENTS, LOAMY | 8-15 | MODERATELY WELL | 361CH | В |
| 5000/ | UDORTHENTS, LOAMY | 15-25 | MODERATELY WELL | 361DH | В |
| 5008/ | UDORTHENTS, LOAMY | 0-8 | MODERATELY WELL | 367BH | В |
| 500C/ | UDORTHENTS, LOAMY | 8-15 | MODERATELY WELL | 367CH | В |
| 500B/ | UDORTHENTS, LOAMY | 0-8 | UNDETERMINABLE | 761BH | B** |
| 500B/ | UDORTHENTS, LOAMY | 0-8 | UNDETERMINABLE | 767BH | B** |
| 514bB | LEICESTER FINE SANDY | 0-8 | POORLY | 521BH | С |

NOTES

1. SEE NOTES ON SHEET C-02 AND C-09.

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

BOARD MEMBER BOARD MEMBER

SITE DEVELOPMENT PLANS

TAX MAP 221, LOTS 158 & 159 **GRADING & DRAINAGE PLAN**

→ 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE

COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

1'=80' (11'X17') SCALE: 1'40' (22'X34')

APRIL 27, 2021

1 170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fox (603) 431-0910 www.tfmoran.com

47424.00 DR DKE FB CK CRR CADFILE 47424-00 - GRADING.DWG

C - 05

MAP 221 LOT 165 N/F SECKENDORF REAL ESTATE HOLDINGS, LLC 11 FARMINGTON ROAD ROCHESTER, NH 03867 SCRD BK.#3127 PG.MO036

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.

MAP 221 LOT 164
N/F
NM COOK 17 FARMINGTON ROAD LLC
22 ISAAC LUCAS CIRCLE
DOVER, NH 03820-4910
SCRD BK.#4766 PG.#0234

HORIZONTAL SCALE 1"=40"

3 6/25/2021 2 6/18/2021

LANDSCAPE CALCULATIONS

MINIMUM OF 25% OF THE TOTAL LAND AREA OF ANY DEVELOPMENT SITE SHALL BE DEVOTED TO LANDSCAPED AREAS OR LEFT IN AN UNALTERED NATURAL STATE.

RECOVIDED: 1,2,23 SF PROVIDED: 7,2,078± SF (43.3±%)

FRONT & SIDE HUFFER PLANTING REQUIREMENTS: ARTICLE III SEC. 5(D)

ONE BROAD-LEAFED SHADE TREE PER 40 LINEAR FEET OF FRONT BUFFER, NOT INCLUDING DRIVEWAYS. REGUIRED:
-CARDINAL DRIVE (PRIVATE WAY), 470'/40' = 12 TREES
PROVIDED: 12 TREES, (1 EXISTING AND 11 PROPOSED) NOTE: ORNAMENTALS USED UNDER UTILITY LINE.

REQUIRED:
-ROUTE 11, 280'/40' = 7 TREES
PROVIDED: 7 TREES (3 EXISTING AND 4 PROPOSED)

TWO SHADE TREES, SPACED AT LEAST 40' APART, SHALL BE LOCATED WITHIN THE FRONT 50' OF EACH SIDE BUFFER.

REQUIRED: 2 TREES
PROVIDED: 2 TREES

3. THE FRONT BUFFER AND FRONT 50 FEET OF BOTH SIDE BUFFERS SHALL BE PLANTED WITH SUFFICIENT TREES AND SHRUBS IN ORDER THAT, AT MATURITY (DEFINED HEREIN TO BE 5 YEARS FROM INSTALLATION), AT LEAST 33-1/3X OF THE AREA OF THE BUFFER, AS LOUGKED DOWN UPON FROM ABOVE, WOULD BE COVERED BY THE CANOPIES/CROWNS OF THE TREES AND SHRUBS. ARTICLE BI SEC. 5(0)(87).

PROPOSED: GREATER THAN 3%

PARKING LOT PLANTING REQUIREMENTS: ARTICLE IN SEC. 5(E)

OFF-STREET PARKING AREAS SHALL BE SCREENED FROM THE PUBLIC RIGHT-OF-WAY TO PROVIDE AT LEAST 50% VERTICAL OPACITY ON AVERAGE UP TO A HEIGHT OF 3-1/2 FEET ABOVE GRADE. EXCLUDING SIGHT TRIANGLES AT VEHICULAR ENTRANCES AND EXITS. A MODERATELY DENSE HEIGH COMPOSED OF EVERGREEN SHRUDS SHALL BE PLANTED WHICH IS REASONABLY EXPECTED TO READ THIS OPACITY AND HEIGHT WITHIN ONE YEAR. ARTICLE III SEC.

SHADE AND/OR ORNAMENTAL TREES SHALL BE PLANTED IN AND AROUND THE PARKING LOT IN ORDER THAT NO SPOT ON THE PARKING LOT IS SITUATED FURTHER THAN 75 FEET FROM THE CENTER OF THE TRUNK OF A SHADE OR ORNAMENTAL TREE. ARTICLE III SEC. 5(E)(9).
 PROPOSED: SHADE AND/OR ORNAMENTAL TREES SHOW MEET ABOVE REQUIREMENT.

LANDSCAPE LEGEND

| SYMBOL | QTY | BOTANICAL NAME COMMON NAME | SIZE | REMARKS |
|--------|-----|---|----------------------|---------|
| EN 3 | 5 | ACER RUBRUM "OCTOBER GLORY" OCTOBER GLORY RED MAPLE | 2 1/2" TO 3" CAL. | ₽&B |
| | 5 | AMELANCHEIR CANADENSIS SHADBLOW SERVICEBERRY | 2" TO 2 1/2" CAL. | ₽&B |
| 3 | 4 | PLATANUS X ACREIFOLIA 'BLOODGOOD' BLOODGOOD LONDON PLANETREE | 2 1/2" TO 3" CAL. | B&B |
| 8 | 10 | MALUS 'RED JEWEL' RED JEWEL CRABAPPLE | 2° TO 2 1/2° CAL. | B&B |
| (3) | 5 | TSUGA CANADENSIS CANADIAN HEMLOCK | 6' MIN. | B&B |
| * | 9 | PICEA GLAUGA WHITE SPRUCE | 6° MIN | B&B |
| Ö | 22 | PINUS STROBUS WHITE PINE | 6' MIN. | BAB |
| 0 | 17 | JUNIPERUS C. 'SEAGREEN' SEAGREEN JUNIPER | 5 GAL | CONT. |
| 0 | 6 | SPIRAEA J. 'LITTLE PRINCESS' LITTLE PRINCESS SPIREA | 3 GAL. | CONT. |
| 0 | 4 | SYRINGA 'TINKERBELLE' TINKERBELLE LILAC | 2' TO 2 1/2' | 888 |
| Θ | 16 | RHODODENDRON 'PJM' PJM RHODODENDRON | 3' MIN. | B&B |
| \$ | 23 | THUJA O. 'TECHNY' MISSION ARBORVITAE | 5' TO 6' | B&B |
| * | 16 | THUJA P. 'GREEN GIANT' GREEN GIANT WESTERN ARBORVITAE | 6" MIN. | B&B |
| 0 | 5 | VIBURNUM LENTAGO NANNYBERRY VIBURNUM | 3' 10 6' | B&B |

 $\left(\begin{smallmatrix}+&+&+\\+&+&+\\+&+&+\end{smallmatrix}\right)$ NEW ENGLAND CONSERVATION/WILDUFE SEED MIX, BY NEW ENGLAND WEILAND PLANTS INC.

SPECIES: VIRGINIA WILD RYE (ELYNUS VIRGINICUS), LITTLE BLUESTEM (SCHIZACHYRIUM SCOPARIUM), BIG BLUESTEM (ANDROPOGON GERARDII), RED FESCUE (FESTUCA RUBRA), SWITCH GRASS (PANICUM VIRGATUM), PARTIRIDGE FEA (CHAMAECKRISTA FASGICULATA), PANICULEDULAE TICK TREFOL (DESMODIUM PANICULATUM), INDIAM GRASS (SORGHASTRUM NUTANS), BLUE VERVAMI (VERBENA HASTATA), SUTTERFLY MILLWRED (ASCLEPIAS TUBEROSA), BLUCK EYED SUSAN (RUDBECKIA HIRTA), COMMON SNEEZEWEE (VELEMIUM AUTUMALE), HEATH ASTER (ASTERDICUSUS/SYMPHYTORICHUM PILOSUM), EARLY GOLDENROD (SOLIDAGO JUNCEA), UPLAND BENTGRASS (AGROSTIS PERENNANS).

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

BOARD MEMBER =

SITE DEVELOPMENT PLANS

TAX MAP 221, LOTS 158 & 159

LANDSCAPE PLAN 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

1'-80' (11'X17') SCALE: 1'=40' (22'X34')

APRIL 27, 2021

Seacoast Division

Structural Engineers Traffic Engineers Land Surveyors Partsmouth, NH 03801 Phone (603) 431-2222 Fox (603) 431-0910

47424.00 DR DKE FB
CK CRR CADFILE 47424--00 - LANDSCAPE

4 8/24/202 3 6/25/202 REVISED PER NHDES AOT REMI REVISED NHDES ACT NOTES 2 6/18/2021

All rights reserved. These plans and materials may not be copied duplicated, replicated or otherwise reproduced in any form whatsoe without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



MAP 221 LOT 165 N/F SECKENDORF REAL ESTATE HOLDINGS, LLC

MAP 221 LOT 164 N/F NM COOK 17 FARMINGTON ROAD LLC 22 ISAAC LUCAS CIRCLE


HORIZONTAL SCALE 1"=40"

REVISED PER CITY TRG COMMENTS REVISED PER CITY TRG COMMENTS REV. DATE DESCRIPTION

C-06

SHRUB PLANTING

NOT TO SCALE



NOT TO SCALE

LANDSCAPE NOTES

- CONTRACTOR WILL LOCATE, VERIFY AND MARK ALL EXISTING AND NEWLY INSTALLED UNDERGROUND UTILITIES PRIOR TO ANY LAWNWORK OR PLANTING.
 ANY CONFLICTS WHICH MIGHT OCCUR BETWEEN PLANTING AND UTILITIES WILL IMMEDIATELY BE REPORTED TO THE LANDSCAPE ARCHITECT OR DWNERS'
 REPRESENTATIVE, SO I HAIT ALTERNATE PLANTING LOCATIONS CAN BE DETERMINED.
- CONTRACTOR WILL FURNISH AND PLANT ALL PLANTS IN QUANTITIES AS SHOWN ON THIS PLAN. IN CASES OF DISCREPANCY BETWEEN PLAN AND LIST CLARIFY WITH LANDSCAPE ARCHITECT PRIOR TO PLACING PURCHASE ORDER AND AGAIN PRIOR TO PLANTING.
- 3. SEE PLANTING DETAILS AND IF INCLUDED, SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- 4. NO SUBSTITUTION OF PLANT MATERIALS WILL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL OF THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAKE THE APPROPRIATE ARRANGEMENTS TO PROVIDE ALL PLANTS AND MATERIALS TO ACCOMMODATE PLANTING WITHIN THE TIME ALLOWED BY THE CONSTRUCTION SCHEDULE.
- 6. PLANTING SHALL BE COMPLETED FROM APRIL 15TH THROUGH OCTOBER 15TH UNLESS OTHERWISE NOTED IN SPECIFICATIONS. THERE WILL BE NO PLANTING DURING JULY AND AUGUST UNLESS SPECIAL PROVISIONS ARE MADE FOR DROUGHT BY PROVIDING ADDITIONAL WATERING.
- 8. PLANTS WILL BE IN ACCORDANCE, AT A MINIMUM, WITH CURRENT EDITION OF "AMERICAN STANDARDS FOR NURSERY STOCK" AS PUBLISHED BY THE AMERICAN HORTICULTURE INDUSTRY ASSOCIATION.
- 9. TREES WILL BE PRUNED IN ACCORDANCE WITH THE LATEST EDITION OF ANSI A300 PART 1, "TREE, SHRUB AND OTHER WOODY PLANT MAINTENANCE STANDARD PRACTICES".
- 10. PLANTS MATERIAL IS SUBJECT TO APPROVAL / REJECTION BY THE LANDSCAPE ARCHITECT AT THE SITE AND AT THE NURSERY
- 11. ALL PLANTS WILL BE MOVED WITH ROOT SYSTEMS AS SOLID UNITS AND WITH BALLS OF EARTH FIRWLY WRAPPED WITH BURLAP. NO PLANT WILL BE ACCEPTED WHEN BALL OF EARTH SURROUNDING ITS ROOTS HAS BEEN BADLY CRACKED OR BROKEN BEFORE PLANTING. ALL PLANTS THAT CANNOT BE PLANTED AT ONCE WILL BE HEELED—IN BY SETTING IN THE GROUND AND COVERING THE BALLS WITH SOIL AND THEN WATERING, DURING TRANSPORT, ALL PLANT MATERIALS WILL BE WRAPPED WITH WIND PROOF COVERING.
- 12. NEWLY PLANTED MATERIAL WILL BEAR THE SAME RELATIONSHIP TO FINISHED GRADE AS TO THE ORIGINAL GRADE OF THE PLANT PRIOR TO DIGGING.
- 13. PROPOSED TREES OVERHANGING SIDEWALKS, ROADS OR PARKING WILL BEGIN BRANCHING NATURALLY (NOT PRUNED) AT 6' HEIGHT.
- 14, MULCH FOR PLANTED AREAS (NOT INCLUDING RAIN GARDENS) WILL BE AGED SHREDDED PINE BARK, PARTIALLY DECOMPOSED, DARK BROWN IN COLOR AND FREE OF WOOD CHIPS UNLESS OTHERWISE SHOWN.
- 15. PLANT MATERIAL WILL BE LOCATED OUTSIDE BUILDING DRIPLINES AND ROOF VALLEY POINTS OF CONCENTRATION TO PREVENT DAMAGE TO PLANTS. CLARIPY DISCREPANCIES WITH LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 16. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED, WILL RECEIVE SIX (6) INCH LOAM AND SEED AT THE DIRECTION OF THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE.
- 17. ALL PLANT GROUPINGS WILL BE IN MULCH BEDS UNLESS OTHERWISE SPECIFIED OR NOTED ON PLANS. WHERE MULCHED PLANT BED ABUTS LAWN, PROVIDE TURF CUT EDGE.
- 18. ALL PLANT BEDS WILL INTERSECT WITH PAVEMENT AT 90 DEGREES UNLESS OTHERWISE NOTED ON PLANS
- 19. ALL PLANT BED EDGES WILL BE SMOOTH AND CONSISTENT IN LAYOUT OF RADII AND TANGENTS. IRREGULAR, WAYY EDGES WILL NOT BE ACCEPTED.

LANDSCAPE GUARANTEE AND MAINTENANCE NOTES

- 1. CONTRACTOR WILL BE RESPONSIBLE FOR ALL MEANS, METHODS AND TECHNIQUES OF WATERING.
- 3. WATER ALL LAWNS AS REQUIRED. DO NOT LET NEWLY PLANTED LAWNS DRY OUT DURING THE FIRST FOUR WEEKS MINIMUM
- 4. ALL NEW LAWNS WILL BE MAINTAINED AND MOWED A MINIMUM THREE (3) TIMES BEFORE REQUESTING REVIEW BY LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE FOR ACCEPTANCE. MAINTENANCE AND MOWING WILL CONTINUE UNTIL ACCEPTED BY LANDSCAPE ARCHITECT OR OWNERS' REPRESENTATIVE IS ISSUED IN WRITING.
- THE CONTRACTOR WILL MAINTAIN AND GUARANTEE ALL PLANTINGS TO BE IN GOOD HEALTHY, FLOURISHING AND ACCEPTABLE CONDITION FOR A PERIOD ONE (1) YEAR BEGINNING AT THE DATE OF ACCEPTANCE BY THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE. ALL GRASSES, TREES AND EXPRUISH THAT, IN THE OPINION OF THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE SHOWING LESS THAN 80% HEALTHY GROWTH AT THE BUT OF ONE (1) YEAR PERIOD WILL BE IMMEDIATELY REPLACED BY THE CONTRACTOR.
- 6. ALL ORNAMENTAL GRASSES WILL BE CUT BACK EVERY FALL OR EARLY SPRING.
- 7. DECIDIOUS PLANT MATERIAL INSTALLED AFTER SEPTEMBER 30 AND BEFORE APRIL 15 WILL NOT BE REVIEWED THAT SEASON FOR ACCEPTANCE DUE TO STAGE OF LEAF PHYSIOLOGY. THIS PLANT MATERIAL WILL NOT BE REVIEWED UNTIL FOLLOWING GROWING SEASON. GUARANTEE PERIOD WILL BEGIN ONLY AFTER ACCEPTANCE BY LANDSCAPE ARCHITECT OR OWNERS: REPRESENTATIVE.
- 8. EVERGREEN PLANT MATERIAL INSTALLED AFTER OCTOBER 30 AND BEFORE APRIL 15 WILL NOT BE REVIEWED THAT SEASON FOR ACCEPTANCE DUE TO END OF GROWTH SEASON. THIS PLANT MATERIAL WILL NOT BE REVIEWED UNTIL FOLLOWING AND WING SEASON. GUARANTEE PERIOD WILL BEGIN ONLY AFTER ACCEPTANCE BY LANDSCAPE APRICTED OR OWNERS' REPRESENTATIVE.

HYDROSEEDING NOTES

HYDROSEEDING MAY BE USED AS AN ALTERNATE METHOD OF SEEDING. THE APPLICATION OF LIMESTONE AS NECESSARY, FERTILIZER AND GRASS SEED MAY BE ACCOMPLISHED IN ONE OPERATION BY THE USE OF A SPRAYING MACHINE APPROVED BY THE LANDSCAPE ARCHITECT OR CIVIL ENGINEER. THE MATERIALS SHALL BE MIXED WITH WATER IN THE MACHINE AND SHALL CONFORM TO RELATIVE REQUIREMENTS OF SECTION 644 OF NH. STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

INVASIVE PLANT NOTES

EXISTING NON-NATIVE, INVASIVE PLANT SPECIES WILL BE IDENTIFIED, REMOVED, DESTROYED AND LEGALLY DISPOSED OF IN ACCORDANCE WITH THE LATEST UNIVERSITY OF NEW HAMPSHIRE COOPERATIVE EXTENSION METHODS OF DISPOSING NON-NATIVE INVASIVE PLANTS. SEE "MANAGE AND CONTROL INVASIVES" AND PROPERTY DISPOSE OF INVASIVE PLANTS.

PRICING & CONSTRUCTION DOCUMENT NOTES

- CONTRACTOR WILL PRICE PLANT MATERIAL IN QUANTITIES SUFFICIENT TO COMPLETE PLANTINGS GRAPHICALLY SHOWN ON THESE DRAWINGS OR IN PLANT
 LIST, WHICHEVER IS GREATER. IN CASES OF DISCREPANCY BETWEEN PLAN AND LIST CLARIFY WITH LANDSCAPE ARCHITECT PRIOR TO PLACING PURCHASE
 GRORE AND AGAIN PRIOR TO PLANTING.
- CONTRACTOR WILL VERIFY PRIOR TO PRICING IF SITE SOILS ARE VERY POORLY DRAINING OR IF LEDGE IS PRESENT. IF CONTRACTOR ENCOUNTERS VERY
 POORLY DRAINING SOILS (BATH TUB EFFECT) OR LEDGE THAT IMPACTS PROPOSED PLANTING PLAN, NOTIFY LANDSCAPE ARCHITECT OR OWNERS'
 REPRESENTATIVE FOR DIRECTION PRIOR TO PRICING AND AGAIN PRIOR TO PERFORMING ANY WORKING.
- 3. PARKING AREA PLANTED ISLANDS WILL HAVE MINIMUM OF 1'-O" TOPSOIL PLACED TO THE TOP OF CURB ELEVATION. REMOVE ALL CONSTRUCTION DEBRIS BEFORE PLACING TOPSOIL.
- 4. EXISTING TREES SHOWN ON THE PLAN WILL REMAIN UNDISTURBED. ALL EXISTING TREES SHOWN TO REMAIN WILL BE PROTECTED WITH A 4-FCOT SNOW FENCE PLACED AT THE DRIP LINE OF THE BRANCHES OR AT 8 FEET MINIMUM FROM THE TREE TRUNK.
- CONTRACTOR WILL STAKE OR PLACE ON GROUND ALL PROPOSED PLANT MATERIALS PER PLAN. CONTACT LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
- COORDINATE WITH LANDSCAPE ARCHITECT'S CONTRACTED NUMBER OF SITE VISITS WHEN PLANNING FOR INSPECTION. NOTIFY LANDSCAPE ARCHITECT 72
 HOURS MINIMUM IN ADVANCE OF REQUESTED SITE VISIT.

- 1. SEEDING SHALL BE DONE BETWEEN APRIL 1 TO JUNE 15 OR AUGUST 15 TO OCTOBER 15, EXCEPT FOR RESEEDING OF BARE SPOTS AND MAINTENANCE. ALL DISTURBED AREAS NOT COVERED BY BUILDINGS, PAVING OR AREAS THAT HAVE NOT BEEN OTHERWISE DEVELOPED SHALL BE SEEDED OR SODDED. SLOPES GREATER THAN 3:1 SHALL BE PROTECTED WITH AN EROSION CONTROL BLANKET. AFTER OCTOBER 15 DISTURBED SOLS SHALL BE PROTECTED IN ACCORDANCE WITH THE WINTER CONSTRUCTION NOTES.
- 2. SLOPES UP TO AND INCLUDING 3:1 GRADE, SEED WILL BE NEW ENGLAND EROSION CONTROL & RESTORATION MIX PER NEW ENGLAND WETLANDS PLANTS INC., AMPERST, MA.
- 3. SLOPES STEEPER THAN 3:1 GRADE, SEED WILL BE NEW ENGLAND EROSION CONTROL & RESTORATION MIX PER NEW ENGLAND WETLANDS PLANTS INC., AMHERST, MA. SEE CMIL FOR ADDITIONAL EROSION CONTROL MEASURES.
- 4. GENERAL SEED WILL BE NHOOT SPECIFICATION SECTION 644, TABLE 644-1-PARK SEED TYPE 15, INCLUDING NOTES TO TABLE 1, 2 & 3.

- 1. THE IRRIGATION SYSTEM SHALL BE DESIGNED BY AN APPROVED IRRIGATION DESIGN/BUILD CONTRACTOR OR BY AN APPROVED EQUAL, TO BE DETERMINED BY THE OWNERS
- 2. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING THE IRRIGATION SYSTEM DESIGN AND SHOP DRAWINGS TO THE OWNER 30 DAYS PRIOR TO THE START OF CONSTRUCTION.
- 3. THE CONTRACTOR SHALL VERIFY LOCATIONS OF ALL EXISTING AND PROPOSED UTILITIES AND NOTIFY THE OWNER'S REPRESENTATIVE OF CONFLICTS.
- 4. THE IRRIGATION CONTRACTOR IS RESPONSIBLE FOR, BUT NOT LIMITED TO, THE COMPLETE INSTALLATION OF THE IRRIGATION SYSTEM AND SHALL FOLLOW ALL APPLICABLE
- 5. REFER TO ARCHITECTURAL PLANS FOR LOCATION OF THE, IRRIGATION SYSTEM'S BUILDING CONNECTION
- 6. REFER TO MANUFACTURER'S INSTRUCTIONS AND PRODUCT SPECIFICATIONS FOR INSTALLATION

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD BOARD MEMBER AND BOARD MEMBER SITE DEVELOPMENT PLANS

> LANDSCAPE DETAILS 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD

TAX MAP 221, LOTS 158 & 159

PREPARED FOR 10 FARMINGTON ROAD, LLC

SCALE, NTS

APRIL 27, 2021

4 8/24/202 REVISED PER NHDES AOT RFM HEG CRE 3 6/25/202 REVISED NHDES AOT NOTES 6/18/202 REVISED PER CITY TRG COMMENTS REVISED PER CITY TRG COMMENTS DKE CRR REV. DATE DESCRIPTION



Civil Engineers Structural Engineers 170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fox (603) 431-0910

47424.00 DR DKE FB
CK CRR CADFILE 17424-00 - LANDSCAPE DETAIL


C - 07

6" LOAM (ITEM 641) SEED (ITEM 644) LIMESTONE (ITEM 642) FERTILIZER (ITEM 643.11) MULCH (ITEM 645.111) LOAM & SEED NOT TO SCALE


A ART TO MY CONTROL OF THE DESIGNATION OF THE PARTY OF TH

Copyright 2021 ©Thomas F. Moran, Inc. 170 Commerce Way, Suite 102, Portsmouth, N.H. 03801

Il rights reserved. These plans and materials may not be copied. duplicated, replicated or otherwise reproduced in any form whotsoever without the prior written permission of Thomas F. Moran, Inc.



MAP 221 LOT 157 N/F RENE G. CARDINAL PO BOX 316 ROCHESTER, NH 03866-0316 SCRD BK.#4328 PG.#0128 MAP 221 LOT 162 N/F WISSLER PROPERTIES, LLC ZO FARMINGTON ROAD ROCHESTER, NH 03867-4304 SCRD BK.#4193 PG.#0444 MAP 221 LOT 150 N/F N/F
MICHAEL V. & JEAN F. GARZILLO
REVOCABLE TRUST
18 FARMINGTON ROAD
ROCHESTER, NH 03867-4304
SCRD BK.#3431 PG.#0885 MAP 221 LOT 154
N/F
JEAN W, EDGERLY REVOCABLE
TRUST OF 1991
2 FARMINGTON ROAD
ROCHESTER, NH 03867-4304
SCRD BK:#3957 PG.#1015 CHLINA FARMINGTON ROAD / NH ROUTE 11 (VARIABLE WIDTH PUBLIC RIGHT OF WAY)



E-ONE HP95 Mid Mount Overall Lenath Overall Width Overall Body Height Min Body Ground Clearance Track Width Lock-to-lock time Max Wheel Angle



APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD BOARD MEMBER BOARD MEMBER

SITE DEVELOPMENT PLANS

TAX MAP 221, LOTS 158 & 159

TRUCK MOVEMENT PLAN 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

1*=80' (11"X17") SCALE: 1'=40' (22'X34")

APRIL 27, 2021

HEG CRR HEG CRR HEG CRR DKE CRR DR CK

REVISED PER NHDES AOT RFMI
REVISED NHDES AOT NOTES
REVISED PER CITY TRG COMMENTS
REVISED PER CITY TRG COMMENTS
DESCRIPTION

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fox (603) 431-0910 www.tfmoran.com

C-08

Copyright 2021 ©Thomas F. Moran, Inc. 170 Commerce Way, Suite 102, Portsmouth, N.H. 03801

This plan is not affective unless signed by ${\tt c}$ duly authorized officer of Thomas F. Moran, Inc.




MAP 221 LOT 165 N/F SECKENDORF REAL ESTATE HOLDINGS, LLC 11 FARMINGTON ROAD ROCHESTER, NH 03867 SCRD BK:#3192 PG:#0036

MAP 221 LOT 164

N/F

NM COOK 17 FARMINGTON ROAD LLC
22 ISAAC LUCAS CIRCLE
DOVER, NH 03820-4910
SCRD BK.#4766 PG.#0234



| н | IORIZONT | AL SCALE 1"=4 | o' | 4 | 8/24/2021 |
|----|----------|---------------|----|-----------|-----------|
| 40 | 20 | D | 40 | 3 | 6/25/2021 |
| | | | | 2 | 6/18/2021 |
| | | | 1 | 5/27/2021 | |
| | | | | REV. | DATE |

THE TOTAL PROPOSED AREA TO BE DISTURBED IS APPROXIMATELY 72,375 SQUARE FEET (1.66 ACRES).

CRITICAL NOTE: THIS DRAWING IS PROVIDED FOR GENERAL GUIDANCE. ALL SPECIAL EROSION CONTROL MEASURES MUST BE EXECUTED IN ACCORDANCE WITH APPLICABLE CURRENT STATE AND LOCAL REGULATIONS, APPROVED SWPPP, AND PERMIT REGUIREMENT.

- INSTALL STABILIZED CONSTRUCTION ENTRANCE AND TEMPORARY EROSION CONTROL MEASURES PER APPROVED SWPPP IF REQUIRED.

- DEMOLISH EXISTING SITE WORK DESIGNATED FOR REMOVAL.
 COMPLETE MAJOR GRADING OF SITE.
 CONSTRUCT BUILDING PAD, STORMWATER SYSTEM, AND SITE UTILITIES.
 CONSTRUCT PARKING LOT.
- 5. CONSTRUCT PARKING LDT.

 WHEN ALL CONSTRUCTION ACTIVITY IS COMPLETE AND SITE IS STABILIZED, REMOVE ALL INLET PROTECTION, SILT BARRIERS, AND SEDIMENT THAT HAS BEEN TRAPPED BY THESE DEVICES.

 CONSULT APPROVED SWPPP FOR CONDITIONS RELATED TO NOTICE OF TERMINATION, IF REQUIRED.

EROSION AND SEDIMENT CONTROLS AND STABILIZATION PRACTICES

STABILIZATION SHALL BE INITIATED ON ALL LOAM STOCKPILES AND DISTURBED AREAS WHERE CONSTRUCTION ACTIVITY WILL NOT OCCUR FOR MORE THAN TWENTY ONE (21) CALENDAR DAYS BY THE FOURTEENTH (14TH) DAY AFTER CONSTRUCTION ACTIVITY HAS PERMANITY OR TEMPORARILY CASED IN THAT AREA. ALL DISTURBED AREA SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED.

- BASE COURSE GRAVELS, WHICH MEET THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM 304.2, HAVE BEEN INSTALLED IN AREAS TO BE PAVED;
 A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
 A MINIMUM OF 30° OF NON-EROSIVE MATERAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED; OR EROSION CONTROL BLANKETS HAVE BEEN PROPERTY INSTALLED.

- DURING CONSTRUCTION, RUNOFF WILL BE DIVERTED AROUND THE SITE WITH EARTH DIKES, PIPING OR STABILIZED CHANNELS WHERE POSSIBLE. SHEET RUNOFF FROM THE SITE WILL BE FILTERED THROUGH SILT BARRIERS. ALL STORM DRAIN INLETS SHALL BE PROVIDED WITH BARRIER FILTERS. STONE RIPRAP SHALL BE PROVIDED AT THE OUTLETS OF DRAINAGE PIPES WHERE EROSIVE VELOCITIES ARE ENCOUNTERED.

STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED.

INSTALLATION, MAINTENANCE AND INSPECTION OF EROSION AND SEDIMENT CONTROLS

THESE ARE THE GENERAL INSPECTION AND MAINTENANCE PRACTICES THAT WILL BE USED TO IMPLEMENT THE PLAN.

- 1. STABILIZATION OF ALL SWALES, DITCHES, AND PONDS IS REQUIRED PRIOR TO DIRECTING FLOW TO THEM
- 2. THE SMALLEST PRACTICAL PORTION OF THE SITE WILL BE DENUDED AT ONE TIME. (5 AC MAX)
- ALL CONTROL MEASURES WILL BE INSPECTED AT LEAST ONCE EACH WEEK AND FOLLOWING ANY STORM EVENT OF 0.10* OR GREATER.
- ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER. IF A REPAIR IS NECESSARY, IT WILL BE INITIATED WITHIN 24 HOURS OF REPORT.
- BUILT UP SEDIMENT WILL BE REMOVED FROM SILT BARRIER WHEN IT HAS REACHED ONE THIRD THE HEIGHT OF THE BARRIER.
- 6. ALL DIVERSION DIKES WILL BE INSPECTED AND ANY BREACHES PROMPTLY REPAIRED.
- TEMPORARY SEEDING AND PLANTING WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND UNHEALTHY GROWTH.
- 8. A MAINTENANCE INSPECTION REPORT WILL BE MADE AFTER EACH INSPECTION
- THE CONTRACTOR'S SITE SUPERINTENDENT WILL BE RESPONSIBLE FOR INSPECTIONS, MAINTENANCE AND REPAIR ACTIVITIES, AND FILLING OUT THE INSPECTION AND MAINTENANCE REPORT.

B. FILTER / BARRIERS

SILT SOCKS

 $^5\!\!A^{\frac{1}{2}}$ knotted mesh netting material, shall be delivered to site in a 5 mil continuous, tubular, hdpe 3/6" material, filled with compost conforming to the following requirements:

PHYSICAL PROPERTY TMECC 04.11-A REQUIREMENTS 5 D TO 8.0

TMECC 02:02-8 2" SIEVE AND MIN. 60% GREATER THAN THE #" SIEVE

STND TESTING < 60% MOISTURE CONTENT

MATERIAL SHALL BE RELATIVELY FREE OF INERT OR FOREIGN MAN-MADE MATERIALS

MATERIAL SHALL BE WEED FREE AND DERIVED FROM A WELL-DECOMPOSED SOURCE OF ORGANIC MATTER, FREE FROM ANY REFUSE, CONTAMINANTS OR OTHER MATERIALS TOXIC TO PLANT GROWTH.

- B. SEDIMENT COLLECTED AT THE BASE OF THE SILT SOCK SHALL BE REMOVED ONCE IT HAS REACHED 1/3 OF THE EXPOSED HEIGHT OF THE SILT SOCK.
- C. SILT BARRIER SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE $$ E. UPSLOPE AREAS HAS BEEN PERMANENTLY STABILIZED.

SEDIMENT BARRIERS SHALL BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE CONTRIBUTING DRAINAGE AREA ABOVE THEM.

- A. SILT BARRIERS SHALL BE INSPECTED WEEKLY AND IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. THEY SHALL BE REPAIRED IF THERE ARE ANY SIGNS OF EROSION OF SEDIMENTATION BELOW THEM. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY. IF THERE ARE SIGNS OF UNDERCULTING AT THE CENTER OR THE EDOES, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THEM. SEDIMENT BARRIERS SHALL BE REPLACED WITH A TEMPORARY CHECK DAM.
- B. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
- C. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE THIRD (1/3) THE HEIGHT OF THE BARRIER.
- D. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFIRM WITH THE EXISTING GRADE, PREPARED AND SEEDED.

IN ORDER FOR MULCH TO BE EFFECTIVE, IT MUST BE IN PLACE PRIOR TO MAJOR STORM EVENTS. THERE ARE TWO (2) TYPES OF STANDARDS WHICH SHALL BE USED TO ASSURE THIS:

THIS IS APPLICABLE WHEN WORKING WITHIN 100' OF WETLANDS, IT WILL BE NECESSARY TO CLOSELY MONITOR WEATHER PREDICTIONS, USUALLY BY CONTACTING THE NATIONAL WEATHER SERVICE, TO HAVE ADEQUATE WARNING OF SIGNIFICANT STORMS.

THE TIME PERIOD CAN RANGE FROM 14 TO 21 DAYS OF INACTIVITY ON AN AREA, WHERE THE LENGTH OF TIME VARIES WITH SITE CONDITIONS, PROFESSIONAL JUDGMENT SHALL BE USED TO EVALUATE THE INTERACTION OF SITE CONDITIONS (SOIL ERODIBILITY, SEASON OF YEAR, EXTENT OF DISTURBANCE, PROXIMITY TO SENSITIVE RESOURCES, ETC.) AND THE POTENTIAL IMPACT OF EROSION ON ADJACENT AREAS TO CHOOSE AN APPROPRIATE TIME RESTRICTION.

2. GUIDELINES FOR WINTER MULCH APPLICATION.

WHEN MULCH IS APPLIED TO PROVIDE PROTECTION OVER WINTER (PAST THE GROWING SEASON) IT SHALL BE AT A RATE OF 6,000 POUNDS OF HAY OR STRAW PER ACRE. A TACKIFIER MAY BE ADDED TO THE MULCH.

ALL MULCHES MUST BE INSPECTED PERIODICALLY, IN PARTICULAR AFTER RAINSTORMS, TO CHECK FOR RILL EROSION. IF LESS THAN 90% OF THE SOIL SURFACE IS COVERED BY MULCH, ADDITIONAL MULCH SHALL BE IMMEDIATELY APPLIED.

- 1. AFTER ROUGH GRADING OF THE SUBGRADE HAS BEEN COMPLETED AND APPROVED, THE SUB GRADE SURFACE SHALL BE SCARFIED TO A DEPTH OF 4". THEN, FURRISH AND INSTALL A LAYER OF LOAM PROVIDING A ROLLED THICKNESS AS SPECIFIED IN THESE PLANS. ANY DEPRESSIONS WHICH MAY OCCUR DURING ROLLED SHALL BE FILLED WITH ADDITIONAL LOAM, REGRADED AND REPOLLED UNTIL THE SUFFACE IS TRUE TO THE FINISHED LINES. AND GRADES, ALL LOAM NECESSARY TO COMPLETE THE WORK UNDER THIS SECTION SHALL BE SUPPLIED BY THE SITE SUBCONTRACTOR.
- ALL LARGE STIFF CLODS, LUMPS, BRUSH, ROOTS, DEBRIS, GLASS, STUMPS, LITTER, AND OTHER FOREIGN MATERIAL, AS WELL AS STONES OVER 1° IN DIAMETER, SHALL BE REMOVED FROM THE LOAM AND DISPOSED OF OFF SITE. THE LOAM SHALL BE RAKED SMOOTH AND EVEN.
- 3. THE LOAM SHALL BE PREPARED TO RECEIVE SEED BY REMOVING STONES, FOREIGN OBJECTS AND GRADING TO ELIMINATE WATER POCKETS AND IRREGULARITIES PRIOR TO PLACING SEED, FINISH GRADING SHALL RESULT IN STRAIGHT UNIFORM GRADES AND SMOOTH, EVEN SURFACES WITHOUT IRREGULARITIES TO LOW POINTS.
- 4. SHAPE THE AREAS TO THE LINES AND GRADES REQUIRED. THE SITE SUBCONTRACTOR'S ATTENTION IS DIRECTED TO THE SCHEDULING OF LOAMING AND SEEDING OF GRADED AREAS TO PERMIT SUFFICIENT TIME FOR THE STABILIZATION OF THESE AREAS. IT SHALL BE THE SITE SUBCONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE AREAS OURING THE CONSTRUCTION PERIOD AND REGRADE, LOAM AND RESELD ANY DAMAGED AREAS.
- ALL AREAS DISTURBED BY CONSTRUCTION WITHIN THE PROPERTY LINES AND NOT COVERED BY STRUCTURES, PAVEMENT, OR MULCH SHALL BE LOAMED AND SEEDED.
- LIMESTONE SHALL BE THOROUGHLY INCORPORATED INTO THE LOAM LAYER AT A RATE OF 2 TONS PER ACRE IN ORDER TO PROVIDE A PH VALUE OF 5.5 TO 6.5.
- 8. SOIL CONDITIONERS AND FERTILIZER SHALL BE APPLIED AT THE RECOMMENDED RATES AND SHALL BE THOROUGHLY WORKED INTO THE LOAM. LOAM SHALL BE RAKED UNTIL THE SURFACE IS FINELY PULVERIZED, SMODIN AND EVEN, AND THEN COMPACTED TO AN EVEN SURFACE CONFORMING TO THE REQUIED LINES AND GRADES WITH APPROVED ROLLERS WEIGHING BETWEEN 4 1/2 POUNDS AND 5 1/2 POUNDS PER INCH OF WIDTH.
- 9. SEED SHALL BE SOWN AT THE RATE SHOWN BELOW. SOWING SHALL BE DONE ON A CALM, DRY DAY, PREFERABLY BY MACHINE, BUT IF BY HAND, ONLY BY EXPERIENCED WORKMEN, IMMEDIATELY BEFORE SEEDING, THE SOIL SHALL BE LIGHTLY RAKED. ONE HALF THE SEED SHALL BE SOWN IN ONE DIRECTION AND THE OTHER HALF AT RIGHT ANGLES TO THE ORIGINAL DIRECTION. IT SHALL BE LIGHTLY RAKED INTO THE SOIL TO A DEPTH NOT OVER 1/4" AND ROLLED WITH A HAND ROLLER WEIGHING NOT DVER 10D POUNDS PER LINEAR FOOT OF
- 10. HAY MULCH SHALL BE APPLIED IMMEDIATELY AFTER SEEDING AT A RATE OF 1.5 TO 2 TONS PER ACRE. MULCH THAT BLOWS OR WASHES AWAY SHALL BE REPLACED IMMEDIATELY AND ANCHORED USING APPROPRIATE TECHNIQUES FROM THE EROSION AND SEDIMENT CONTROL HANDBOOK.
- 11. THE SURFACE SHALL BE WATERED AND KEPT MOIST WITH A FINE SPRAY AS REQUIRED, WITHOUT WASHING AWAY THE SOIL, UNTIL THE GRASS IS WELL ESTABLISHED. ANY AREAS WHICH ARE NOT SATISFACTORILY COVERED WITH GRASS SHALL BE RESELEDED, AND ALL NOKIOUS WELEDS REMOVED.
- 12. THE SITE SUBCONTRACTOR SHALL PROTECT AND MAINTAIN THE SEEDED AREAS UNTIL ACCEPTED, INCLUDING CUTTING, AS SPECIFIED HEREIN AFTER UNDER MAINTENANCE AND PROTECTION.
- 13. UNLESS OTHERWISE APPROVED, SEEDING SHALL BE DONE DURING THE APPROXMATE PERIODS OF EARLY SPRING TO SEPTEMBER 3.0, WHEN SOIL CONETTIONS AND WEATHER ARE SUITABLE FOR SUCH WORK, IN NO CASE SHALL THE WEED CONTENT EXCELLED 1 FEALINETH BY WEIGHT, ALL SEED SHALL COMPLY WITH STATE AND FEDERAL STED LAWS, FOR TEMPORARY PLANTINGS AFTER SEPTEMBER 3.0, TO EARLY SPRING AND FOR TEMPORARY PROTECTION OF DISTURBED AFEAS:
- A. FOLLOW ABOVE SLOPE, LOAM DEPTH AND GRADING REQUIREMENTS.
 B. FERTILIZER SHALL BE SPREAD AND WORKED INTO THE SURFACE AT A RATE OF 500 POUNDS PER ACRE.

MULCHING AND SEEDING SHALL BE APPLIED AT THE FOLLOWING RATES:
WINTER RYE (FALL SEEDING) 2.5 LBS/1,000 SF
OATS (SPRING SEEDING) 2.0 LBS/1,000 SF

1.5 TONS/ACRE

CATCH BASIN INLET PROTECTION

- A. INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY PRIOR TO DISTURBING PAVEMENT AND SHALL REMAIN IN PLACE AND MAINTAINED UNTIL PAVEMENT BINDER COURSE IS COMPLETE.
- B. MOLD 6X6, 42 LB. WIRE SUPPORT AROUND INLET FRAME AND GRATE AND EXTEND 6" BEYOND SIDES. SECURE FILTER FABRIC TO WIRE SUPPORT.
- C. THE FILTER FABRIC SHALL BE A GEOTEXTILE FABRIC; POLYESTER, POLYPROPYLENE, STABILIZED NYLON, POLYETHYLENE OR POLYMNYLIDENE CHLORIDE MEETING THE FOLLOWING SPECIFICATIONS:

GRAB STRENGTH: 45 LB. MINIMUM IN ANY PRINCIPAL DIRECTION (ASTM D1682) MULLEN BURST STRENGTH: MIN. 60PSI (ASTM D774)

- D. THE FABRIC SHALL HAVE AN OPENING NO GREATER THAN A NUMBER 20 U.S. STANDARD SIEVE AND A MINIMUM PERMEABILITY OF 120 CPM.
- E. THE INLET PROTECTION SHALL BE INSPECTED WITHIN 24 HOURS AFTER EACH RAINFALL OR DAILY DURING EXTENDED PERIODS OF PRECIFITATION. REPAIRS SHALL BE MADE IMMEDIATELY, AS NECESSARY, TO PREVENT PARTICLES FROM REACHING THE DRAINAGE SYSTEM AMD/OR CAUSING SURFACE CLOCGING.
- F. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT, OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED.

- 1. ALL PROPOSED POST-DEVELOPMENT LANDSCAPED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL SLANKETS ON SLOPES GREATER THAN 3: 1 AND SEEDING AND PLACRING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE, THE PLACEMENT OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING WELT EVENT.
- ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR
 WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL
 BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.
- 3. AFTER OCTOBER 15TH, INCOMPLETE PARKING AREAS WHERE ACTIVE CONSTRUCTION HAS STOPPED FOR THE WINTER ALL TRAVEL SURFACES SHALL BE PROTECTED WITH A MINIMUM OF 3" OF CRUSHED GRAVEL PER NHDOT ITEM 30-43, OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOWFALL AFTER EACH STORM EVENT.

AS INDICATED IN THE SEQUENCE OF MAJOR ACTIVITIES, SILT BARRIERS SHALL BE INSTALLED PRIOR TO COMMENCING ANY CLEARING OR CRADING OF THE SITE STRUCTURAL CONTROLS SHALL BE INSTALLED CONCURRENTLY WITH THE APPLICABLE ACTIVITY. AREAS WHERE CONSTRUCTION ACTIVITY TEMPORALLY CEASES FOR MORE THAN TWENTY ONE (21) DAYS WILL BE STABILZED WITH A TEMPORARY SEED AND MULCH WITHIN FOURTEEN (14) DAYS OF THE LAST DISTURBANCE. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN AREA, SILT BARRIERS AND ANY EARTH/DIKES WILL BE REMOVED ONCE PERMANENT MEASURES ARE ESTABLISHED.

. WASTE MATERIALS ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN A DUMPSTER. NO CONSTRUCTION WASTE MATERIALS WILL BE BURIED ON SITE. ALL PERSONNEL WILL BE INSTRUCTED RECARDING THE CORRECT PROCEDURE FOR WASTE DISPOSA BY THE SUPERINITANDENT.

HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER. SITE PERSONNEL WILL BE INSTRUCTED IN THESE PRACTICES BY THE SUPERINTENDENT. SANITARY WASTE ALL SENTENCE WILL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONCE PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

SPILL PREVENTION

MATERIAL MANAGEMENT PRACTICES
THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES DURING CONSTRUCTION TO STORMWATER RUNOFF:

GOOD HOUSEKEEPING: THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ON SITE DURING THE CONSTRUCTION

- A. AN EFFORT WILL BE MADE TO STORE ONLY SUFFICIENT AMOUNTS OF PRODUCTS TO DO THE JOB B. ALL MATERIALS STORED ON SITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR PROPER (ORIGINAL IF POSSIBLE) CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE.
- C. MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED
- D. THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS.
- F. WHENEVER POSSIBLE ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER

HAZARDOUS PRODUCTS:
THE FOLLOWING PRACTICES WILL BE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS:

- A. PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE
- B. ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED FOR IMPORTANT PRODUCT INFORMATION.
- C. SURPLUS PRODUCT THAT MUST BE DISPOSED OF WILL BE DISCARDED ACCORDING TO THE MANUFACTURER'S RECOMMENDED METHODS OF DISPOSAL.

PRODUCT SPECIFICATION PRACTICES THE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ON SITE:

MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS

PETROLEUM PRODUCTS:
ALL ON SITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT BASED SUBSTANCES USED ON SITE WILL BE APPLIED ACCORDING TO THE MANUF ACTURE "S' RECOMMENDATIONS

FERTILIZERS:
FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS DIRECTED BY THE SPECIFICATIONS. ONCE APPLIED FERTILIZER WILL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORMWATER. STORAGE WILL BE IN A COVERED SHED OR ENCLOSED TRAILERS. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER WILL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS. PAINTS:
ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE, EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM BUT WILL BE DISPOSED OF PROPERLY ACCORDING TO

<u>CONCRETE_TRUCKS.</u>

CONCRETE_TRUCKS WILL DISCHARGE AND WASH OUT SURPLUS CONCRETE OR DRUM WASH WATER IN A CONTAINED AREA DESIGNATED ON SITE.

4 8/24/20

REV. DATE

3 6/25/202 6/18/202

5/27/202

SPILL CONTROL PRACTICES

IN ADDITION TO GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTION THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

- MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.
- B. MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE ARE/ ON SITE. EQUIPMENT AND MATERIALS WILL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUSTPANS. MOPS, RACS, GLOVES, COGGLES, KITTY LITTER, SAND, SAWDUST, AND PLASTIC OR METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE.
- C. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.
- D. THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE.
- E. SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE.
- F. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM RECURRING AND HOW TO GLEANUP THE SPILL IF IT RECURS. A DESCRIPTION OF THE SPILL, IT'S CAUSE AND THE CLEANUP MEASURES WILL BE INCLUDED.
- G. THE SITE SUPERINTENDENT RESPONSIBLE FOR DAY-TO-DAY SITE OPERATIONS WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR.

THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST THROUGHOUT THE CONSTRUCTION PERIOD. DUST CONTROL METHODS SHALL INCLUDE, BUT NOT LIMITED TO SPRINKLING WATER ON EXPOSED AREAS, COVERING COADED DUMP TRUCKS LEAVING THE SITE, AND TEMPORARY MULCHING, DUST CONTROL MEASURES SHALL BE UTILIZED SO AS TO PREVENT THE MIGRATION OF DUST FROM THE SITE TO ABUTTING AREAS.



REVISED PER CITY TRG COMMENTS

DESCRIP TION

SCALE: NTS Seacoast Division DR CK

BOARD MEMBER

Civil Engineer: ndscape Architects

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

SITE DEVELOPMENT PLANS

TAX MAP 221, LOTS 158 & 159

EROSION CONTROL NOTES

10 FARMINGTON ROAD

ROCHESTER, NEW HAMPSHIRE

COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

I 170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fox (603) 431-0910

APRIL 27, 2021

47424.00 DR DKE FB CK CRR CADFILE 47424-00 - EC NOTES C - 09

Copyright 2021 ©Thomas F. Moran, Inc. 170 Commerce Way, Suite 102, Portsmouth, N.H. 03801

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoeve without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



CONSTRUCTION SEQUENCE NOTES

- NSTALL STABILIZED CONSTRUCTION ENTRANCE.

 CUT AND CLEAR TREES WITHIN AREA OF DISTURBANCE UNLESS OTHERWISE NOTED.

 ALL AREAS SHALL BE STABLIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE
 CONSTRUCT TEMPORARY AND PERMANENT EROSION CONTROL FACILITIES PRIOR TO ANY EARTH MOVING
 DEPERATION.
- PPERATION. PONDS AND SWALES SHALL BE INSTALLED EARLY ON IN THE CONSTRUCTION SEQUENCE (BEFORE ROUGH
- OPERATIONS AND SWALES SHALL BE INSTALLED EARLY ON IN THE CONSTRUCTION SEQUENCE (BEFORE ROUGH GRADOING THE STIRE OR PHASED WORK AREA. ALL SLOPES SHALL BE STABILIZED IMMEDIATELY AFTER GRADING. ALL DISTURBED AREAS SHALL BE STABILIZED IN CHER THAN 72 HOURS AFTER CONSTRUCTION ACTIVITY. CEASES IN EXPENDING HER PROPERTY (EASES ON A PORTION OF OR THE ENTIRE SITE, AND WILL NOT RESUME WITHIN 21 DAYS, THE AREA SHALL BE STABILIZED.

 AN AREA SHALL BE CONSIDERED STABILIZED IN:

 A) BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED:

 B) A MINIMUM OF 85% VEGETATED GROWIN HAS BEEN ESTABLISHED;

 C) A MINIMUM OF 85% VEGETATED GROWIN HAS BEEN ESTABLISHED;

 C) A MINIMUM OF 85% VEGETATED GROWIN FROM PROPERTY INSTALLED, OR

 D) EROSSION CONTROL BLANKETS HAVE BEEN PROPERTY INSTALLED.

 C. CONSTRUCT CLUIVERTS, DETENTION BASINS AND TREATMENT SWALES, PLACE HEADWALLS, RIP-RAP AND OTHER DRAINAGE FACILITIES ACCORDING TO PLAN. THE CONTRACTOR SHALL STABILIZE ALL DITCHES, SWALES, AND PORSING PROPERTY INSTALLED.

 INSTALL ALL UNDERCROUND UTILITIES.

- THE STATE OF THE S
- AFTER STORM EVENTS.

 5. COMPLETE PERMANENT SEEDING AND LANDSCAPING.

 6. REMOVE TEMPORARY EROSION CONTROL MEASURES DNCE ALL AREAS ARE STABILIZED WITH A SUITABLE STAND OF GRASS, PAYEMENT OR COMPACTED GRAVELS.

 6. LOT DISTURBANCE, OTHER THAN THAT SHOWN ON THE APPROVED PLANS, SHALL NOT COMMENCE UNTIL AFTER THE GOLDWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE.

*REFER TO THE STORM WATER MANAGEMENT PLAN FOR EROSION CONTROL MEASURES AND SPECIFIC INFORMATION

GENERAL NOTES

STOCKPILE NOTES

- DEATHS STOCKPILES A MINIMUM OF 50 FEET AWAY FROM CONCENTRATED FLOWS OF STORMWATER, DRAINAGE COURSES AND INLETS.

 PROTECT ALL STOCKPILES FROM STORMWATER RUN—ON USING TEMPORARY PERIMETER MEASURES SUCH AS DINEFSHOOKS, BETRUS, SANDBAGS OR OTHER APPROVED PRACTICES.

 STOCKPILES SHOULD BE SURROUNDED BY SEDIMENT BARRIERS, SUCH AS SILT ENDEC OR SILT SOCK, TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONTINES OF THE STOCKPILES.

 MPLEMENT WIND EROSION CONTROL PRACTICES AS APPROPRIATE ON ALL STOCKPILED MATERIAL.

 PLACE BAGGED MATERIALS ON PALLETS AND UNDER COVER.

 NACTIVE STOCKPILES.
- - INACTIVE SOIL STOCKPILES SHOULD BE COVERED WITH ANCHORED TARPS OR PROTECTED WITH
- INACTIVE SOIL STOCKPILES 9HOULD BE COVERED WITH ANCHORED TARPS OR PROTECTED WITH SOIL STABLIZATION MEASURES (TEMPORARY SEED AND MULCIN OR OTHER TEMPORARY PERIMETER SEDIMENT BARRIERS AT ALL TIMES. AND TEMPORARY PERIMETER SEDIMENT BARRIERS AT ALL TIMES. INACTIVE STOCKPILES OF CONCRETE RUBBLE, ACORECONTE MADERALS AND OTHER SMILLAR MATERALS SHOULD BE PROTECTED WITH TEMPORARY SEDIMENT PERIMETER SARRIERS AT ALL STOCK PLANT THE SHOULD SEDIMENT BARRIERS AND CONTROL OF THE SHOULD SHOULD SEDIMENT BARRIERS PRIOR TO THE ONSET OF PRECIPITATION. PERIMETERS BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMDANT HE DEDUCENT WAND REMOVALD FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMDANT HE DEDUCENT WAND REMOVALD OF MATERIALS FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIERS SHOULD BE INSPECTED AT THE END OF EACH WORKING DAY.
- b. WHEN A STORM EVENT IS PREDICTED, STOCKPILES SHOULD BE PROTECTED WITH AN ANCHORED

CONSTRUCTION FENCE TO BE "VISUAL BARRIER FENCE" AS MANUFACTURED BY EXXON CHEMICAL COMPANY ATLANTA, CA; "KONTROL SAFETY FENCE" AS MANUFACTURED BY MIRAFI, CHARLOTTE, N.C. OR APPROVED EQUAL.

6' O.C. (TYP.)

WINTER CONSTRUCTION

- WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED AS SUCH THAT NO MORE THAN 1 ACRE OF THE
- 1. WINITER EXLAVATION AND EXPERIENCES SHALL BE COMMITCHED AS SUCH THAN NO MORE THAN I ACRE. OF THE STEEL IS MITTING STREAM, STATE AND THE STATE AS T

EROSION CONTROL NOTES

DURING CONSTRUCTION AND THEREAFTER, EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED AS NOTED:

- INSTALLATION OF SILTATION FENCES AND OTHER FROSION CONTROL MEASURES SALE IC BE INPLEMENTED AS NOT
 THE START OF SITE WORK IN ANY CAPEN AREA. PREFABRICATED SILTATION FENCES SHALL BE (OMPLETED PRIOR TO
 THE START OF SITE WORK IN ANY CAPEN AREA. PREFABRICATED SILTATION FENCES SHALL BE INSTALLED
 ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

 SILTATION FENCES AND OTHER EROSION CONTROL MEASURES SHALL BE KEPT CLEAN DURING CONSTRUCTION
 AND REMOVED WHEN ALL SLOPES HAVE A VECETATIVE COVER OF GREATER HAM BSX. EROSION CONTROL
 MEASURES SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EVERY RANFALL.

 EXISTING VECETATION IS TO REMAIN UNDISTURBED WHEREVER POSSIBLE.

 IEMPORARY WATER DIVERSIONS MUST BE USED AS NECESSARY UNTIL AREAS ARE STABLIZED.

 IF AREA OF LAND EXPOSED AND THE THE OF EXPOSURE SHALL BE MINIMIZED. ALL DISTURBED AREAS SHALL
 BE STRABILIZED WITHIN 72 HOURS AFTER FINAL GRADING.
- ALL DISTURBED AREAS SHALL HAVE A MINIMUM OF 4" OF LOAM. ACCEPTABLE SEED MIXES ARE AS FOLLOWS:

PARK SEED MIX (NHDOT TYPE 44) MIN. 135 LBS/ACRE:
33% CREEPING RED FESCUE (MIN. 45 LBS/ACRE)
42% PERENNAL RYEGRASS (MIN. 35 LBS/ACRE)
43% REDTOP (MIN. 5 LBS/ACRE)

TEMPORARY LAWN MIX: (MIN. 47 LBS/ACRE) 100% ANNUAL RYE

SLOPE SEED (WP) (NHDOT TYPE 45) MIX 3.1 OR GREATER SLOPES (MIN. 105 LBS/ACRE):

38% CREEPING RED FESCUE (MIN. 40 LBS/ACRE)

32% FERENMAL RYGGRASS (MIN. 35 LBS/ACRE)

5% REDTOP (MIN. 5 LBS/ACRE)

5% BIRDSOTO TIEFFOIL (MIN. 5 LBS/ACRE)

3% LONCE-LEAF COREOPSIS (MIN. 3 LBS/ACRE)

3% DAYED BUTERFLY WEED (MIN. 3 LBS/ACRE)

3% BLACKFLOS SUSAN (MIN. 3 LBS/ACRE)

3% WILD LUPINE (MIN. 3 LBS/ACRE)

SLOPE SEED (NHDOT TYPE 44) MIX 3:1 OR GREATER SLÓPES (MIN. 90 LBS/ACRE):
44% CREEPING RED FESCUE (MIN. 40 LBS/ACRE)
44% CREEPING RED FESCUE (MIN. 35 LBS/ACRE)
6% REDTOP (MIN. 5 LBS/ACRE)
6% BIROSFOOT TREFOIL (MIN. 5 LBS/ACRE)
6% BIROSFOOT TREFOIL (MIN. 5 LBS/ACRE)

A PLACING LOAM ON SITE

a. ALL SUBGRADE ELEVATIONS SHOULD BE UNIFORMLY GRADED TO RECEIVE LOAM AND SHALL BE INSPECTED AND APPROVED BY THE GENERAL CONTRACTOR PRIOR TO PLACEMENT OF LOAM.

b. PLACE LOAM TO FORM A MINIMUM DEPTH OF 4" WHEN ROLLED, UNLESS OTHERWISE INDICATED.

c. ALL DEPRESSIONS EXPOSED DURING THE ROULING SHALL BE FILLED WITH ADDITIONAL LOAM.

SEED BED PREPARATION ATTENDED THE REPARKED FOR SEEDING, THE AREAS TO BE SEEDED SHALL BE LOOSENED ATTER FINISH ROQUING AND JUST BEFORE SEEDING, THE AREAS TO BE SEEDED SHALL BE LOOSENED TO PROVIDE A ROUGH, FIRM BUT FINELY PULVERIZED SEEDING. THE INTENT IS A TEXTURE CAPABLE OF RETAINING WATER, SEED AND FERTILEZED THE TO GERMINATE. SEED SHALL BE APPLIED TO THE CONDITIONED SEEDING NOT MORE THAN 48 HOURS AFTER THE SEEDING HOUSE PREPARED.

LIME AND FERTILIZER SHALL BE INCORPORATED INTO THE SOIL PRIOR TO OR AT THE TIME OF AT THE TIME OF SEEDING. A MINIMUM OF 2 TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 500 LBS. PER ACRE OF 600-20-20 FERTILIZER SHALL DE APPLIED. SEEDING PRACTICES SHALL COMPLY WITH LOCAL USDA SOIL CONSERVATION SERVICES RECOMMENDATIONS.

HAY MUCH OR WITE MATTING SHALL BE USED WHERE INDICATED ON THE PLANS. A MINIMUM OF 1.5 TONS OF MULCH SHALL BE ANCHORED IN PLACE WHERE RECESSARY. WITE MATTING SHALL BE LAD IN THE DIRECTION OF RUNOFF FLOW AND APPLIED IN ACCORDANCE WITH

MAINING SHALL BE LIDD IN THE DIRECTION OF RUNDER FLOW AND APPLIED IN ACCORDANCE WITH MANUFACTURES'S INSTRUCTIONS.

PERMANENT OR TEXT STRUCTIONS MUST BE IN PLACE FERDER THE GROWING SEASON ENDS. WHEN SEEDED AREAS ARE MOT MILCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO SHALY OCTOBER. WHEN SEEDED AREAS ARE MOT MILCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 15 TO SEPTEMBER 15, NO SOUTHED HAVE ANALL BE LEFT EXPOSED DURING WINTER MONTHS. WATER SHALL BE USED FOR DUST CORTROL IN APPROPRIATE AREAS.

ALL EROSION OUTRICLS SHALL BE INSPECTION WEREN'X HAD AFTER EVERY MALF—INCH OF RANFALL.

OUTLET PROTECTION APRON LIFT STRAPS - DANDY BAG® II STANDARD FARRIC IS MONOFILAMENT ALLOWS FOR EASY REMOVAL OF CONTENTS

HEADWALL OR CURB CUT

HEADWALL OR CURB CUT

MINIMUM OUTLET APRON DIMENSIONS (SEE NOTE #1)

(<u>)_____</u>

HW#1 9' 3'

INSTALLATION

L=SEE TABLE

TYPE I GEOTEXTILE

% OF WEIGHT SMALLER
THAN THE GIVEN SIZE SIZE OF STONE (INCHES)
100 4.50 TO 6.00

INSTALLATION
INSTALLATION
IF USING OPTIONAL OIL ABSORBENTS: PLACE
ABSORBENT PILLOW IN UNIT. STAND THE GRATE ON
END, MOVE THE TOP LIFTING STRAPS OUT OF THE
WAY AND PLACE THE GRATE INTO THE DANDY BAG II
SO THAT THE GRATE IS BELOW THE TOP STRAPS AND
ABOVE THE LOWER STRAPS. HOLDING THE LIFTING
DEVICES, INSERT THE GRATE INTO THE INLET.

MAINTENANCE

MAIN TENANCE

MAINTENANCE REMOVE ALL ACCUMULATED SEDIMENT
AND DEBRIS FROM MCINITY OF UNIT AFTER EACH
STORM EVENT. AFTER EACH STORM EVENT AND AT
REGULAR INTERVALS, LOOK INTO THE DANDY BAG II, IF
THE CONTAINMENT AREA IS MORE THAN 1/3 FULL OF
SEDIMENT, THE UNIT MUST BE EMPTED. TO EMPTY
UNIT, LET THE UNIT OUT OF THE INLET USING THE
LIFTING STRAPS AND REMOVE THE GRATE. IF USING
OPTIONAL DIC ABSORBENTS; REPLACE ABSORBENT
WHEN NEAR SATURATION.



COMPOST FILLED SILT SOCK (12"-18" TYP.) FLOW - WORK AREA TOP OF GROUND -SILT SOCK

NOTES

- SILT SOCK SHALL BE FILTREXXm SILTSOXXm OR APPROVED EQUIVALENT.
 SEE SPECIFICATIONS FOR SOCK SIZE AND COMPOST FILL SIZE AND COMPOST FILL
 REQUIREMENTS.

 3. SILT SOCK SHALL BE
 INSPECTED PERBODICALLY AND
 AFTER ALL STORM EVENTS, AN
 REPAIR OR REPLACEMENT
 SHALL BE PERFORMED AS
 NEPDER
- NEEDED.
 4. COMPOST MATERIAL SHALL BE



DR CK

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

BEGIN AT THE TOP OF BLANKET INSTALLATION AREA BY ANCHORING BLANKET IN A 6" DEEP TRENCH, BACKFILL AND COMPACT TRENCH AFTER STAPLING. ROLL THE BLANKET DOWN THE SWALE IN THE DIRECTION OF THE WATER FLOW.
THE EDGES OF BLANKETS MUST BE STAPLED WITH APPROX. 4 INCH OVERLAP WHERE 2 OR MORE STRIP WIDTHS ARE

REQUIRED.

N. WHEN BLANKETS MUST BE SPLICED DOWN THE SWALE, PLACE BLANKET END OVER END WITH 6 INCH (MIN.) OVERLAP AND ANCHOR DOWN SLOPE BLANKET IN A 6 INCH DEEP TRENCH.

BLANKET SHALL BE NORTH AMERICAN GEREN SC-150 OR APPROVED EQUAL.

BLANKET SLOPE PROTECTION

NOT TO SCALE

-CREST LENGTH (FT) 6 x DRAINAGE AREA (ACRES)

SEDIMENT TRAP - ISOMETRIC VIEW

BACKFILL AND COMPACT TRENCH AFTER INSTALLATION

4" OVERLAP (MIN.)

SECTION A-A

DIMENSIONS.

2. 3,600 CF OF BASIN STORAGE IS REQUIRED FOR EVERY ACRE OF CONTRIBUTING DRAINAGE AREA. SEDIMENT TRAP NOT TO SCALE

DIKE, IF NECESSARY, TO DIVERT FLOW INTO TRAP

NOTES

SITE DEVELOPMENT PLANS TAX MAP 221, LOTS 158 & 159

DETAILS

10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

SCALE: NTS

NOTES

BOARD MEMBER

APRIL 27, 2021




| 170 Commerce Way, Suite 102 Portsmouth, NH 03B01 kone (603) 431-2222 Fox (603) 431-0910 www.tfmoron.com

-STAPLE 12" ON CENTER

47424.00 DR DKE FB
CK CRR CADFILE 47424-00 - DETAILS

C-10



TEMPORARY CONSTRUCTION FENCE

All rights reserved. These plans and materials may not be copied

plan is not effective unless signed by a duly authorized officer of




FILER CLOTH — WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE SURFACE.
WATER — ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED
ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5: SLOPE WILL BE PERMITTED.
MAINTENANCE — THE ENTRANCE SHALL BE MAINTAINES IN A CORDITION WHICH WILL PREVENT TRACKING OR
FLOWING OF SEDIMEN ONTO PUBLIC PRIORITS—OF—WAY. THIS WAY REQUIRE PREVIOUS TOP DESINES WITH
ADDITIONAL STONE AS CONDITIONS DEBMAD AND REPARA MAD/OR CLANOUT OF ANY MESSURES USED TO TRANF
ENTRY TO STONE AS CONDITIONS OF THE STONE OF TRACKED ONTO PUBLIC RIGHTS—OF—WAY MUST BE
SERMOYED MINERALITY SPILED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS—OF—WAY MUST BE


SCUMMENT: ALL SCUMENT STEELS DIVERTED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC
MINISTER - WESTER SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC
MINISTER - WESTER WESTER OF SCUIRED IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND
WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DIVICE.

5. PERIODIC INSPECTION AND NEEDED MANTEMANCE STALL BE PROVIDED AFTER EACH RAIN STORM EVENT.

STABILIZED CONSTRUCTION ENTRANCE



REVISED PER NHOES ACT REM REVISED NHDES ACT NOTES STONE CHECK DAM REVISED PER CITY TRG COMMENTS REVISED PER CITY TRG COMMENTS REV. DATE DESCRIPTION



8/24/2021

6/25/2021

REV. DATE

REVISED PER NHDES AOT RFM

REVISED NHDES AOT NOTES
REVISED PER CITY TRG COMMENTS
REVISED PER CITY TRG COMMENTS

DESCRIPTION

Fax (603) 431-0910

47424.00 DR DKE FB

DKE CRR

Oct 07, 2021 - 5.02pm

CONSTRUCTION SPECIFICATIONS

BACKFILL MATERIAL AROUND THE END SECTION MAY BE THE SAME AS THE MATERIAL AROUND THE PIPE, PLACE A FEW INCHES OF BACKFILL MATERIAL IN THE TRENCH OR DITCH WHERE THE END SECTION MILL BE PLACED. COMPACT AND CONTOUR THIS BEDDING MATERIAL TO GENERALLY MATCH THE END SECTION, EXCAVATE AN AREA IN THE BEDDING WHERE TOE TROUGH WILL SEAT SO THAT THE END SECTION, WILL BE LEVEL WITH THE BOTTOM OF THE TRENCH OR DITCH IN THE FINISHED INSTALLATION.

PLACE END SECTION OF PIPE:

OPEN THE END SECTION COLLAR AND SEAT IT OVER THE TWO PIPE CONNECTIONS. ONCE THE END SECTION SECTION SECTION MAKE SURE THAT THE INVERT OF THE END SECTION MATCHES THE INVERT OF THE PIPE AND THAT THE END SECTION IS LEVEL WITH THE PIPE AND THAT THE END SECTION SECTION IS LEVEL WITH THE TRENCH OR DITCH SITTOM.

SCOURE THE END SECTION:
SUP THE STAINLESS STEEL ROD THROUGH THE PRE-DRILLED HOLES AT THE TOP OF THE COLLAR.
THE ROD SHOULD BE BETWEEN THE CROWNS OF THE TWO PIPE CONNECTIONS. PLACE A WASHER
ON EITHER END OF THE ROD. PLACE A NUT ON EITHER END OF THE ROD AND TIGHTEN WITH A

TO PREVENT WASHOUTS FROM HICH VELOCITY FLOW, IT IS RECOMMENDED THAT THE TROUGH BE SECURED WITH CONCRETE. POUR CONCRETE IN THE TROUGH UP TO THE LEVEL OF THE TRENCH OR DITCH BOTTOM AND ALONG THE ENTIRE LENGTH OF THE TROUGH.

FLARED END SECTION

8" PRECAST SLAB SECTION =

5" MINIMUM W THICKNESS (8" IF UNREINF THEORY

PIPE TO MANHOLE JOINT TO BE SEALED WITH NON-SHRINK MORTAR

SECTION A-A

30" NEW HAMPSHIRE STANDARD MANHOLE CAST IRON FRAME AND COVER H-20 LOADING SET

TOP VIEW SIDE VIEW

| | DIMENSIONS, INCHES (mm) | | | | | |
|--------------------|-------------------------|------------|----------|------------|--------------|------------|
| PIPE DIAMETER | PART NO. | A, ±1 (25) | B MAX | H, ±1 (25) | L, ±1/2 (13) | W, ±2 (50) |
| 12", 15" (300,375) | 1210 NP | 6.5 (165) | 10 (254) | 6.5 (165) | 25 (635) | 29 (735) |
| 18" (450) | 1810 NP | 7.5 (190) | 15 (380) | 6.5 (168) | 32 (812) | 35 (890) |
| 24" (600) | 2410 NP | 7.5 (190) | 18 (450) | 6.5 (165) | 36 (900) | 45 (1140) |
| 30" (750) | 3010 NP | 10.5 (266) | NA | 7.0 (178) | 53 (1346) | 68 (1725) |
| 36" (900) | 3610 NP | 10.5 (266) | NA | 7.0 (178) | 53 (1346) | 68 (1725) |

39 1/4 PLAN VIEW

31-3/4"

39 1/4"

SECTION A-A

ELEV 270.3'±

1 1/2" RAILS 1 1/2" RAILING

IN GROUND

COVER

SEWER

OR 'DRAIN' AS APPROPRIATE

CAST IRON COVER MIN. WEIGHT 265 LBS. NEENAH R-1743 OR EQUAL

COVER

FRAME AND GRATE

BRICK RISERS (IF REQUIRED) SEE STRUCTURE DETAILS

FINISH GRADE FINISH GRADE ON FULL BED OF MORTAR AND SEALED WITH MORTAR ACCEPTABLE.) TEE REQUIRED IN EACH CATCH BASIN JOINTS W/ BITUMINOUS SEAL NOT TO SCALE NOTE: ALL PRECAST SECTIONS SHALL CONFORM TO ASTM C-478

ADJUST TO GRADE WITH PRECAST CONCRETE PAVERS OR CONCRETE ADJUSTMENT RINGS SEAL JOINTS IN ACCORDANCE W/NHDOT STANDARDS 4'-10" (MIN) NOTES MANHOLE FRAME & COVER: SHALL BE PAMREX CLASS D400, HINGED, OR APPROVED FOLIAL BY THE CITY ENGINEED

- APPROVED EQUAL BY THE CITY ENGINEER,
 MANHOLE TO BE STAMPED TO SAY "STORM",
 COVERS AND FRAMES TO BE COATED BLACK,
 MANHOLES SHALL MEET NHEOT SPECIFICATIONS.
 ALL COMPONENTS SHALL BE DESIGNED FOR HS-ZO LOADING
 REINFORCINO SHALL COMPONENTO AND HS OR ASTM 1497 & ASTM A615,


CATCH BASIN NOT TO SCALE ECCENTRIC CONE (FOR USE IN CURBED AREAS)

DRAIN MANHOLE

TRENCH

BOARD MEMBER

FOR SEWER, WATER AND DRAIN LINES.



| UTILITY | MINIMUM | PIPE COVER |
|---------------------|-------------|---------------|
| | PAVED AREAS | UNPAVED AREAS |
| SANITARY SEWER MAIN | 6' | 4' |
| STORM DRAIN | 3' | 3' |
| WATER MAIN | 5' | 5' |

NOTE: ALL PRECAST SECTIONS SHALL CONFORM TO ASTM C-478 DROP OVER DRAIN MANHOLE

NOT TO SCALE

48" MINIMUM

SAWCUT_ (TYP.)

MANHOLE FRAME & COVER HEAVY DUTY NOT TO SCALE

1-3/4"

NOT TO SCALE

FRAME & GRATE

ENE EN TO

PLAN VIEW

SINGLE GRATE


23-11/16" 23-3/16" 2-5/16" 1/2"

3/8 21 3/16

SECTION A-A



PLAN VIEW



SECTION B-B

NOTES

1. FRAME AVAILABLE IN 8" OR 4" HEIGHTS.
2. FREE OPEN AREA = 2.55 S.F.
3. USS 3-FLANGE FRAME IF INSTALLED
ADJACENT TO GRANTE CUBB.
4. USE NEEWAH FOUNDRY R-3570-A GRATE &
FRAME OR APPROVED EQUAL.

UNDERDRAIN FLUSHING PORT NOT TO SCALE

| | | | _ | |
|------|-----------|-------------------------------|-----|-----|
| | | | | |
| 4 | 8/24/2021 | REVISED PER NHDES AOT RFMI | HEG | CRR |
| 3 | 6/25/2021 | REVISED NHDES AOT NOTES | HEG | CRR |
| 2 | 6/18/2021 | REVISED PER CITY TRG COMMENTS | HEG | CHR |
| 1 | 5/27/2021 | REVISED PER CITY TRG COMMENTS | DKE | CRR |
| REV. | DATE | DESCRIPTION | DR | CK |

SITE DEVELOPMENT PLANS

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

TAX MAP 221, LOTS 158 & 159

DETAILS

10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC


SCALE, NTS APRIL 27, 2021



Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmpran.com

NOT TO SCALE

47424.00 DR DKE FB
CK CRR CADFILE 47424-00 - DETAILS C-12



CONCRETE HEADWALL



ADJUST TO GRADE WITH PRECAST CONCRETE PAVERS OR CONCRETE ADJUST TO GRADE WITH PRECAST CONCRETE PAVERS OR CONCRETE ADJUSTMENT JNV=266.10* ---> **→** NV.=261.27 INV 261.27

GROUVE OF THE JOINT SHALL
CONTAIN ONE LINE OF
CIRCUMFERENTIAL REINFORCEMENT
EQUAL TO 0.12 SQ. IN. PER L.F.
PIPE TO MANHOLE JOINT TO BE
SEALED WITH NON-SHRINK
MORTAR FLUSH WITH STRUCTURE

FLOW

OUTLET CONTROL STRUCTURE #18

plan is not effective unless signed by a duly authorized officer ones F. Moran, Inc.

OUTLET CONTROL STRUCTURE #13

FRAME AND GRATE

 \Longrightarrow

U INV 261.05

STORMTECH PRODUCT SPECIFICATIONS

- GENERAL
 STORMTECH CHAMBERS ARE DESIGNED TO
 CONTROL STORMWATER RUNOFF, AS A
 SUBSURFACE RETENTION SYSTEM, STORMTECH
 CHAMBERS RETAIN AND ALLOW EFFECTIVE
 INFILTRATION OF WATER INTO THE SOIL. AS A
 SUBSURFACE DETENTION SYSTEM, STORMTECH
 CHAMBERS DETAIN AND ALLOW FOR THE METERED
 STORME STORMERS AND ALLOW FOR THE METERED FLOW OF WATER TO AN OUTFALL.
- CHAMBER PARAMETERS
 THE CHAMBER SHALL BE INJECTION MOLDED OF
 POLYPROPYLEN RESIN TO BE INHERENTLY
 RESISTANT TO ENVIRONMENTAL STREESS CRACKING
 (ESCR), AND TO MAINTAIN ADEQUATE STIFFNESS
 THROUGH HIGHER TEMPERATURES EXPERIENCED
 DURING INSTALLATION AND SERVICE.
- THE NOMINAL CHAMBER DIMENSIONS OF THE STORMTECH SC-310 SHALL BE 18.0 INCHES TALL, 34.0 INCHES WIDE AND 90.7 INCHES LONG.
- 2.3 THE CHAMBER SHALL HAVE A CONTINUOUSLY CURVED SECTION PROFILE.
- 2.4 THE CHAMBER SHALL BE OPEN-BOTTOMED.
- 2.5 THE CHAMBER SHALL INCORPORATE AN OVERLAPPING CORRUGATION JOINT SYSTEM TO ALLOW CHAMBER ROMS OF ALMOST ANY LENGTH TO BE GREATED. THE OVERLAPPING CORRUGATION JOINT SYSTEM SHALL BE EFFECTIVE WHILE ALLOWING A CHAMBER TO BE TRIMMED TO SHORTEN ITS OVERALL LENGTH.
- THE NOMINAL STORAGE VOLUME OF A JOINED STORMTECH SC-310 CHAMBER SHALL BE 31.0 CUBIC FEET PER CHAMBER HAVEN INSTALLED PER STORMTECH'S TYPICAL DETAILS (INCLUDES THE VOLUME OF CRUSHED ANGULAR STONE WITH AN ASSUMED 40X POROSITY). THIS EQUATES A STORAGE VOLUME PER UNIT AREA OF BED OF 1.3 FT/FT?
- THE CHAMBER SHALL HAVE FORTY—EIGHT ORIFICES PENETRATING THE SIDEWALLS TO ALLOW FOR LATERAL CONVEYANCE OF WATER.
- 2.8 THE CHAMBER SHALL HAVE TWO ORIFICES NEAR ITS TOP TO ALLOW FOR EQUALIZATION OF AIR PRESSURE BETWEEN ITS INTERIOR AND EXTERIOR.
- THE CHAMBER SHALL HAVE BOTH OF ITS ENDS OPEN TO ALLOW FOR UNIMPEDED HYDRAULIC FLOWS AND VISUAL INSPECTIONS DOWN A ROW'S ENTIRE LENGTH.


- 2.10 THE CHAMBER SHALL HAVE 14 CORRUGATIONS.
- 2.11 THE CHAMBER SHALL HAVE A CIRCULAR, INDENIED, FLAT SURFACE ON THE TOP OF THE CHAMBER FOR AN OPTIONAL 4-INCH INSPECTION PORT OR CLEAN-OUT.
- 2.12 THE CHAMBER SHALL BE ANALYZED AND DESIGNED USING AASHTO METHODS FOR THERMOPLASTIC COLVERTS CONTINEED IN THE LEFT DERIDGE DESIGN SPECIFICATIONS, 2ND EDITION, INCLUDING INTERIM SPECIFICATIONS, 2ND EDITION, INCLUDING INTERIM SPECIFICATIONS THROUGH 2001. DESIGN LIVE LOAD SHALL DESIGN EARTH AND LIVE LOADS AS APPROPRIATE FOR THE MINIMUM TO MAXIMUM SPECIFIED DEPTH OF FILL.
- 2.13 THE CHAMBER SHALL BE MANUFACTURED IN AN ISO 9001: 2000 CERTIFIED FACILITY.
- 3.0 END CAP PARAMETERS
 3.1 THE END CAP SHALL BE INJECTION MOLDED OF POLYPROPYLENE RESIN TO BE INFERENTLY RESISTANT TO ENMRONMENTAL STRESS CRACKING, AND TO MAINTAIN ABOUGH ESTERNESS THROUGH HIGHER TEMPRATURES EXPRENDED DURING INSTALLATION AND SERVICE.
- 3.2 THE END CAP SHALL BE DESIGNED TO FIT INTO ANY CORRUGATION OF A CHAMBER, WHICH ALLOWS: CAPPING A CHAMBER THAT HAS ITS LENGTH TRIMMED; SEGMENTING ROWS INTO STORAGE BASINS OF VARIOUS LENGTHS.
- 3.3 THE END CAP SHALL HAVE SAW GUIDES TO ALLOW EASY CUTTING FOR VARIOUS DIAMETERS OF PIPE THAT MAY BE USED TO INLET THE SYSTEM.
- 3.4 THE END CAP SHALL HAVE EXCESS STRUCTURAL ADEQUACIES TO ALLOW CUTTING AN ORIFICE OF ANY SIZE AT ANY INVERT ELEVATION.
- 3.5 THE PRIMARY FACE OF AN END CAP SHALL BE CURVED OUTWARD TO RESIST HORIZONTAL LOADS GENERATED NEAR THE EDGES OF BEDS.
- 3.6 THE END CAP SHALL BE MANUFACTURED IN AN ISO 9001: 2000 CERTIFIED FACILITY.

STORMTECH GENERAL NOTES

- STORMTECH LLC ("STORMTECH") REQUIRES INSTALLING CONTRACTORS TO USE AND UNDERSTAND STORMTECH'S LATEST INSTALLATION INSTRUCTIONS PRIOR TO BEGINNING SYSTEM INSTALLATION.
- PRIOR TO BEGINNING SYSTEM INSTALLATION.

 2. OUR TECHNICAL SERVICES DEPARTMENT OFFERS INSTALLATION CONSULTATIONS TO INSTALLING CONTRACTORS. CONTACT OUR TECHNICAL SERVICES REPRESENTATIVE AT LEAST 30 DAYS PRIOR TO SYSTEM INSTALLATION TO ARRANGE A PRE-INSTALLATION CONSULTATION. OUR REPRESENTATIVES CAN THEN ANSWER QUESTIONS OR ADDRESS COMMENTS ON THE STORMITCH CHAMBER SYSTEM AND INFORM THE INSTALLING CONTRACTOR OF THE MINIMUM INSTALLATION REQUIREMENTS BEFORE BEGINNING THE SYSTEM'S CONSTRUCTION. CALL 1888 892 2694 TO SPEAK TO A TECHNICAL SERVICE REPRESENTATIVE OR VISIT WWW.STORMILE CH.CUM TO RECEIVE A COPY OF OUR INSTALLATION. INSTRUCTIONS.
- 3. STORMTECH'S REQUIREMENTS FOR SYSTEMS WITH . STORNIECH'S REQUIREMENTS FOR SYSTEMS WITH PAYMENT DESIGN (ASPHALT, CONCRETE PAYERS, ETC.): MINIMUM COVER IS 18 INCHES NOT INCLUDING PAYMENTI. MAXIMUM COVER IS 98 INCHES INCLUDING PAYMENTI. FOR INSTALLATIONS THAT DO NOT INCLUDE PAYMENT, WHERE RUTTING FROM VEHICLES MAXIMUM COCCUP, MINIMUM REQUIRED COVER IS 24 INCHES, MAXIMUM COVER IS 98 INCHES.
- 4. THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE DESIGN ENGINEER.
- 5. AASHTO M288 CLASS 2 NON-WOVEN GEDTEXTILE (FILTER FABRIC) MUST BE USED AS INDICATED IN THE PROJECT PLANS.

- 6. STONE PLACEMENT BETWEEN CHAMBERS ROWS AND AROUND PERIMETER MUST FOLLOW INSTRUCTIONS AS INDICATED IN THE MOST CURRENT VERSION OF STORMECH'S INSTALLATION INSTRUCTIONS.
 - 7. BACKFILLING OVER THE CHAMBERS MUST FOLLOW REQUIREMENTS AS INDICATED IN THE MOST CURRENT VERSION OF STORMTECH'S INSTALLATION INSTRUCTIONS.
 - 8. THE CONTRACTOR MUST REFER TO STORMTECH'S INSTALLATION INSTRUCTIONS FOR A TABLE OF ACCEPTABLE VEHICLE LOADS AT VARIOUS DEPTHS OF COVER, THIS INFORMATION IS ALSO AVAILABLE AT STORMTECH'S WEBSITE: WWW.STORMTLCH.COM. THE CONTRACTOR IS RESPONSIBLE FOR REVENTING VEHICLES THAT EXCEED STORMTECH'S REQUIREMENTS FROM TRAVELING ACROSS OR PARKING OVER THE STORMWATER SYSTEM. TEMPORARY FENCING, WARNING TAPE AND APPROPRIATELY LOCATED SIGNS ARE COMMONLY USED TO PREVENT UNAUTHORIZED VEHICLES FROM ENTERING SENSITIVE CONSTRUCTION AREAS.
 - 9. THE CONTRACTOR MUST APPLY EROSION AND SEDIMENT CONTROL MEASURES TO PROTECT THE STORMWATER SYSTEM DURING ALL PHASES OF SITE CONSTRUCTION PER LOCAL CODES AND DESIGN ENGINEER'S SPECIFICATIONS.
 - 10. STORMTECH PRODUCT WARRANTY IS LIMITED. SEE CURRENT PRODUCT WARRANTY FOR DETAILS. TO ACQUIRE A COPY CALL STORMTECH AT 1 888 892 2594 OR VISIT WWW.STOPMTECH.COM.



NOTES
1. THE FILTER MEDIA SHALL CONSIST OF ONE OF THE FOLLOWING MIXTURES VOLUME:

A. 50% TO 55% BY VOLUME SAND THAT IS CERTIFIED BY ITS PRODUCER AS METING THE

REQUIREMENTS FOR ASTIM G-33 CONCRETE SOME THAT IS CONTINUED BY ITS PRODUCER AS METING THE

REQUIREMENTS FOR ASTIM G-33 CONCRETE SOME THAT IS CONTINUED BY ITS PRODUCE OF THE SAME OF THE OWNER OF LOAMY SAND

(PERSONNEL METING SHEED FOR SAND THE MANUFER 20 SIEVE AND 20% TO 30% BY

PASSING THE NUMBER 200 SIEVE AND SAND THE NUMBER 200 SIEVE, WITH 70 TO 80% BY VOLUME

LOAMY COARSE SAND USED IN THE MIXTURE MEETING THE FOLLOWING SIEVE ANALYSIS

SPECIFICATION:

(1) FROM 85 TO 100 PERCENT BY WEIGHT SHALL PASS THE NUMBER 10 SIEVE.

(1) FROM 85 TO 100 PERCENT BY WEIGHT SHALL PASS THE NUMBER 10 SIEVE.

SPECIFICATION:

(1) FROM 85 TO 100 PERCENT BY WIGHT SHALL PASS THE NUMBER 10 SIEVE:

(2) FROM 70 TO 100 PERCENT BY WIGHT SHALL PASS THE NUMBER 20 SIEVE:

(3) FROM 15 TO 40 PERCENT BY WIGHT SHALL PASS THE NUMBER 20 SIEVE:

(4) FROM 8 TO 15 PERCENT BY WIGHT SHALL PASS THE NUMBER 20 SIEVE:

(4) FROM 8 TO 15 PERCENT BY WIGHT SHALL PASS THE NUMBER 20 SIEVE:

(4) FROM 8 TO 15 PERCENT BY WIGHT SHALL PASS THE NUMBER 200 SIEVE:

2. THE INSTALLED CHAMBER SYSTEM SHALL PROVIDE THE LOUD FACTIONS SPECIFIED IN THE ABSHTO LIFE

BRIDGE DESIGN SPECIFICATIONS SECTION 12.12 FOR EARTH AND LIVE LOADS WITH CONSIDERATION FOR

BIRDET SHALL CONFORM TO THE REQUIREMENTS OF ASTIM F24.18 "STANDARD

SPECIFICATION FOR POLYPROPLIEME (PP.) CORRUCATED WALL STORMWARE COLLECTION CHAMBERS", OR

ASTIM F292.2 "J'STANDARD SPECIFICATION FOR POLYETHYLENE (PE) CORRUCATED WALL STORMWATER

COLLECTION CHAMBERS".

COLLECTION CHAMBERS."

SC-310 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS."

| | STORMTECH SC-310 | SS#3 | SS#4 |
|---|-------------------------|-----------|----------|
| | CHAMBERS PER ROW | 7 | SEE PLAN |
| | NO. OF CHAMBER ROWS | 30 | SEE PLAN |
| | TOTAL CHAMBERS | 210 | 142 |
| | TOTAL END CAPS | 60 | 34 |
| | LENGTH | 53.04 | SEE PLAN |
| | WIDTH | 101.50 | SEE PLAN |
| | SYSTEM VOLUME | 12,666 CF | 8,979 CF |
| | MIN. PAVEMENT ELEVATION | 268.1± | 267.7± |
| Ģ | TOP OF STONE | 266.60 | 266.39 |
| F | TOP OF CHAMBER | 266.10 | 265.89 |
| E | BOTTOM OF CHAMBER | 264.77 | 264.55 |
| D | BOTTOM OF STONE | 264.27 | 264.05 |
| С | BOTTOM OF FILTER MEDIA | 262.27 | 262.05 |

| BOTTOM OF CRUSHED STONE | 260.77 | 260.55 | ESHWT | 263.2± | 262.7±

STORMTECH SC-310 CHAMBER SYSTEM TYPICAL CROSS SECTION

NOT TO SCALE

| MATERIAL LOCATION | DESCRIPTION | AASHTO M43 DESIGNATION ₍₁₎ | COMPACTION/DENSITY REQUIREMENT |
|--|--|--|---|
| ID IL MATERIA TOR LAYER O STARTS FROM THE TOP OF THE C LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISH GRADE ABOVE. NOTE THAT PAVEMENT SUB-BASE MAY BE PART OF THIS LAYER. | ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS. | N/A | PREPARE PER ENGINEER'S PLANS, PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS. |
| C FILL MATERIAL FOR LAYER C STARTS FROM THE TOP OF THE EMBEDMENT STONE (B LAYER) TO 18" ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUB-BASE MAY BE A PART OF THIS LAYER. | GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, < 35% FINES. MOST PAVEMENT SUB-BASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER. | AASHTO M431 (1) 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10 | BEGIN COMPACTION AFTER 12" OF MATERIAL, OVER THE CHAMBERS IS REACHED, COMPACT ADDITIONAL LAVERS IN 6" LIFST TO A MIN. 95% STANDARD PROCTOR DENSITY (p). ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs. DYNAMIC FORCE NOT TO EXCEED 20,000 lbs. |
| B EMBEDMENT STONE SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE (A LAYER) TO THE C LAYER ABOVE. | CLEAN, CRUSHED, ANGULAR STONE, NOMINAL SIZE DISTRIBUTION BETWEEN 3/4 - 2 INCH | AASHTO M43 (1) 3, 357, 4, 467, 5, 56, 57 | NO COMPACTION REQUIRED. |
| A FOUNDATION STONE BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER. | CLEAN, CRUSHED, ANGULAR STONE, NOMINAL SIZE DISTRIBUTION BETWEEN 3/4 - 2 INCH | AASHTO M43 (1) 3, 357, 4, 467, 5, 56, 57 | PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE(2)(3). |

- PLEASE NOTE:

 1. THE LISTED ASHITO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR, FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO MA3) STONE".

 2. AS AN ALTERNATE TO PROCTOR TESTING AND FIELD DENSITY MEASUREMENTS ON OPEN GRADED STONE, STORMIECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION AMATERIALS WHEN PLACED AND COMPACTION IN 9' MAN) LITTS USING TWO FULL COVERAGES WITH AN APPROPRIATE COMPACTOR.

 3. WHERE INFILITATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOC CONDITIONS. A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRACGING WITHOUT COMPACTION REQUIREMENTS.

(D) 0 商 AASHTO M288 CLASS 2 NON-WOVEN GEOTEXTILE

- 1. THE INSTALLER SHALL NOT ALLOW ANY VEHICULAR OR CONSTRUCTION EQUIPMENT TRAVEL TO OCCUR ACCOSS THE PROPOSED RECHARGE BASIN AREA AT ANY TIME EXCEPT DURING EXCAVATION OF TOPSOIL, SUESOIL AND OTHER MATERIALS NOT SUITABLE FOR SEED BOTTOM CONDITIONS.
- CAUTION SHOULD BE EXERCISED DURING SITE PREPARATION TO AVOID COMPACTION OF THE INFILTRATIVE SURFACE.

DRAIN MANHOLE

2 LAYERS OF AASHTO M288 CLASS 1 WOVEN GEOTEXTILE BETWEEN FOUNDATION STONE AND

SCHEDULE FOR INSPECTION AND MAINTENANCE AFTER CONSTRUCTION: STREET SWEEPING -STREET SWEEPING EFFORTS SHALL BE CONDUCTED AT LEAST ONCE A MONTH OUTSIDE OF WINTER MONTHS. -SAND SWEPT FROM THE ROADWAYS AND PARKING LOTS WILL BE REMOVED TO AN APPROVED OFF-SITE LOCATION.

THE OWNER IS RESPONSIBLE FOR THE MAINTENANCE AND OPERATION OF THE PROPOSED STORMWATER COLLECTION SYSTEM INCLUDING ROUTINE INSPECTION, CLEANING AND MAINTENANCE OF MANHOLES, DEEP SUMP HOODED CATCH BASINS, CLEAN OUTS, UNDERGROUND DETENTION SYSTEMS AND REGULAR STREET SWEEPING.

DEEP SUMP CATCH BASINS & LEACHING CATCH RASINS
-INLETS SHOULD BE CLEARED ANNUALLY AND INSPECTED SEMI-ANNUALLY.
-ALL SEDIMENTS, FLORITABLES, AND HYDROCARBONS SHOULD BE PROPERLY HANDLED AND DISPOSED OF, IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL GUIDELINES AND REGULATIONS.

6" PERFORATED HDPE


UNDERGROUND DETENTION SYSTEMS (STORMTECH ISOLATOR SC-740 CHAMBER OR EQUAL)

-ISOLATOR ROWS AND PIPE HEADERS SHALL BE INSPECTED IMMEDIATELY AFTER COMPLETION OF THE SITE'S CONSTRUCTION. THE NORMAL INSPECTION SCHEDULE AFTER CONSTRUCTION FOR ISOLATOR ROWS IS SEMI-ANNIAL LIMIT. AN UNDERSTANDING OF THE SITE'S CHARACTERISTICS IS DEVELOPED. PIPE HEADERS SHOULD BE INSPECTED QUARTERY AFTER CONSTRUCTION.
--INSPECTION OF THE ISOLATOR ROW SHALL INVOLVE A VISUAL CHECK USING EITHER THE INSPECTION PORTS OR AN ACCESS MANHOLE.
--IF UPON VISUAL INSPECTION OF THE ISOLATOR ROW, IT IS FOUND THAT SEDIMENT HAS ACCUMULATED TO AN AVERAGE DEPTH EXCEEDING 3 INCHES, CLEANOUT IS REQUIRED.
--CLEANOLT OF SEDIMENT WITHIN THE PIPE HEADER IS REQUIRED WHEN THE SEDIMENT YOUNGE HAS REDUCED HE STORAGE AREA BY 25% OR THE DEPTH OF SEDIMENT HAS REACHED APPROXIMATELY 25% OF THE DAMATER OF THE STRUCTURE.
--CLEANOLT OF THE ACCUMULATED MATERIAL IN THE PIPE HEADER SHOULD BE ACCOMPUSHED BY VACUUM PUMPING, CLEANOUT SHOULD BE PERFORMED DURING DRY WEATHER AND CARE SHOULD BE TAKEN TO AVOID FLUSHING SEDIMENTS OUT ##**UPON THE CONTINUATED MATERIAL IN THE PIPE HEADER SHOULD BE ACCOMPUSHED BY VACUUM PUMPING, CLEANOUT SHOULD BE PERFORMED DURING DRY WEATHER AND CARE SHOULD BE TAKEN TO AVOID FLUSHING SEDIMENTS OUT ##**UPON THE CHAMBER ROWS.

A SITE MAINTENANCE LOG WILL BE KEPT. THIS LOG WILL RECORD THE DATES WHEN MAINTENANCE TASKS WERE COMPLETED, THE PERSON WHO COMPLETED THE TASK, AND ANY OBSERVATIONS OF MAINTENANCE TASKS WERE COMPLETED, THE PERSON WHO COMPLETED THE TASK, AND ANY OBSERVATIONS OF MAINTENANCE TASKS WERE COMPLETED, THE PERSON WHO COMPLETED THE TASK, AND ANY OBSERVATIONS OF MAINTENANCE TASKS WERE COMPLETED, THE PERSON WHO COMPLETED THE TASK, AND ANY OBSERVATIONS OF

SUBSURFACE DETENTION SYSTEM OPERATION AND MAINTENANCE PLAN

BOARD MEMBER



INSPECTION PORT DETAIL



BOARD MEMBER

SITE DEVELOPMENT PLANS

APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

TAX MAP 221, LOTS 158 & 159


DETAILS 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD

PREPARED FOR 10 FARMINGTON ROAD, LLC

SCALE: NTS

APRIL 27, 2021

4NO



| | Sead | coas | st Div | isior |
|------|------|------|--------|-------|
| | | L | 7 | 1 |
| 1740 | 4.00 | DR | DKE | FB |

Civil Engineers Structural Engineers Traffic Engineers Land Surveyors

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910

C - 1347424.00 CK CRR CADFILE 47424-00 - DETAILS

Copyright 2021 ©Thomas F. Moran, Inc. 170 Commerce Way, Suite 102, Portsmouth, N.H. 03801 All rights reserved. These plans and materials may not be a duplicated, replicated or otherwise reproduced in any form without the prior written permission of Thomas F. Moran, Inc.

ROW & INLET PROFILE VIEW DETAIL

PLAN VIEW DETAIL

STORMTECH ISOLATORTM ROW

This plan is not effective unless signed by a duly authorized officer of

7 0 CONTACT DIG SAFE 73 BUSINESS HOURS PRIOR TO CONSTRUCTION

STORMTECH ISOLATOR™ ROW

COVER ENTIRE ROW WITH

ORAIN ANHOLE

ACCEPTABLE FILL MATERIALS

12" MIN ID 25" MAX OD PIPE SET 1.5" FROM BOTTOM OF CHAMBER

(24" MAX.)

DRAIN MANHOLE

MDS

对版

NOT TO SCALE

PLAN VIEW DETAIL

STORMTECH SC-310 CHAMBER SYSTEM

SC-310 CHAMBER SC-310 END CAP

2-INCH WASHED CRUSHED ANGULAR STONE BENEATH AND AROUND CHAMBER BED. TO A DEPTH OF 24" UNDER CHAMBER

- PAVEMENT

PAVEMENT SUB-BASE

AASHTO M288 CLASS 2 NON-WOVEN GEOTEXTILE

6" MIN. DEPTH OF 1 - 2-INCH WASHED, CRUSHED, ANGULAR

STONE BACKFILL (NHDOT 304.4)

- COMPACTED FILL

INSPECTION PORT BY DESIGN ENGINEER

COVER ENTIRE ROW WITH ADS GEOSYNTHETICS 601T NON-WOVEN GEOTEXTILE SC-740 - 8' MIN WIDE S' SC-310 - 5' MIN WIDE ST

DRAIN MANHOLE

STORMTECH ISOLATOR

b.o 5,0 b.o

b.c b.o b.o b.o b.o b.o

b.o b.o b.o b.o b.o





FIXTURE "W"



APPROVED BY THE CITY OF ROCHESTER PLANNING BOARD

BOARD MEMBER

SITE DEVELOPMENT PLANS

TAX MAP 221, LOTS 158 & 159 LIGHTING PLAN 10 FARMINGTON ROAD ROCHESTER, NEW HAMPSHIRE COUNTY OF STRAFFORD PREPARED FOR

10 FARMINGTON ROAD, LLC

1'=80' (11'X17') SCALE: 1'-40' (22'X34")

APRIL 27, 2021



Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910


F 47424.00 OR DKE FB - CK CRR CADFILE 47424-00 - LICHTING



HORIZONTAL SCALE 1"=40"

REVISED PER NHDES AOT RFMI
REVISED NHDES AOT NOTES
REVISED PER CITY TRG COMMENTS
REVISED PER CITY TRG COMMENTS
DESCRIPTION 4 8/24/2021 3 6/25/2021 2 6/18/2021 1 5/27/2021





A.F.C.

Decretor
Revision Schedule

Freject Info: Key Collision of Rochester

10 Farmington Road Rochester, NH

Sheet Status:
Linke Release
Issued Far:
One has bee in
JOS NO. 21001
DRAFTED. AVB
ORICIDED JMT
SCALE: 3/32* = 1'-0
Shoot Title:

Sheet Title:

ADDITION PLAN

Sheet Number:

rinted on: 6/15/2021


NEW ADDITION EXISTING BUILDING



PROJECT KEY

DESIGN | BUILD Architectural Document Set-Prepared For Exclusive Use By:

HITCHER
BUILDERS



F.F.C.

Sheet Number: A1.2

Printed on: 6/45/2024

Project Info: Key Collision of

Rochester


10 Farmington Road Rochester, NH

Sheet Status:
Linest Status:
Linest

Part of the state of the state

T3. Projects/21001-Roch Collision/21001 h 100FT

_



DESIGN | BUILD Architectural Document Set-Prepared For Exclusive Use By:

WHITCHER BUILDERS

